

CONSTRUCTION SPECIFICATIONS

MAINTENANCE BLDG. RENOVATIONS

WASHINGTON AQUEDUCT DIVISION WASHINGTON, D.C.

INVITATION NO. DACW31-02-B-0011

CONTRACT NO.

DATE MARCH 25, 2002

PROJECT TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

- 01000 ADMINISTRATIVE REQUIREMENTS
- 01050 JOB CONDITIONS
- 01060 SAFETY
- 01200 WARRANTY REQUIREMENT
- 01330 SUBMITTAL PROCEDURES
- 01420 SOURCES FOR REFERENCE PUBLICATIONS
- 01451 CONTRACTOR QUALITY CONTROL
- 01510 TEMPORARY CONSTRUCTION ITEMS
- 01562 ENVIRONMENTAL PROTECTION
- 01720 AS-BUILT DRAWINGS CADD

DIVISION 02 - SITE WORK

02220 DEMOLITION

DIVISION 09 - FINISHES

09900 PAINTS AND COATINGS

DIVISION 15 - MECHANICAL

- 15080 THERMAL INSULATION FOR MECHANICAL SYSTEMS
- 15400 PLUMBING, GENERAL PURPOSE
- 15569 OIL-FIRED FORCED HOT-WATER HEATING SYSTEM
- 15700 UNITARY HEATING AND COOLING EQUIPMENT
- 15896 CLEANING OF THE AIR DISTRIBUTION SYSTEM
- 15990 TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS

DIVISION 16 - ELECTRICAL

16415 ELECTRICAL WORK, INTERIOR

-- End of Project Table of Contents --

SECTION 01000

ADMINISTRATIVE REQUIREMENTS

PART 1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Title Evidence

Proof of purchase for equipment and/or materials.

Invoice Copies

Proof of rental equipment costs.

Payment Evidence

Proof of full payment.

Photographs

SD-03 Product Data

Cost or Pricing Data

Proof of actual equipment costs.

Equipment Data

An itemized list of serial/model numbers and equipment installed by the Contractor under this contract.

SD-05 Design Data

Progress Schedule; G WA.

A schedule that shows the manner in which the Contractor intends to prosecute the work.

Modified Chart; G WA.

Prepared when changes are authorized that result in contract time extensions.

SD-10 Operations and Maintenance Data

O and M Data

A list of proposed maintenance and instruction manuals that is mainly used for but not limited to customized equipment.

1.2 PROGRESS SCHEDULING AND REPORTING (AUG. 1999)

The Contractor, shall within five days or as otherwise determined by the Contracting Officer, after date of commencement of work, submit for approval a practicable progress schedule showing the manner in which he intends to prosecute the work. Contractor prepared form shall contain the same information as shown on the attached NADB Form 1153 ("Physical Construction Progress Chart" (CENAB-CO-E)

1.3 PAYMENTS TO CONTRACTORS: (NOV 1976)

For payment purposes only, an allowance will be made by the Contracting Officer of 100 percent of the invoiced cost of materials or equipment delivered to the site but not incorporated into the construction, pursuant to the Contract Clause entitled "PAYMENTS UNDER FIXED-PRICE CONSTRUCTION CONTRACTS". The Contracting Officer may also, at his discretion, take into consideration the cost of materials or equipment stored at locations other than the jobsite, when making progress payments under the contract. In order to be eligible for payment, the Contractor must provide satisfactory evidence that he has acquired title to such material or equipment, and that it will be utilized on the work covered by this contract. Further, all items must be properly stored and protected. Earnings will be computed using 100% of invoiced value. (CENAB-CO-E)

1.4 IDENTIFICATION OF EMPLOYEES: (OCT 1983)

Each employee assigned to this project by the Contractor and subcontractors shall be required to display at all times, while on the project site, an approved form of identification provided by the Contractor, as an authorized employee of the Contractor/subcontractor. In addition, on those projects where identification is prescribed and furnished by the Government, it shall be displayed as required and it shall immediately be returned to the Contracting Officer for cancellation upon release of the assigned employee and or completion of project. To obtain a Government issued identification card, each employee of the Contractor working on this project shall be required to complete a "NAB 1603 Request for Identification Card." This card shall be submitted to the Government, who will then schedule the employee to come in and have his or her picture taken for the identification card. (CENAB)

1.5 PURCHASE ORDER: (SEP 1975)

One readable copy of all purchase orders for material and equipment, showing firm names and addresses, and all shipping bills, or memoranda of shipment received regarding such material and equipment, shall be furnished to the appointed Contracting Officer's Representative as soon as issued. Such orders, shipping bills or memoranda shall be so worded or marked that all material and each item, piece or member of equipment can be definitely

identified on the drawings. Where a priority rating is assigned to a contract, this rating, the required delivery date, and the scheduled shipping date shall also be shown on the purchase order. At the option of the Contractor, the copy of the purchase order may or may not indicate the purchase price. (CENAB-CO-E)

- 1.6 EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE (EFARS 52.0231.5000 (OCT 1995))
 - (a) This clause does not apply to terminations. See 52.249-5000, Basis for settlement of proposals and FAR Part 49.
 - (b) Allowable cost for construction and marine plant and equipment in sound workable conditions owned or controlled and furnished by a contractor or subcontractor at any tier shall be based on actual costs data for each piece of equipment or groups of similar serial and services for which the government can determine both ownership and operating costs from the contractor's accounting records. When both ownership and operating costs can not be determined for any piece of equipment or groups of similar serial or series equipment from the contractor's accounting records, costs for that equipment shall be based upon the applicable provisions of EP1110-1-8 Construction Equipment Ownership and Operating Expenses Schedule, Region East. Working conditions shall be considered to be average for determining equipment rates using the schedule unless specified otherwise by the contracting officer. For equipment not included in the schedule, rates for comparable pieces of equipment may be used or a rate may be developed using the formula provided in the schedule. For forward pricing, the schedule in effect at the time of negotiations shall apply. For retroactive pricing, the schedule in effect at the time the work was performed shall apply.
 - (c) Equipment rental costs are allowable, subject to the provisions of FAR 31.105(d) (ii) and Far 31.205-36. Rates for equipment rented from an organization under common control, lease-purchase arrangements, and sale-leaseback arrangements, will be determined using the schedule, except that actual rates will be used for equipment leased from an organization under common control that has an established proactive of leasing the same or similar equipment to unaffiliated leasees.
 - (d) When actual equipment costs are proposed and the total amount of the pricing action exceeds the small purchase threshold, the contracting officer shall request the contractor to submit either certified cost or pricing data, or partial/limited data, as appropriate. The data shall be submitted on Standard Form 1411, Contract Pricing Proposal Cover Sheet. CENAB-CT/SEP 95 (EFARS 52.231-5000)

1.7 REAL PROPERTY EQUIPMENT DATA: (APR 1975)

At or before the time of completion of the contract, the Contractor shall submit to the Contracting Officer a complete itemized list, including serial and model number where applicable, showing the unit retail value of each Contractor furnished item of mechanical, electrical and plumbing equipment installed by the Contractor under this contract. For each of the items which is specified herein to be guaranteed for a specified period

from the date of acceptance thereof, either for beneficial use or final acceptance, whichever is earlier, against defective materials, design, and workmanship, the following information shall be given: the name, address and telephone number of the Subcontractor, Equipment Supplier, or Manufacturer originating the guaranteed item. The list shall be accompanied by a copy of the specific guarantee document for each item which is specified herein to be guaranteed if one had been furnished to the Contractor by the Equipment Supplier or Manufacturer. The Contractor's guarantee to the Government of these items will not be limited by the terms of any manufacturer's guarantee to the Contractor. Baltimore District NADB Form 1019 may be utilized for the itemized listing and will be made available to the Contractor upon request. (CENAB-CO-E)

1.8 O and M DATA: (JUL 1979)

The requirements for furnishing operating and maintenance data and field instruction are specified elsewhere in the specifications. The Contractor shall submit to the Contracting Officer, at a time prior to the 50% project completion time, a list of proposed maintenance and instruction manuals to be furnished the Government and the scheduled dates of all required field instructions to be provided by Contractor furnished personnel or manufacturer's representatives. All maintenance and instruction manuals must be furnished to the Contracting Officer at least 2 weeks prior to the scheduled dates of any required Contractor furnished field instructions or at least one month prior to project completion if no Contractor furnished field instructions are required. (CENAB)

1.9 HOT-WORK PERMIT

A hot-work permit, DA Form 5383-R is attached to the end of this section.

1.10 NEGOTIATED MODIFICATIONS: (OCT 84)

Whenever profit is negotiated as an element of price for any modification to this contract with either prime or subcontractor, a reasonable profit shall be negotiated or determined by using the OCE Weighted Guidelines method outlined in EFARS 15.902. (Sugg. NAB 84-232)

1.11 PHOTOGRAPHS

PHOTOGRAPHIC COVERAGE: (SEP 85) The Contractor shall furnish ten each $8" \times 10"$ (commercial grade color photographs of the project (with negatives) to the Contracting Officer. These photographs shall be taken at systematic intervals during the contract where and when directed by the Contracting Officer. (CENAB-CO)

PART 2 PRODUCTS

NOT APPLICABLE

PART 3 EXECUTION

NOT APPLICABLE

ATTACHMENTS:

NADB Form 1153 ("Physical Construction Progress Chart"

-- End of Section --

MILESTONE DATES 1 . DATE NOTICE TO PROCEED RECEIVED COMPLETION DATE STARTING DATE DATE DATE SUBMITTED FOR APPROVAL
APPROVAL RECOMMENDED
APPROVED PHYSICAL CONSTRUCTION PROGRESS CHART CONTRACT DESCRIPTION PRINCIPAL CONSTRUCTION FEATURE EST, COST DURATION CAL DAYS PROJECT LOCATION CONTRACT NUMBER CONTRACTOR

HOT WOF	RK PERMIT		
1. LOCATION	2. DATE	3. PERMIT NO).
4. TYPE OF WORK	5. START TIME	6. FINISH TIM	E
7.a. NAME OF PERSON RESPONSIBLE FOR HOT-WORK	7.b. SIGNATURE	l	
AT JOB SITE			
PRECAUTIONS BEI	FORE OPERATIONS		
011701/1107		CHECH	
CHECKLIST		YES	NO
8. Fire extinguisher present specific to the hazard and inspec	ted prior to use?		
9. Forced air ventilation?			
10. Fire Watch required?			
11. Confined Space Permit certification?			
12. Lock Out/Tag Out procedures?			
13. Emergency communications available?			
14. Removal/protection of combustibles/flammables? (If yes, n	ote in remarks)		
15. Personnel protective equipment available and used? (Welding shield/goggles, gloves, hearing protection, safety sho	es, respiratory protection)		
16. Fire Blanket			
17. Welding screen required?			
18. Area barricades required and in place?			
19. Are other precautions required? (If yes, note in remarks)			
20. AREA FIRE CAPTAIN'S SIGNATURE		21. DATE/TIM	IE
PRECAUTIONS AF	TER OPERATIONS		
		CHECH	K ONE
CHECKLIST		YES	NO
Are after work conditions safe?			
Are heat producing devices safe if left at site?			
3. Area Fire Chief notified?			
4. AREA FIRE CAPTAIN'S SIGNATURE		5. DATE/TIME	<u> </u>
T. ANEATINE OAI TAIN O GIGNATURE		J. DATE/TIME	•
DEM	ADICO		
REIVI	ARKS		
NOTE: PERMIT VALID ON DAY OF C	PERATION AT ONE LOCAT	TION ONLY	

SECTION 01050

JOB CONDITIONS

PART 1 GENERAL

1.1 LAYOUT OF WORK

LAYOUT OF WORK: (APR 1972) The Contractor shall lay out his work and shall be responsible for all measurements in connection therewith. The Contractor shall furnish, at his own expense, all templates, platforms, equipment, tools and materials and labor as may be required in laying out any part of the work. The Contractor will be held responsible for the execution of the work to such lines and elevations shown on the drawings or indicated by the Contracting Officer. (CENAB)

1.2 PHYSICAL DATA: (APR 1984)

Data and information furnished or referred to below is for the Contractor's information. The Government shall not be responsible for any interpretation or conclusion drawn from the data or information by the Contractor. (CENAB)

1.2.1 Transportation Facilities

WASHINGTON AQUEDUCT DIVISION (WAD), WASHINGTON, D.C.

The principal access route to the Washington Aqueduct is MacArthur Boulevard. Public bus service is provided by the Washington Metropolitan Area Transit Service.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Shut Down Utility Services; G WA.

Prior approval for service/utility interruptions.

Advance Notice

When changes and/or relocations are required.

SD-07 Certificates

Operations Statement

Written proof that the boilers have been properly installed and

are operating satisfactorily in accordance with the manufacturer's instructions.

1.4 UTILITIES

1.4.1 Availability of Utilities Including Lavatory Facilities: (JUN 1980)

It shall be the responsibility of the Contractor to provide all utilities he may require during the entire life of the contract. He shall make his own investigation and determinations as to the availability and adequacy of utilities for his use for construction purposes and domestic consumption. He shall install and maintain all necessary supply lines, connections, piping, and meters if required, but only at such locations and in such manner as approved by the Contracting Officer. Before final acceptance of work under this contract, all temporary supply lines, connections and piping installed by the Contractor shall be removed by him in a manner satisfactory to the Contracting Officer. (CENAB)

- 1.4.2 Interruption of Utilities: (1972)
 - a. No utility services shall be interrupted by the Contractor to make connections, to relocate, or for any purpose without approval of the Contracting Officer.
 - b. Request for permission to shut down utility services shall be submitted in writing to the Contracting Officer not less than 17 days prior to proposed date of interruption. The request shall give the following information:
 - c. Nature of Utility (Gas, L.P. or H.P., Water, Etc.)
 - d. Size of line and location of shutoff.
 - e. Buildings and services affected.
 - f. Hours and date of shutoff.
 - g. Estimated length of time service will be interrupted.
 - h. Services will not be shut off until receipt of approval of the proposed hours and date from the Contracting Officer.
 - i. Shutoffs which will cause interruption of Government work operations as determined by the Contracting Officer shall be accomplished during regular non-work hours or on non-work days of the Using Agency without any additional cost to the Government.
 - j. Operation of valves on water mains will be by Government personnel. Where shutoff of water lines interrupts service to fire hydrants or fire sprinkler systems, the Contractor shall arrange his operations and have sufficient material and personnel available to complete the work without undue delay or to restore service without delay in event of emergency.
 - k. Flow in gas mains which have been shut off shall not be restored

until the Government inspector has determined that all items serviced by the gas line have been shut off. (CENAB)

1.4.3 Alterations to Utilities: (AUG 1968)

Where changes and relocations of utility lines are noted to be performed by others, the Contractor shall give the Contracting Officer in writing advance notice at least thirty days' of the time that the change or relocation is required. In the event that, after the expiration of thirty days after the receipt of such notice by the Contracting Officer, such utility lines have not been changed or relocated and delay is occasioned to the completion of the work under this contract, the Contractor will be entitled to a time extension equal to the period of time lost by the Contractor after the expiration of said thirty day period. Any modification to existing or relocated lines required as a result of the Contractor's method of operation shall be made wholly at the Contractor's expense and no additional time will be allowed for delays incurred by such modifications. (CENAB)

1.5 DISPOSAL OF EXISTING MATERIAL AND EQUIPMENT: (DEC 1975)

All removed, dismantled or demolished material and/or equipment including rubble, scrap and debris not specified or indicated to be Government salvaged, reinstalled under this contract or otherwise retained for disposal on Government land will become the property of the Contractor and shall be promptly removed from the site and disposed of by the Contractor at his own expense and responsibility. (CENAB)

1.6 COMPLIANCE WITH WATER TREATMENT PLANT REGULATIONS: (JUL 1980)

The project site is on U.S. Army Corps of Engineers property and all rules and regulations issued by the Chief, Washington Aqueduct Division covering general safety, security, sanitary requirements, pollution control, traffic regulations, and parking shall be observed by the Contractor. Information regarding these requirements may be obtained by contacting the Contracting Officer, who will provide such information or assist in obtaining same from appropriate authorities. (MEMO)

1.7 MAINTENANCE OF ACCESS: (DEC 1975)

The Contractor shall not block passage through sidewalks, roads, alleys or other entranceways to the building during performance of work under this contract. In addition, the Contractor shall at all times maintain safe and clear passage through interior corridors and doorways to allow minimal disruption of normal activities within the building. No equipment or new materials are to be stored in the building except those items that are necessary for progress of the immediate work. All existing equipment, materials and debris removed during the work that are not to be reinstalled shall be removed daily by the Contractor from the building. (CENAB)

1.8 PROTECTION OF GOVERNMENT PROPERTY AND PERSONNEL: (DEC 1975)

1.8.1 Protection of Equipment

All existing Government owned equipment within the work area shall be protected by the Contractor from damage caused by construction operations. As a minimum, the Contractor shall cover all furniture, equipment and carpets in the work area with dust barriers and protect such items from any damage due to dust, vibration, water, heat or other conditions resulting from construction activities. Existing work damaged by construction operations shall be promptly repaired by the Contractor at his own expense.

1.8.2 Protection of Personnel

The Contractor shall protect occupants of the building by installing safety rails and/or barricades as applicable to prevent injury from unauthorized entry of personnel into work areas. Warning signs shall be erected as necessary to indicate Construction areas or hazardous zones. Work shall proceed in such manner as to prevent the undue spread of dust and flying particles.

1.8.3 Measures to Prevent Damage/Injury

The Contractor shall take such additional measures as may be directed by the Contracting Officer to prevent damage or injury to Government property or personnel. (CENAB)

1.9 ASBESTOS HANDLING AND REMOVAL (FEB 85)

Through site investigations, friable asbestos has not been found, however if asbestos is encountered, its testing, removal and disposal is covered in "CHANGES" clause of the Contract Clauses. (CENAB)

1.10 TIME EXTENSIONS FOR UNUSUALLY SEVERE WEATHER

1.10.1 Procedure for Determination

This provision specifies the procedure for determination of time extensions for unusually severe weather in accordance the contract clause entitled "Default: (Fixed Price Construction)". In order for the Contracting Officer to award a time extension under this clause, the following conditions must be satisfied:

- a. The weather experienced at the project site during the contract period must be found to be unusually severe, that is, more severe than the adverse weather anticipated for the project location during any given month.
- b. The unusually severe weather must actually cause a delay to the completion of the project. The delay must be beyond the control and without the fault or negligence of the contractor.

1.10.2 Anticipated Adverse Weather Delays

The following schedule of monthly anticipated adverse weather delays is based on National Oceanic and Atmospheric Administration (NOAA) or similar data for the project location and will constitute the base line for monthly weather time evaluations. The contractor's progress schedule must reflect these anticipated adverse weather delays in all weather dependent

activities.

MONTHLY ANTICIPATED ADVERSE WEATHER DELAY WORK DAYS BASED ON (5) DAY WORK WEEK

Washington Aqueduct Division (WAD), Washington, D.C.

JAN FEB MAR APR MAY JUN JUL AUG SEP OCT NOV DEC 4 5 6 7 6 6 6 5 2 5 4 3

1.10.3 Impact

Upon acknowledgment of the Notice to Proceed (NTP) and continuing throughout the contract, the contractor will record on the daily CQC report, the occurrence of adverse weather and resultant impact to normally scheduled work. Actual adverse weather delay days must prevent work on critical activities for 50 percent or more of the contractor's scheduled work day. The number of actual adverse weather delay days shall include days impacted by actual adverse weather (even if adverse weather occurred in previous month), be calculated chronologically from the first to the last day of each month, and be recorded as full days. If the number of actual adverse weather delay days exceeds the number of days anticipated in paragraph "Anticipated Adverse Weather Delays", above, the Contracting Officer will convert any qualifying delays to calendar days, giving full consideration for equivalent fair weather work days, and issue a modification in accordance with the contract clause entitled "Default (Fixed Price Construction)".

1.11 WORKING HOURS

WORKING HOURS: (DEC 93) It shall be the Contractors responsibility to obtain the working hours other than the normal five (5) day work week 07:00 am to 3:30 pm. All duct cleaning work in the office areas shall be performed outside normal work hours per Section 15896, CLEANING OF THE AIR DISTRIBUTION SYSTEM.

1.12 MEASUREMENT AND PAYMENT

No separate measurement and payment will be made for the work performed in this Section 01050, JOB CONDITIONS, specified herein; and all costs in connection therewith shall be considered a subsidiary obligation of the Contractor, and shall be included in the overall cost of the work.(CENAB)

PART 2 PRODUCTS

NOT APPLICABLE

PART 3 EXECUTION

NOT APPLICABLE

-- End of Section --

SECTION 01060

SAFETY

PART 1 GENERAL

1.1 APPLICABLE PUBLICATION

The publications listed below form a part of this specification and are referred to in the text by the basic designation only. All interim changes (changes made between publications of new editions) to the U.S. Army Corps of Engineers Safety and Health Requirements Manual, EM 385-1-1, will be posted on the Headquarters Website. The date that it is posted shall become the official effective date of the change and contracts awarded after this date shall require to comply accordingly. The website location where these changes can be found is under the button entitled "Changes to EM", located at: "http://www.hq.usace.army.mil/soh/hqusace_soh.htm".

U.S. ARMY CORPS OF ENGINEERS:

EM 385-1-1

(3 Sep 1996) U.S. Army Corps of Engineers Safety and Health Requirements Manual

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Safety Supervisor; G WA.

A safety supervisor shall be responsible for overall supervision of accident prevention activities.

SD-07 Certificates

Language Certification

It is the Contractors responsibility to ensure that all employees understand the basic English language.

SD-09 Reports

Activity Phase Hazard Analysis Plan; G WA.

The addressing of the activity phase hazard analysis plan for each activity performed in a phase of work.

OSHA Log

A log shall be reported monthly for injuries.

1.3 GENERAL

- The U.S. Army Corps of Engineers Safety and Health Requirements Manual, EM 385-1-1, and all subsequent revisions referred to in the Contract Clause ACCIDENT PREVENTION of this contract, are hereby supplemented as follows:
- a. The Contractor shall designate an employee responsible for overall supervision of accident prevention activities. Such duties shall include: (1) assuring applicable safety requirements are (a) communicated to the workers in a language they understand (reference EM 385-1-1, September 1996, 01.A.04). It is the Contractor's responsibility to ascertain if there are workers on the job who do not speak and/or understand the English language, if such workers are employed by the prime contractor or subcontractors, at any tier, it is the prime contractor's responsibility to insure that all safety programs, signs, and tool box meetings are communicated to the workers in a language they understand, and that a bilingual employee is on site at all time. If the contractor contends that interpreters and/or bilingual signs are not required, language certification must be provided which verifies that all workers (whose native tongue is other than English) have a command of the English language sufficient to understand all direction, training and safety requirements, whether written or oral, and (b) incorporated in work methods, and (2) inspecting the work to ensure that safety measures and instructions are actually applied. The proposed safety supervisor name and qualifications shall be submitted in writing for approval to the Contracting Officer's Representative. This individual must have prior experience as a safety engineer or be able to demonstrate his/her familiarity and understanding of the safety requirements over a prescribed trial period. The safety engineer shall have the authority to act on behalf of the Contractor's general management to take whatever action is necessary to assure compliance with safety requirements. The safety supervisor is required to be on the site when work is being performed.
- b. Prior to commencement of any work at a job site, a preconstruction safety meeting shall be held between the Contractor and the Contracting Officer's Representative to discuss the Contractor's safety program and in particular to review the following submittals:
- (1) Contracts Accident Prevention Plan: An acceptable accident prevention plan, written by the prime Contractor for the specific work and implementing in detail the pertinent requirements of EM 385-1-1, shall be submitted for Government approval.
- (2) Activity Phase Hazard Analysis Plan: Prior to beginning each major phase of work, an activity hazard analysis (phase plan) shall be prepared by the Contractor for that phase of work and submitted to the Contracting Officer's Representative for approval. A phase is defined as an operation involving a type of work presenting hazards not experienced in previous operations or where a new subcontractor or work crew is to perform work. The analysis shall address the hazards for each activity performed in the phase and shall present the procedures and safeguards necessary to eliminate the hazards or reduce the risk to an acceptable level.

- c. Subsequent jobsite safety meetings shall be held as follows:
- (1) A safety meeting shall be held at least once a month for all supervisors on the project to review past activities, to plan ahead for new or changed operations and to establish safe working procedures to anticipated hazards. An outline report of each monthly meeting shall be submitted to the Contracting Officer's Representative.
- (2) At least one safety meeting shall be conducted weekly, or whenever new crews begin work, by the appropriate field supervisors or foremen for all workers. An outline report of the meeting giving date, time, attendance, subjects discussed and who conducted it shall be maintained and copies furnished the designated authority on request.

1.4 ACCIDENTS

Chargeable accidents are to be investigated by both Contractor personnel and the Contracting Officer.

1.4.1 Accident Reporting, ENG FORM 3394

Section 1, Paragraph 01.D, OF EM 385-1-1 and the Contract Clause entitled ACCIDENT PREVENTION are amended as follows: The prime Contractor shall report on Eng Form 3394, supplied by the Contracting Officer, all injuries to his employees or subcontractors that result in lost time and all damage to property and/or equipment in excess of \$2,000 per incident. Verbal notification of such accident shall be made to the Contracting Officer within 24 hours. A written report on the above noted form shall be submitted to the Contracting Officer within 72 hours following such accidents. The written report shall include the following:

- a. A description of the circumstances leading up to the accident, the cause of the accident, and corrective measures taken to prevent recurrence.
- b. A description of the injury and name and location of the medical facility giving examination and treatment.
- c. A statement as to whether or not the employee was permitted to return to work after examination and treatment by the doctor, and if not, an estimate or statement of the number of days lost from work. If there have been days lost from work, state whether or not the employee has been re-examined and declared fit to resume work as of the date of the report.

1.4.2 OSHA Requirements

1.4.2.1 OSHA Log

A copy of the Contractor's OSHA Log of Injuries shall be forwarded monthly to the Contracting Officer.

1.4.2.2 OSHA Inspections

Contractors shall immediately notify the Contracting Officer when an OSHA

Compliance official (Federal or State representative) presents his/her credentials and informs the Contractor that the workplace will be inspected for OSHA compliance. Contractors shall also notify the Contracting Officer upon determination that an exit interview will take place upon completion of the OSHA inspection. (NABSA OCT 05, 1976)

1.5 GOVERNMENT APPROVAL

Submittals shall be in accordance with Section 01330 SUBMITTAL PROCEDURES. All required submittals of items specified in this section shall be for information only, except for those items including, but not limited to, the following which shall be submitted for Government approval:

- a. Written designation of safety representative.
- b. Written project specific accident prevention plan.
- c. Written activity phase hazard analysis plan.

PART 2 PRODUCT NOT APPLICABLE

PART 3 EXECUTION NOT APPLICABLE

-- End of Section --

SECTION 01200

WARRANTY REQUIREMENT

PART 1 GENERAL

1.1 WARRANTY OF CONSTRUCTION

The Contractor shall warranty all materials and workmanship in accordance with Contract Clause (FAR 52.246-21), "WARRANTY OF CONSTRUCTION"

1.2 MANUFACTURER'S WARRANTY:

The Contractor shall provide manufacturer's warranties, when available, on all equipment for one year starting from the day of facility acceptance by the Government. Any warranty offered by the manufacturer for periods greater than one year or required by other sections of the specifications shall also be provided.

1.3 WARRANTY PAYMENT

Warranty work is a subsidiary portion of the contract work, and has a value to the Government of \$5,000. The Contractor will assign a value of that amount in the breakdown for progress payments mentioned in the Contract Clause (FAR 52.232-5) "Payments Under Fixed-Price Construction". If the Contractor fails to respond to warranty items as provided in paragraph CONTRACTOR'S RESPONSE TO WARRANTY SERVICE REQUIREMENTS below, the Government may elect to acquire warranty repairs through other sources and, if so, shall backcharge the Contractor for the cost of such repairs. Such backcharges shall be accomplished under the Contract Clause (FAR 52.243-4) "CHANGES" of the contract through a credit modification(s).

1.4 PERFORMANCE BOND:

The Contractor's Performance Bond will remain effective throughout the construction warranty period and warranty extensions.

1.4.1 Failure to Commence

In the event the Contractor or his designated representative(s) fail to commence and diligently pursue any work required under this clause, and in a manner pursuant to the requirements thereof, the Contracting Officer shall have the right to demand that said work be performed under the Performance Bond by making written notice on the surety. If the surety fails or refuses to perform the obligation it assumed under the Performance Bond, the Contracting Officer shall have the work performed by others, and after completion of the work, may demand reimbursement of any or all expenses incurred by the Government while performing the work, including, but not limited to administrative expenses.

1.5 PRE-WARRANTY CONFERENCE:

Prior to contract completion and at a time designated by the Contracting Officer, the Contractor shall meet with the Contracting Officer to develop

a mutual understanding with respect to the requirements of this specification. Communication procedures for Contractor notification of warranty defects, priorities with respect to the type of defect, reasonable time required for Contractor response, and other details deemed necessary by the Contracting Officer for the execution of the construction warranty shall be reviewed at this meeting. The Contractor shall provide names, addresses, and telephone numbers of all subcontractors, equipment suppliers, or manufacturers with specific designation of their area of responsibilities if they are to be contacted directly on warranty corrections. This point of contact will be located within the local service area of the warranted construction, will be continuously available, and will be responsive to Government inquiry on warranty work action and status. Minutes of the meeting will be prepared by the Government and signed by both, the Contractor and the Contracting Officer. The minutes shall become part of the contract file.

1.6 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-04 Samples

Sample Tags.

To identify the warranty for all Contractor and Government furnished equipment which the Contractor installs.

1.7 ADDITIONAL REQUIREMENTS

1.7.1 Equipment Warranty Identification Tags:

The Contractor shall provide warranty identification tags on all Contractor and Government furnished equipment which he has installed.

1.7.1.1 Format and Size for Tags

The tags shall be similar in format and size to the exhibits provided by this specification, they shall be suitable for interior and exterior locations, resistant to solvents, abrasion, and to fading caused by sunlight, precipitation. etc. These tags shall have a permanent pressure-sensitive adhesive back, and they shall be installed in a position that is easily (or most easily) noticeable. Contractor furnished equipment that has differing warranties on its components will have each component tagged.

1.7.1.2 Sample Tags

Sample tags shall be filled out representative of how the Contractor will complete all other tags. These tags shall be submitted to the Government.

1.7.1.3 Tags for Warranted Equipment:

The tag for this equipment shall be similar to the following. Exact format and size will be as approved.

EQUIPMENT WARRANTY	
CONTRACTOR FURNISHED EQUIPMENT	
MFG: MODEL NO.:	_
 SERIAL NO.: CONTRACT NO.:	_
CONTRACTORS NAME:	
CONTRACTOR WARRANTY EXPIRES:	_
MFG WARRANTY(IES) EXPIRE:	_
EQUIPMENT WARRANTY	
GOVERNMENT FURNISHED EQUIPMENT	
MFG: MODEL NO.:	
 SERIAL NO.:	
DATE EQUIPMENT PLACED IN SERVICE:	
 MFG WARRANTY(IES) EXPIRES:	

1.7.1.4 Execution

The Contractor will complete the required information on each tag and install these tags on the equipment by the time of and as a condition of final acceptance of the equipment. All tags shall be mechanically attached to the equipment as directed by the Contracting Officer.

1.7.1.5 Equipment Warranty Tag Replacement.

The contractor shall provide new tags on repaired or replaced equipment during the warranty period. The tag shall be identical to the original tag, except that the Contractor's warranty expiration date shall be updated to show the correct warranty expiration date.

- 1.8 CONTRACTOR'S RESPONSE TO WARRANTY SERVICE REQUIREMENTS.
- 1.8.1 Availability of Required Parts

Should parts be required to complete the work and the parts are not immediately available the Contractor shall have a maximum of 12 hours after arrival at the job site to provide authorized representative of the installation with firm written plan for emergency alternatives and temporary repairs for Government participation with the Contractor to provide emergency relief until the required parts are available on site for the Contractor to perform permanent warranty repair. The Contractors plan shall include a firm date and time that the required parts shall be available on site to complete the permanent warranty repair.

- PART 2 PRODUCTS NOT APPLICABLE
- PART 3 EXECUTION NOT APPLICABLE
 - -- End of Section --

SECTION 01330

SUBMITTAL PROCEDURES

PART 1 GENERAL

1.1 SUBMITTAL IDENTIFICATION

Submittals required are identified by SD numbers and titles as follows:

- SD-01 Preconstruction Submittals
- SD-02 Shop Drawings
- SD-03 Product Data
- SD-04 Samples
- SD-05 Design Data
- SD-06 Test Reports
- SD-07 Certificates
- SD-08 Manufacturer's Instructions
- SD-09 Manufacturer's Field Reports
- SD-10 Operation and Maintenance Data
- SD-11 Closeout Submittals

1.2 SUBMITTAL CLASSIFICATION

Submittals are classified as follows:

1.2.1 Government Approved

Government approval is required for extensions of design, critical materials, deviations, equipment whose compatibility with the entire system must be checked, and other items as designated by the Contracting Officer. Within the terms of the Contract Clause entitled "Specifications and Drawings for Construction," they are considered to be "shop drawings."

1.2.2 Information Only

All submittals not requiring Government approval will be for information only. They are not considered to be "shop drawings" within the terms of the Contract Clause referred to above. Submittal Register ENG FORM 4288, column labeled "Reviewer", this column is blank and is understood that the reviewer is "WA" (Washington Aqueduct).

1.3 APPROVED SUBMITTALS

The Contracting Officer's approval of submittals shall not be construed as a complete check, but will indicate only that the general method of construction, materials, detailing and other information are satisfactory. Approval will not relieve the Contractor of the responsibility for any error which may exist, as the Contractor under the Contractor Quality Control (CQC) requirements of this contract is responsible for dimensions, the design of adequate connections and details, and the satisfactory construction of all work. After submittals have been approved by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

1.4 DISAPPROVED SUBMITTALS

The Contractor shall make all corrections required by the Contracting Officer and promptly furnish a corrected submittal in the form and number of copies specified for the initial submittal. If the Contractor considers any correction indicated on the submittals to constitute a change to the contract, a notice in accordance with the Contract Clause "Changes" shall be given promptly to the Contracting Officer.

1.5 WITHHOLDING OF PAYMENT

Payment for materials incorporated in the work will not be made if required approvals have not been obtained.

PART 2 PRODUCTS (Not used)

PART 3 EXECUTION

3.1 GENERAL

The Contractor shall make submittals as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work covered in the respective sections. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) System Manager and each item shall be stamped, signed, and dated by the CQC System Manager indicating action taken. Proposed deviations from the contract requirements shall be clearly identified. Submittals shall include items such as: Contractor's, manufacturer's, or fabricator's drawings; descriptive literature including (but not limited to) catalog cuts, diagrams, operating charts or curves; test reports; test cylinders; samples; O&M manuals (including parts list); certifications; warranties; and other such required submittals. Submittals requiring Government approval shall be scheduled and made prior to the acquisition of the material or equipment covered thereby. Samples remaining upon completion of the work shall be picked up and disposed of in accordance with manufacturer's Material Safety Data Sheets (MSDS) and in compliance with existing laws and regulations.

At the end of this section is one set of ENG Form 4288 listing items of equipment and materials for which submittals are required by the specifications; this list may not be all inclusive and additional submittals may be required. The Contractor will also be given the submittal register files, containing the computerized ENG Form 4288 and instructions on the use of the files. These submittal register files will be furnished on a separate diskette. Columns "c" through "f" have been completed by the Government; the Contractor shall complete columns "a" and "g" through "i" and submit the forms (hard copy plus associated electronic file) to the Contracting Officer for approval within 30 calendar days after Notice to Proceed. The Contractor shall keep this diskette up-to-date and shall submit it to the Government together with the monthly payment request. The approved submittal register will become the scheduling document and will be used to control submittals throughout the life of the contract. The submittal register and the progress schedules shall be coordinated.

3.3 SCHEDULING

Submittals covering component items forming a system or items that are interrelated shall be scheduled to be coordinated and submitted concurrently. Certifications to be submitted with the pertinent drawings shall be so scheduled. Adequate time (a minimum of 30 calendar days exclusive of mailing time) shall be allowed and shown on the register for review and approval. No delay damages or time extensions will be allowed for time lost in late submittals.

3.4 TRANSMITTAL FORM (ENG FORM 4025)

The sample transmittal form (ENG Form 4025) attached to this section shall be used for submitting both Government approved and Information Only submittals in accordance with the instructions on the reverse side of this form. A copy of this form will be furnished to the Contractor. The Contractor shall submit a copy of this form with each submittal after properly filling out the form. Special care shall be exercised to ensure proper listing of the specification paragraphs and/or sheet numbers of the contract drawing pertinent to the data submitted for each item.

3.5 SUBMITTAL PROCEDURE

Six (6) copies of submittals shall be made as follows:

3.5.1 Procedures

In the signature block provided on ENG Form 4025 the Contractor certifies that each item has been reviewed in detail and is correct and is in strict conformance with the contract drawings and specifications unless noted otherwise. The accuracy and completeness of submittals is the responsibility of the Contractor. Any costs due to resubmittal of documents caused by inaccuracy, lack of coordination, and/or checking shall be the responsibility of the Contractor. This shall include the handling and review time on the part of the Government. Each variation from the contract

specifications and drawings shall be noted on the form; and, attached to the form, the Contractor shall set forth, in writing, the reason for and description of such variations. If these requirements are not met, the submittal may be returned for corrective action.

3.5.2 Deviations

For submittals which include proposed deviations requested by the Contractor, the column "variation" of ENG Form 4025 shall be checked. The Contractor shall set forth in writing the reason for any deviations and annotate such deviations on the submittal. The Government reserves the right to rescind inadvertent approval of submittals containing unnoted deviations.

3.6 CONTROL OF SUBMITTALS

The Contractor shall carefully control his procurement operations to ensure that each individual submittal is made on or before the Contractor scheduled submittal date shown on the approved "Submittal Register."

3.7 GOVERNMENT APPROVED SUBMITTALS

Upon completion of review of submittals requiring Government approval, the submittals will be identified as having received approval by being so stamped and dated. Four (4) copies of the submittal will be retained by the Contracting Officer and two (2) copies of the submittal will be returned to the Contractor.

3.8 INFORMATION ONLY SUBMITTALS

Normally submittals for information only will not be returned. Approval of the Contracting Officer is not required on information only submittals. The Government reserves the right to require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe.

3.9 STAMPS

Stamps used by the Contractor on the submittal data to certify that the submittal meets contract requirements shall be similar to the following:

CONTRACTOR
 (Firm Name)
 Approved
Approved with corrections as noted on submittal data and/or attached sheets(s).
 TITLE:
DATE:

-- End of Section --

TITLE A					G	CONTRAC	CTOR				•						
-	т	ce Buil	ding HVAC Improvements		V C T		ONTRACTO			ITRACTOR ACTION		APP	ROVING AU	JTHOF	RITY		
A	I T T A L	S P E C S E C T	DESCRIPTION ITEM SUBMITTED	P A R A G # R A P H	L A O S R S I A F / I E C A R I V O W N R	OLIDAUT.	APPROVAL NEEDD	MATERIAL NEEDED	ACT-ON CODE		DATE FWD TO APPR AUTH/ DATE RCD FROM	DATE FWD	DATE RCD FROM OTH	A C T I O N C O D E	DATE OF	MAILED TO CONTR/ DATE RCD FRM APPR	DEMARKO
(a) (I	b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)	(o)	(p)	(q)	(r)
	01	000	SD-01 Preconstruction Submittals														
	_		Title Evidence														
\rightarrow			Invoice Copies														
_			Payment Evidence														
			Photographs	1.11													
_			SD-03 Product Data														
\dashv	_		Cost or Pricing Data	1.6													
\dashv	_			1.7													
+			SD-05 Design Data														
_	_		Progress Schedule	1.2	G WA												
-			Modified Chart		G WA												
			SD-10 Operation and Maintenance														
$-\!\!\!\!+$	_		Data			1	1										
+	+		O and M Data	1.8									 	-			
+	01	050	SD-01 Preconstruction Submittals			1											
+	_		Shut Down Utility Services	1.4.2	G WA	1							-				
+	_		Advance Notice	1.4.3		1							-				
+	_		SD-07 Certificates			1							-				
$-\!\!\!\!+$			Operations Statement														
-+	01	060	SD-01 Preconstruction Submittals														
+	_			1.3	G WA	1							-				
-+			SD-07 Certificates														
-+	-			1.3													
$-\!\!\!\!+$	-		SD-09 Manufacturer's Field														
$-\!\!\!+$	-		Reports			1								-			

TITLE	AND	LOCATIO	N			CONTRAC	TOR				<u> </u>						
Mair	nten	ance Bui	Iding HVAC Improvements		G												
	T R				V C T L		ONTRACTO			ITRACTOR ACTION		APP	ROVING AU	THOF	RITY		
A C T I V I T Y	A N S M I T T A L NO	S P E C S E C T	DESCRIPTION ITEM SUBMITTED	P A R A G # R A P H	S R S I A F / E C A R E I V W R	SUBMIT	APPROVAL NEEDED	MATERIAL NEEDED DY	A C T I O N C O D E		DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD	DATE RCD FROM OTH REVIEWER	A C T I O N C O D E	DATE OF AGTION	MAILED TO CONTR/ DATE RCD FRM APPR	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)	(o)	(p)	(q)	(r)
		01060	Activity Phase Hazard Analysis	1.3	G WA												
		0.000	Plan														
			OSHA Log														
		01200	SD-04 Samples														
			Sample Tags	1.7.1.2													
		01451	SD-01 Preconstruction Submittals														
			CQC Plan	3.2	G WA												
			Phase Notification														
			CQC Mgr Qualification		G WA												
			SD-05 Design Data														
			Notification of Changes	3.2.4													
			Punchlist	3.7.1													
			Minutes	3.3													
			SD-06 Test Reports														
			Tests														
			Documentation	3.8													
			Tests Performed														
			QC Records		G WA												
		01562	SD-01 Preconstruction Submittals														
			Implementation	1.5	G WA												
		01720	SD-02 Shop Drawings														
			Progress Prints		G WA												
			Final Prints		G WA												
			SD-03 Product Data														
			CADD Files														
		02220	SD-03 Product Data														
		102220	13D-03 PTOQUEL Data	1	1	ı	l						<u> </u>				

TITLE AND LOCATION Maintenance Building HVAC Improvements G G				CONTRACTOR													
Maint	_																
	T R		g		V C T L		ONTRACTO			ITRACTOR ACTION		APP	ROVING AU	THOF	RITY		
A C T I V I T Y	ANSMITTAL NO	S P E C S E C T	DESCRIPTION ITEM SUBMITTED	P A R A G R A P H	A O S R S A F / E C A R E I V W R	SUBMIT	APPROVAL NEEDD	MATERIAL NEEDED BY	A C T I O N C O D E		DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR		DATE RCD FROM OTH REVIEWER	A C T I O N C O D E	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR	REMARKO
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)	(o)	(p)	(q)	(r)
		02220	Work Plan		G WA												
		09900	SD-02 Shop Drawings														
			Piping identification	3.7													
			stencil	3.7													
			SD-03 Product Data														
			Coating	2.1	G WA												
			Manufacturer's Technical Data	2.1													
			Sheets														
			SD-04 Samples														
			Color	1.7	G WA												
			SD-08 Manufacturer's Instructions											ļ			
			Application instructions	3.2.1										ļ			
			Mixing	3.4.2													
	_		Manufacturer's Material Safety	1.5.2										<u> </u>			
	_		Data Sheets														
\perp		15080	SD-04 Samples											-			
\perp			Thermal Insulation Materials		G WA									 			
\perp	-	15400	SD-02 Shop Drawings											<u> </u>			<u> </u>
	_		Plumbing System	3.4.1	G WA												
_	\dashv		Electrical Schematics	ļ	G WA	1	ļ										<u> </u>
_			SD-03 Product Data		<u> </u>								 				<u> </u>
-	\dashv		Welding	1.5.1	G WA												<u> </u>
-			Plumbing Fixture Schedule		G WA												
_	\dashv		SD-07 Certificates						_				 				
+	\dashv		Materials and Equipment		G WA												<u> </u>
		15569	SD-02 Shop Drawings	<u> </u>	<u> </u>	l							<u> </u>				

TITLE	AND	LOCATIO	N			CONTRAC	TOR										
			Iding HVAC Improvements		G												
	T R		ionig o p. o . o o		V C T		ONTRACTO			ITRACTOR ACTION		APP	ROVING AU	THOF	RITY		
A C T I V I T Y	ANSMITTAL NO	S P E C S E C T	DESCRIPTION	P A R A G R A P H	A O R S I A / I E C A R E I V W N R		APPROVAL		A C T - O Z C O D E	DATE	DATE FWD TO APPR AUTH/ DATE RCD	DATE FWD	DATE RCD	A C T I O N C O D E	DATE	MAILED TO CONTR/ DATE RCD	
	٥	'	ITEM SUBMITTED	П	IN K	OUDMIT	NEEDED	NEEDED		OF	FROM	TO OTHER	FROM OTH	_	OF	FRM APPR	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(1)	(m)	(n)	(o)	(p)	(q)	(r)
		15569	Heating System		G WA												
		10000		3.2	G WA												
			SD-03 Product Data	·-													
			Manufacturer's Catalog Data		G WA												
			Spare Parts Data		G WA												
			Tests		G WA												
			Rigging Plan		G WA												
			SD-06 Test Reports														
				3.5	G WA												
			Fuel System Tests		G WA												
			SD-07 Certificates														
			Boiler Emissions														
			SD-10 Operation and Maintenance														
			Data														
			Boiler System		G WA												
		15700	SD-02 Shop Drawings														
			Drawings		G WA												
			SD-03 Product Data														
			Unitary Equipment	2.4	G WA												
			Spare Parts Data		G WA												
			Verification of Dimensions	1.5.1													
			Demonstrations	3.4													
			SD-06 Test Reports														
			Refrigerant Tests, Charging, and	3.2	G WA	<u> </u>											
\rightarrow	_		Start-Up			1											
			System Performance Tests	3.3	G WA								<u> </u>				

TITLE A	ND L	OCATIO	N			CONTRAC	CTOR										
	Maintenance Building HVAC Improvements																
	т		ioning		V C T		ONTRACTO			ITRACTOR ACTION		APP	ROVING AU	THOF	RITY		
A N C S T N I I I I I I I I I I I I I I I I I I	A N S M I T T A L	S P E C S E C T	DESCRIPTION ITEM SUBMITTED	P A R A G # R A P H	A O R S A F / E C A R E I W N R	SUBMIT	APPROVAL NEEDED DY	NEEDED BY	A C T I O N C O D E	DATE OF ACTION	CONTR	TO OTHER	FROM OTH	A C T I O N C O D E	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR	REMARKS
(a) (l	b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)	(o)	(p)	(p)	(r)
	1	15700	SD-07 Certificates														
			Unitary Equipment	2.4													
			SD-10 Operation and Maintenance														
			Data .														
			Operation & Maintenance		G WA												
			Manuals														
	1	15896	SD-02 Shop Drawings														
			Work Plan		G WA												
			Access Panels/Doors		G WA												
			SD-03 Product Data														
			Materials		G WA												
	1	15990	SD-02 Shop Drawings														
			TAB Schematic Drawings and	3.3	G WA												
			Report Forms														
			SD-03 Product Data														
				3.2													
			TAB Procedures	3.4.1	G WA												
			SD-06 Test Reports														
			TAB Report	3.4.3	G WA												
			TAB Verification Report	3.4.4	G WA												
			SD-07 Certificates														
			Ductwork Leak Testing														
	\perp		TAB Firm	1.5.1	G WA												
	_		TAB Specialist	1.5.2	G WA												
	1	16415															
			Interior Electrical Equipment		G WA												

		LOCATIO				CONTRAC	CTOR										
Mai	nten	ance Bui	Iding HVAC Improvements		G												
	T R				V C T		ONTRACTO			TRACTOR ACTION		APP	ROVING AU	JTHOF	RITY		
A C T I V I T Y	A N S M I T T A L N O	S P E C S E C T	DESCRIPTION ITEM SUBMITTED	P A R A G # R A P H	S R S A F E C A R E V W R	SUBMIT	APPROVAL NEEDED	MATERIAL NEEDED DY	ACT-OR CODE		DATE FWD TO APPR AUTH/ DATE RCD FROM SONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	A C T I O N C O D E	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)	(j)	(k)	(I)	(m)	(n)	(o)	(p)	(p)	(r)
		16415	SD-03 Product Data														
		10110	Manufacturer's Catalog														
			Material, Equipment Lists		G WA												
			Installation Procedures														
			As-Built Drawings	1.2.6	G WA												
			Onsite Tests		G WA												
			SD-06 Test Reports														
			Field Test Plan		G WA												
			Field Test Reports	3.13	G WA												
			SD-07 Certificates														
			Materials and Equipment	1.4													
													1				

	TRANSMITTAL OF SHOP DRAWINGS, EQUIPMENT DATA, MATERIAL SAMPLES, OR	DUIPMENT DATA, MATERIAL SA	MPLES, OR	DATE			TRANSMITTAL NO.		
	MANUFACTURER'S CERTIFICATES OF (Read instructions on the reverse side prior to initial)	ANUFACTURER'S CERTIFICATES OF COMPLIANCE (Read instructions on the reverse side prior to initiating this form)							
	SECTION I -	SECTION I - REQUEST FOR APPROVAL OF TH	APPROVAL OF THE FOLLOWING ITEMS (This section will be initiated by the contractor)	This section will be	initiated by the cont.	actor)			
10:	999999999999999999999999999999999999999	FROM:		CONTR	CONTRACT NO.		CHECK ONE:		
				-			THIS IS A NEW TRANSMITTAL THIS IS A RESUBMITTAL OF TRANSMITTAL	/ TRANSMITTAL Ubmittal of	
SPECIFICATION (SPECIFICATION SEC. NO. (Cover only one section with each transmital)	PROJECT TITLE AND LOCATION		 					1
ITEM NO.	DESCRIPTION OF ITEM SUBMITTED (Type size, model numberjete.)	BMITTED or/occ.)	MFG OR CONTR.	R. NO.		CONTRACT REFERENCE DOCUMENT	FOR	VARIATION (See	FOR
ė	4		DRAWING UR BROCHURE NO. (See instruction no. 8) E.		S SPEC. PARA. NO.	DRAWING SHEET NO.	USE CODE	instruction No. 6) A.	USE CODE
:		3					1		:
					i i				
			1						
***		: :							
REMÄRKS					l certify that the in detail and are contract drawin	above submitted i correct and in stri gs and specificatio	I certify that the above submitted items have been reviewed in detail and are correct and in strict conformance with the contract drawings and specifications except as other wise stated.	riewed th the wise stated.	
						į			
						NAME AND SIG	NAME AND SIGNATURE OF CONTRACTOR	CTOR	
		SECTION II	SECTION II - APPROVAL ACTION				:		
ENCLOSURES RE	ENCLOSURES RETURNED (List by Item No.)	NAME, TITL	NAME, TITLE AND SIGNATURE OF APPROVING AUTHORITY	ING AUTHORITY			DATE		
ENG FORM 4025, May 91	(25, May 91		EDITION OF AUG 89 IS OBSOLETE.		SHEET OF			(Proponent:	(Proponent: CEMP-CE)

INSTRUCTIONS

- 1. Section I will be initiated by the Contractor in the required number of copies.
- number for identifying each submittal. For new submittals or resubmittals mark the appropriate box; on resubmittals, insert transmittal number of last submission as Each transmittal shall be numbered consecutively in the space provided for "Transmittal No.". This number, in addition to the contract number, will form a serial well as the new submittal number. 2
- 3. The "Item No." will be the same "Item No." as indicated on ENG FORM 4288 for each entry on this form.
- Submittals requiring expeditious handling will be submitted on a separate form.
- Separate transmittal form will be used for submittals under separate sections of the specifications.
- A check shall be placed in the "Variation" column when a submittal is not in accordance with the plans and specifications-also, a written statement to that effect shall be included in the space provided for "Remarks". œ.
- 7. Form is self-transmittal, letter of transmittal is not required.
- When a sample of material or Manufacturer's Certificate of Compliance is transmitted, indicate "Sample" or "Certificate" in column c, Section I. œ.
- addition they will ensure enclosures are indicated and attached to the form prior to return to the contractor. The Contractor will assign action codes as indicated below U.S. Army Corps of Engineers approving authority will assign action codes as indicated below in space provided in Section I, column i to each item submitted. In in Section I, column g, to each item submitted. a;

THE FOLLOWING ACTION CODES ARE GIVEN TO ITEMS SUBMITTED

Disapproved (See attached).	Receipt acknowledged.	Receipt acknowledged, does not comply as noted with contract requirements.	Other (Specify)
:	:	:	:
ш	ш.	ĸ	9
Approved as submitted.	Approved, except as noted on drawings.	Approved, except as noted on drawings. Refer to attached sheet resubmission required.	Will be returned by separate correspondence.
;	1	1	ı
⋖	8	၁	

10. Approval of items does not relieve the contractor from complying with all the requirements of the contract plans and specifications.

SECTION 01420

SOURCES FOR REFERENCE PUBLICATIONS

PART 1 GENERAL

1.1 REFERENCES

Various publications are referenced in other sections of the specifications to establish requirements for the work. These references are identified in each section by document number, date and title. The document number used in the citation is the number assigned by the standards producing organization, (e.g. ASTM B 564 Nickel Alloy Forgings). However, when the standards producing organization has not assigned a number to a document, an identifying number has been assigned for reference purposes.

1.2 ORDERING INFORMATION

The addresses of the standards publishing organizations whose documents are referenced in other sections of these specifications are listed below, and if the source of the publications is different from the address of the sponsoring organization, that information is also provided. Documents listed in the specifications with numbers which were not assigned by the standards producing organization should be ordered from the source by title rather than by number.

ACI INTERNATIONAL (ACI)

P.O. Box 9094

Farmington Hills, MI 48333-9094

Ph: 248-848-3700 Fax: 248-848-3701

Internet: http://www.aci-int.org

AOK 6/00 LOK 6/00

ACOUSTICAL SOCIETY OF AMERICA (ASA)

2 Huntington Quadrangle Melvile, NY 11747-4502

Ph: 516-576-2360 Fax: 516-576-2377 email: asa@aip.org

Internet: http://asa@aip.org

AOK 6/00 LOK 6/00

AGRICULTURAL MARKETING SERVICE (AMS)

Seed Regulatory and Testing Branch USDA, AMS, LS Div.
Room 209, Bldg. 306, BARC-East Beltsville, MD 20705-2325

Ph: 301-504-9430 Fax: 301-504-8098

Internet: http://www.ams.usda.gov/lsg
e-mail: james_p_triplitt@usda.gov

AOK 6/00 LOK 6/00

AIR CONDITIONING AND REFRIGERATION INSTITUTE (ARI)

4301 North Fairfax Dr., Suite 425

ATTN: Pubs Dept.
Arlington, VA 22203
Ph: 703-524-8800
Fax: 703-528-3816
E-mail: ari@ari.org
Internet: www.ari.org

AOK 6/00 LOK 6/00

AIR CONDITIONING CONTRACTORS OF AMERICA (ACCA)

1712 New Hampshire Avenue, NW

Washington, DC 20009 Ph: 202-483-9370 FAX: 202-588-1217

Intrnet: www.acca.org

AOK 6/00 LOK 6/00

AIR DIFFUSION COUNCIL (ADC)

104 So. Michigan Ave., No. 1500

Chicago, IL 60603 Ph: 312-201-0101 Fax: 312-201-0214

Internet: www.flexibleduct.org

AOK 6/00 LOK 6/00

AIR MOVEMENT AND CONTROL ASSOCIATION (AMCA)

30 W. University Dr.

Arlington Heights, IL 60004-1893

Ph: 847-394-0150 Fax: 847-253-0088

Internet: www.amca.org

AOK 6/00 LOK 6/00

ALUMINUM ASSOCIATION (AA)

900 19th Street N.W. Washington, DC 20006

Ph: 202-862-5100 Fax: 202-862-5164

Internet: www.aluminum.org

AOK 6/00 LOK 6/00

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

1827 Walden Ofc. Sq.

Suite 104

Schaumburg, IL 60173-4268

Ph: 847-303-5664 Fax: 847-303-5774

Internet: www.aamanet.org

AOK 6/00 LOK 6/00

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

444 N. Capital St., NW, Suite 249

Washington, DC 20001

Ph: 800-231-3475 202-624-5800 Fax: 800-525-5562 202-624-5806

Internet: www.aashto.org

AOK 6/00 LOK 6/00

NOTE: AASHTO documents with numbers beginning with M or T are available only in Standard Specifications for Transportation Materials and Methods of Sampling and Testing, 1998 @ $$289.00\X$

AMERICAN ASSOCIATION OF TEXTILE CHEMISTS AND COLORISTS (AATCC)

P.O. Box 12215

1 Davis Drive

Research Triangle Park, NC 27709-2215

Ph: 919-549-8141
Fax: 919-549-8933
Internet: aatcc.org

AOK 6/00 LOK 6/00

AMERICAN BEARING MANUFACTURERS ASSOCIATION (AFBMA)

1200 19th Street, NW, Suite 300

Washington, DC 20036-2422

Ph: 202-429-5155
Fax: 202-828-6042
Internet: abma-dc.org

AOK 6/00 LOK 6/00

AMERICAN BOILER MANUFACTURERS ASSOCIATION (ABMA)

950 North Glebe Road, Suite 160 Arlington, Virginia 22203-1824

Ph:703-522-7350
Fax: 703-522-2665
Internet: abma.com

AOK 6/00 LOK 6/00

AMERICAN CONCRETE PIPE ASSOCIATION (ACPA)

222 West Las Colinas Blvd., Suite 641

Irving, TX 75039-5423

Ph: 972-506-7216 Fax: 972-506-7682

Internet: http://www.concrete-pipe.org

e-mail: info@concrete-pipe.org

AOK 6/00 LOK 6/00

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)

1330 Kemper Meadow Dr.

Suite 600

Cincinnati, OH 45240 Ph: 513-742-2020

Fax: 513-742-3355

Internet: www.acgih.org
E-mail: pubs@acgih.org

AOK 6/00 LOK 6/00

AMERICAN FOREST & PAPER ASSOCIATION (AF&PA)

American Wood Council

ATTN: Publications Dept.

1111 Nineteenth St. NW, Suite 800

Washington, DC 20036

Ph: 800-294-2372 202-463-2700

Fax: 202-463-2471

Internet: http://www.afandpa.org

AOK 6/00 LOK 6/00

AMERICAN GAS ASSOCIATION (AGA)

400 N. Capitol St. N.W.Suite 450

Washington, D.C. 20001

Ph: 202-824-7000 Fax: 202-824-7115

Internet: www.aga.org

AOK 6/00 LOK 6/00

AMERICAN GAL ASSOCIATION LABORATORIES (AGAL)

Address Ph:

Fax:

Internet:

AMERICAN GEAR MANUFACTURERS ASSOCIATION (AGMA)

1500 King St., Suite 201 Alexandria, VA 22314-2730

Ph: 703-684-0211 Fax: 703-684-0242

Internet: www.agma.org

AOK 6/00 LOK 6/00

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

One East Wacker Dr., Suite 3100

Chicago, IL 60601-2001

Ph: 312-670-2400

Publications: 800-644-2400

Fax: 312-670-5403

Internet: www.aisc.org

AOK 6/00 LOK 6/00

AMERICAN INSTITUTE OF TIMBER CONSTRUCTION (AITC)

7012 So. Revere Parkway, Suite 140

Englewood, CO 80112 Ph: 303-792-9559

Fax: 303-792-9669

Internet: www.aitc-glulam.org

AOK 6/00 LOK 6/00

AMERICAN IRON AND STEEL INSTITUTE (AISI)

1101 17th St., NW Suite 1300

Washington, DC 20036

Ph: 202-452-7100

AOK 6/00

LOK 6/00

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

11 West 42nd St

New York, NY 10036 Ph: 212-642-4900

Fax: 212-398-0023

Internet: www.ansi.org/

Note: Documents beginning with the letter "S" can be ordered from: Acoustical Society of America P. O. Box 1020 Sweickley, PA 15143-9998 Ph: 412-741-1979 Fax: 412-741-0609 Internet: asa.aip.org AOK 6/00 LOK 6/00 AMERICAN NURSERY AND LANDSCAPE ASSOCIATION (ANLA) 1250 I St., NW, Suite 500 Washington, DC 20005-3922 Ph: 202-789-2900 FAX: 202-789-1893 AOK 6/00 LOK 6/00 AMERICAN PETROLEUM INSTITUTE (API) 1220 L St., NW Washington, DC 20005-4070 Ph: 202-682-8000 Fax: 202-962-4776 Internet: http://www.api.org AOK 6/00 LOK 6/00 AMERICAN RAILWAY ENGINEERING & MAINTENANCE-OF-WAY ASSOCIATION (AREMA) 8201 Corporate Dr., Suite 1125 Landover, MD 20785-2230 Ph: 301-459-3200 Fax: 301-459-8077 Internet: www.arema.org AOK 6/00 LOK 6/00 AMERICAN SOCIETY FOR NONDESTRUCTIVE TESTING (ASNT) 1711 Arlingate Lane P.O. Box 28518 Columbus, OH 43228-0518 Ph: 800-222-2768 Fax: 614-274-6899 Internet: www.asnt.org AOK 6/00

AMERICAN SOCIETY FOR QUALITY (ASQ)

611 East Wisconscin Ave.

LOK 6/00

P.O. Box 3005

Milwaukee, WI 53201-3005

Ph: 800-248-1946 Fax: 414-272-1734

Internet: http://www.asq.org

AOK 6/00 LOK 6/00

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

100 Barr Harbor Drive

West Conshohocken, PA 19428-2959

Ph: 610-832-9585 Fax: 610-832-9555

Internet: www.astm.org

AOK 6/00 LOK 6/00

NOTE: The annual ASTM Book of Standards (66 Vol) is available for \$3500.00. Prices of individual standards vary.

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

1801 Alexander Bell Drive Reston, VA 20190-4400

Ph: 703-295-6300 - 800-548-2723

Fax: 703-295-6222
Internet: www.asce.org
e-mail: marketing@asce.org

AOK 6/00 LOK 6/00

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

1791 Tullie Cir., NE Atlanta, GA 30329

Ph: 800-527-4723 or 404-636-8400

Fax: 404-321-5478

Internet: http://www.ashrae.org

AOK 6/00 LOK 6/00

AMERICAN SOCIETY OF SANITARY ENGINEERING FOR PLUMBING AND SANITARY RESEARCH (ASSE)

901 Canterbury, Suite A Westlake, OH 44145 Ph: 440-835-3040

Fax: 440-835-3488

E-mail: asse@ix.netcom.com
Internet: www.asse-plumbing.org

AOK 6/00

LOK 6/00

AMERICAN WATER WORKS ASSOCIATION (AWWA)

6666 West Quincy Denver, CO 80235

Ph: 800-926-7337 - 303-794-7711

Fax: 303-347-0804

Internet: www.awwa.org

AOK 6/00 LOK 6/00

AMERICAN WELDING SOCIETY (AWS)

550 N.W. LeJeune Road

Miami, FL 33126

Ph: 800-443-9353 - 305-443-9353

Fax: 305-443-7559

Internet: http://www.amweld.org

AOK 6/00 LOK 6/00

AMERICAN WOOD-PRESERVERS' ASSOCIATION (AWPA)

P.O. Box 5690

Grandbury, TX 76049-0690

Ph: 817-326-6300 Fax: 817-326-6306

Internet: http://www.awpa.com

AOK 8/00 LOK 6/00

NOTE: AWPA Book of Standards is published yearly @\$75.00; individual standards may be ordered separately for \$12.00 to \$28.00 each.

APA - THE ENGINEERED WOOD ASSOCIATION (APA)

P.O.Box 11700

Tacoma, WA 98411-0700

Ph: 253-565-6600 Fax: 253-565-7265

Internet: www.apawood.org

AOK 8/00 LOK 6/00

Note: Prices are available only by calling APA

ARCHITECTURAL WOODWORK INSTITUTE (AWI)

1952 Isaac Newton Square West Reston, VA 20190

Ph: 703-733-0600 Fax: 703-733-0584

Internet: www.awinet.org

AOK 8/00 LOK 6/00

ARMY ENVIRONMENTAL CENTER (AEC)

5179 Hoadley Road Aberdeen Roving Ground, MD 21010-5401 Internet: www.aec.army.mil AOK 8/00

ARMY PAMPHLET (DAPAM)

www.usace.army.mil/publications

ASBESTOS CEMENT PIPE PRODUCERS ASSOCIATION (ACPPA)

1745 Jefferson Davis Highway, Suite 406 Arlington, VA 22202

Ph: 703-412-1153 Fax: 703-412-1152

ASME INTERNATIONAL (ASME)

Three Park Avenue

New York, NY 10016-5990

Ph: 212-591-7722 Fax: 212-591-7674

Internet: www.asme.org

AOK 8/00 LOK 6/00

ASPHALT INSTITUTE (AI)

Research Park Dr.

P.O. Box 14052

Lexington, KY 40512-4052

Ph: 606-288-4960 Fax: 606-288-4999

Internet: www.asphaltinstitute.org

AOK 8/00 LOK 6/00

ASSOCIATED AIR BALANCE COUNCIL (AABC)

1518 K St., NW, Suite 503

Washington, DC 20005

Ph: 202-737-0202 Fax: 202-638-4833 Internet: www.aabchq.com

8/00 LOK 6/00

ASSOCIATION FOR THE ADVANCEMENT OF MEDICAL INSTRUMENTATION (AAMI)

1110 N. Globe Rd., Suite 220 Arlington, VA 22201-5762

Ph: 703-525-4890 Fax: 703-525-1424

Internet: www.aami.org

AOK 8/00 LOK 6/00

ASSOCIATION OF EDISON ILLUMINATING COMPANIES (AEIC)

600 No. 18th St.

P.O. Box 2641

Birmingham, AL 35291

Ph: 205-257-2530 Fax: 205-257-2540

Internet: http://www.aeic.org

AOK 8/00 LOK 6/00

ASSOCIATION OF HOME APPLIANCE MANUFACTURERS (AHAM)

1111 19th St. NW., Suite 402

Washington, DC 20036 Ph: 202-872-5955

Fax: 202-872-9354

Internet: http://www.aham.org

AOK 8/00 LOK 6/00

ASSOCIATION OF IRON AND STEEL ENGINEERS (AISE)

Three Gateway Center, Suite 1900

Pittsburg, PA 15222-1004

Ph: 412-281-6323 Fax: 412-281-4657

Internet: http://www.aise.org

AOK 8/00 LOK 6/00

BIFMA INTERNATIONAL (BIFMA)

2680 Horizon Drive SE, Suite A-1

Grand Rapids, MI 49546-7500

Ph: 616-285-3963 Fax: 616-285-3765

Internet: www.bifma.com
E-mail: email@bifma.com

AOK 8/00

LOK 6/00

BIOCYCLE, JOURNAL OF WASTE RECYCLING

BRICK INSTITUTE OF AMERICA (BIA)

11490 Commerce Park Dr., Suite 308

Reston, VA 22091-1525

Ph: 703-620-0010 Fax: 703-620-3928

Internet: www.bia.org

AOK 8/00 LOK 6/00

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

355 Lexington Ave.

17th floor

New York, NY 10017-6603

Ph: 212-297-2100 Fax: 212-370-9047

Internet: www.buildershardware.com

AOK 8/00 LOK 6/00

BUILDING OFFICIALS & CODE ADMINISTRATORS INTERNATIONAL (BOCA)

4051 W. Flossmoor Rd.

Country Club Hills, IL 60478

Ph: 708-799-2300 Fax: 708-799-4981 Internet: www.bocai.org

AOK 8/00 LOK 6/00

BUREAU OF RECLAMATION (BOR)

Denver Federal Center

P.O. Box 25007 Denver, CO 80225 Ph: 303-445-2080

Order from:

National Technical Information

Services (NTIS) 5285 Port Royal Rd.

Springfield, VA 22161

Ph: 703-605-6000 Fax: 703-605-6900 Internet: www.ntis.org

AOK 8/00 LOK 6/00

CALIFORNIA DEPARTMENT OF TRANSPORTATION (CDT)

Publication Distribution Unit 1900 Royal Oaks Dr.

Sacramento, CA 95815

Ph: 916-445-3520 or 916-227-7000 (CA Transportation Lab)

Fax: 916-324-8997

CALIFORNIA REDWOOD ASSOCIATION (CRA)

405 Enfrente Drive., Suite 200

Novato, CA 94949 Ph: 415-382-0662 Fax: 415-382-8531

Internet: www.calredwood.org

AOK 8/00 LOK 6/00

CARPET AND RUG INSTITUTE (CRI)

310 Holiday Ave.

Dalton, GA 30720

P.O. Box 2048

Dalton, GA 30722-2048

Ph: 706-278-0232 Fax: 706-278-8835

Internet: www.carpet-rug.com

AOK 8/00 LOK 6/00

CAST IRON SOIL PIPE INSTITUTE (CISPI)

5959 Shallowford Rd., Suite 419

Chattanooga, TN 37421

Ph: 423-892-0137 Fax: 423-892-0817

Internet: www.cispi.org

AOK 8/00 LOK 6/00

CEILINGS & INTERIOR SYSTEMS CONSTRUCTION ASSOCIATION (CISCA)

1500 Lincoln Highway, Suite 202

St. Charles, IL 60174

Ph: 630-584-1919 Fax: 630-584-2003

Internet: www.cisca.org

AOK 8/00 LOK 6/00

CHLORINE INSTITUTE (CI)

2001 L St., NW Suite 506

Washington, DC 20036

Ph: 202-775-2790 Fax: 202-223-7225 Internet: www.cl2.com

AOK 8/00 LOK 6/00

CODE OF FEDERAL REGULATIONS (CFR)

Order from:

Government Printing Office

Washington, DC 20402 Ph: 202-512-1800 Fax: 202-275-7703

Internet: http://www.gpo.gov

AOK 8/00 LOK 6/00

COMMERCIAL ITEM DESCRIPTIONS (CID)

Order from:

General Services Administration Federal Supply Service Bureau

470 E L'Enfant Plaza, S.W., Suite 8100

Washington, DC 20407 Ph: 202-619-8925

Internet: http://pub.fss.gsa.gov/h1-pub.html

LOK 6/00

COMPRESSED GAS ASSOCIATION (CGA)

1725 Jefferson Davis Highway, Suite 1004

Arlington, VA 22202-4102

Ph: 703-412-0900 Fax: 703-412-0128

Internet: www.cganet.com

e-mail: Customer_Service@cganet.com

AOK 8/00 LOK 6/00

CONCRETE REINFORCING STEEL INSTITUTE (CRSI)

933 N. Plum Grove Rd.

Schaumburg, IL 60173-4758

Ph: 847-517-1200 Fax: 847-517-1206

Internet: www.crsi.org

AOK 8/00 LOK 6/00

CONSUMER PRODUCT SAFETY COMMISSION (CPSC)

4330 East-West Highway

Bethesda, Maryland 20814-4408

Ph: 301-504-0990 Internet: www.cpsc.gov

AOK

LOK 6/00

CONVEYOR EQUIPMENT MANUFACTURERS ASSOCIATION (CEMA)

6724 Lone Oak Blvd.
Naples, Florida 34109
Ph: 941-514-3441
Fax: 941-514-3470

Internet: www.cemanet.org

AOK 8/00 LOK 6/00

COOLING TOWER INSTITUTE (CTI)

530 Wells Fargo Dr., Suite 218, Houston, TX 77090

Ph: 281-583-4087 Fax: 281-537-1721 Internet: www.cti.org

AOK 8/00 LOK 6/00

COPPER DEVELOPMENT ASSOCIATION (CDA)

260 Madison Ave. New York, NY 10016 Ph: 212-251-7200 Fax: 212-251-7234

E-mail: http://www.copper.org

AOK 8/00 LOK 6/00

CORPS OF ENGINEERS (COE)

Order from:

U.S. Army Engineer Waterways Experiment Station

ATTN: Technical Report Distribution Section, Services

Branch, TIC

3909 Halls Ferry Rd.

Vicksburg, MS 39180-6199

Ph: 601-634-2664 Fax: 601-634-2388

Internet: www.usace.army.mil

AOK 8/00 LOK 6/00

NOTE: COE Handbook for Concrete and Cement (Documents w/prefix CRD-C) (1949-present; 2 Vol) free to Government offices; \$10.00 plus \$8.00 per yr for 4 qtrly supplements to others). Individual documents, single copies free. Order from address above.

INTERNATIONAL CODE COUNCIL (ICC)

5203 Leesburg Pike, Suite 708

Falls Church, VA 22041 Ph: 703-931-4533

Fax: 703-379-1546
Internet: www.intlcode.org

AOK 8/00 LOK 6/00

DEPARTMENT OF AGRICULTURE (USDA)

14TH STREET & INDEPENDENCE AVE. S.W.

WASHINGTON, D.C. 20250 Ph: (202) 720-2791

Publications: 301-344-2340

Internet: www.usda.gov

AOK 8/00 LOK 6/00

DEPARTMENT OF COMMERCE (DOC)

Order From:

National Technical Information Service

5285 Port Royal Road Springfield, VA 22161

Ph: 703-605-6000 Fax: 703-605-6900

Internet: http://www.ntis.gov

AOK 8/00 LOK 6/00

DEPARTMENT OF DEFENSE (DOD)

Order from:

National Technical Information Service

5285 Port Royal Road Springfield, VA 22161 Ph: 703-605-6040 FAX: 703-487-4639

AOK 8/00

LOK 6/00

DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT (HUD)

Order from:

HUD User

P.O. Box 6091

Rockville, MD 20849 Ph: 800-245-2691

Fax: 301-519-5767

Internet: www.huduser.org
e-mail: Huduser@aspensys.com

AOK 8/00 LOK 6/00

DEPARTMENT OF STATE (SD)

ATTN: DS/PSP/SEP SA-6, Room 804

Washington, DC 20522-0602

Ph: 703-875-6537

LOK 6/00

DOOR AND ACCESS SYSTEM MANUFACTURERS ASSOCIATION (DASMA)

1300 Sumner Avenue

Cleveland, OH 44115-2851

Ph: 216-241-7333 Fax: 216-241-0105

Internet: www.dasma.com
e-mail: dasma@dasma.com

AOK 8/00 LOK 6/00

DOOR AND HARDWARE INSTITUTE (DHI)

14150 Newbrook Dr.Suite 200 Chantilly, VA 20151-2223

Ph: 703-222-2010

Fax: 703-222-2410

Internet: www.dhi.org

E-mail: techdept@dhi.org

AOK 8/00 LOK 6/00

DUCTILE IRON PIPE RESEARCH ASSOCIATION (DIPRA)

245 Riverchase Parkway East, Suite 0

Birmingham, AL 35244 Ph: 205-402-8700

Fax: 205-402-8730

Internet: www.dipra.org
E-mail: info@dipra.org

AOK 8/00 LOK 6/00

EIFS INDUSTRY MEMBERS ASSOCIATION (EIMA)

3000 Corporate Center Drive, Suite 270

Morrow, GA 30260 Ph: 770-968-7945 Fax: 700-968-5818

Internet: www.eifsfacts.com

AOK 8/00 LOK 6/00

ELECTRONIC INDUSTRIES ALLIANCE (EIA)

2500 Wilson Blvd.

Arlington, VA 22201-3834

Ph: 703-907-7500 Fax: 703-907-7501

Internet: www.eia.org

AOK 8/00 LOK 6/00

ENGINEERING MANUALS (EM)

USACE Publications Depot

Attn: CEIM-SP-D 2803 52nd Avenue

Hyattsville, MD 20781-1102

Ph: 301-394-0081 Fax: 301-394-0084

Internet: www.usace.army.mil

AOK 8/00 LOK 6/00

ENGINEERING PAMPHLETS (EP)

USACE Publications Depot

Attn: CEIM-SP-D 2803 52nd Avenue

Hyattsville, MD 20781-1102

Ph: 301-394-0081 Fax: 301-394-0084

Internet: www.usace.army.mil

AOK 8/00 LOK 6/00

ENGINEERING REGULATIONS (ER)

USACE Publications Depot

Attn: CEIM-SP-D 2803 52nd Avenue

Hyattsville, MD 20781-1102

Ph: 301-394-0081 Fax: 301-394-0084

Internet: www.usace.army.mil

AOK 8/00 LOK 6/00

ELECTRICAL GENERATING SYSTEMS ASSOCIATION (EGSA)

1650 South Dixie Highway, Ste. 500

Boca Raton, FL 33432

Ph: 561-750-5575 Fax: 561-395-8557

Internet: www.egsa.org

AOK 8/00 LOK 6/00

ENVIRONMENTAL PROTECTION AGENCY (EPA)

Ariel Rios Building

1200 Pennsylvania Avenue, N.W.

Washington, DC 20460

Ph: 202-260-2090 FAX: 202-260-6257

Internet: http://www.epa.gov

NOTE: Some documents are available only from: National Technical

Information Services (NTIS)

5285 Port Royal Rd. Springfield, VA 22161

Ph: 800-553-6847 Fax: 703-321-8547 Internet: www.ntis.gov

AOK 8/00 LOK 6/00

EXPANSION JOINT MANUFACTURERS ASSOCIATION (EJMA)

25 N Broadway

Tarrytown, NY 10591 Ph: 914-332-0040 Fax: 914-332-1541

Internet: www.ejma.org

AOK 8/00 LOK 6/00

FACTORY MUTUAL ENGINEERING AND RESEARCH (FM)

500 River Ridge Drive

Norwood, MA 02062 Ph: 781-440-8000

Ph: (Toll-Free): 877-364-6726

Fax: 718-440-8742

Internet: www.fmglobal.com

AOK 8/00 LOK 6/00

FEDERAL AVIATION ADMINISTRATION (FAA)

Order from:

Superintendant of Documents

U. S. Government Printing Office

Washington, DC 20402 Ph: 202-512-1800 Fax: 202-512-1356

Internet: www.gpo.gov
For free documents, order from:
Federal Aviation Administration

Dept. of Transportation

ATTN: General Services Section M-45

400 Seventh St., SW

Washington, DC 20590-0001

Ph: 202-619-8925 Fax: 202-619-8978 Internet: www.faa.gov

AOK 8/00 LOK 6/00

FEDERAL HIGHWAY ADMINISTRATION (FHWA)

Office of Highway Safety (HHS-31)

400 Seventh St., SW

Washington, DC 20590-0001

Ph: 202-366-0411 Fax: 202-366-2249

Internet: www.fhwa.dot.gov

Order from:

Government Printing Office Superintendent of Documents

Washington, DC 20402 Ph: 202-783-3238

AOK 8/00 LOK 6/00

FEDERAL SPECIFICATIONS (FS)

Order from:

General Services Administration Federal Supply Service Bureau 470 L'Enfant Plaza, S.W. Washington, DC 20407

Ph: 202-619-8925 Fax: 202-619-8978

Internet: http://pub.fss.gsa.gov/

FEDERAL STANDARDS (FED-STD)

Order from:

General Services Administration Federal Supply Service Bureau 470 E L'Enfant Plaza, S.W. Washington, DC 20407

Ph: 202-619-8925 Fax: 202-619-8978

Internet: http://pub.fss.gsa.gov/

FORESTRY SUPPLIERS (FSUP)

205 West Rankin St.

P.O. Box 8397

Jackson, MS 39284-8397

Ph: 601-354-3565 Fax: 601-292-0165

Internet: www.forestry-suppliers.com

AOK 8/00 LOK 6/00 FOUNDATION FOR CROSS-CONNECTION CONTROL AND HYDRAULIC RESEARCH (FCCCHR)

University of South California

Kaprielian Hall 200

Los Angeles, CA 90089-2531

Ph: 213-740-2032 Fax: 213-740-8399 Internet: www.usc.edu

AOK 8/00 LOK 6/00

GEOLOGICAL SOCIETY OF AMERICA (GSA)

P.O. Box 9140

Boulder, CO 80301-9140

3300 Penrose Place

Boulder, CO 80301-1806

Ph: 800-447-2020 Fax: 303-447-1133

Internet: www.geosociety.org

AOK 8/00 LOK 6/00

GEOSYNTHETIC INSTITUTE (GSI)

475 Kedron Ave.

Folsom, PA 19033-1208

Ph: 610-522-8440 Fax: 610-522-8441

AOK 8/00 LOK 6/00

GERMANY INSTITUTE FOR STANDARDIZATION (DIN)

BURGGRAFENSTRAÁE 6

POSTFACH 11 07

10787 BERLIN

GERMANY

Internet: www.gsf.de
Ph: 49-30-2601-2260
Fax: 49-30-2601-1231

AOK 8/00 LOK 6/00

Order from a United States publications service.

GLASS ASSOCIATION OF NORTH AMERICA (GANA)

2945 SW Wanamaker Drive, Suite A

Topeka, KS 66614-5321

Ph: 785-271-0208 Fax: 785-271-0166

Internet:www.glasswebsite.com

AOK 8/00

LOK 6/00

GRETAG MACBETH (GM)

Munsell Department 617 Little Britain Road New Windsor, NY 12553-6148

Ph: 800-662-2384 or 914-565-7660

Fax: 914-565-0390

Internet: www.gretagmacbeth.com

AOK 8/00 LOK 6/00

GYPSUM ASSOCIATION (GA)

810 First St. NE, Suite 510

Washington, DC 20002 Ph: 202-289-5440 Fax: 202-289-3707

Internet: www.gypsum.org

AOK 8/00 LOK 6/00

HARDWOOD PLYWOOD & VENEER ASSOCIATION (HPVA)

1825 Michael Faraday Dr.

P.O. Box 2789

Reston, VA 20195-0789

Ph: 703-435-2900 Fax: 703-435-2537

Internet: www.hpva.org

AOK 8/00 LOK 6/00

HEAT EXCHANGE INSTITUTE (HEI)

1300 Sumner Ave

Cleveland, OH 44115-2851

Ph: 216-241-7333 Fax: 216-241-0105

Internet: www.heatexchange.org

email: hei@heatexchange.org

AOK 8/00 LOK 6/00

H.P. WHITE LABORATORY (HPW)

3114 Scarboro Rd. Street, MD 21154

Ph: 410-838-6550 fax: 410-838-2802

Internet: www.hpwhite.com

AOK 8/00 LOK 6/00

HYDRAULIC INSTITUTE (HI) 9 Sylvan Way, Suite 180 Parsippany, NJ 07054-3802 Ph: 888-786-7744 or 973-267-9700 Fax: 973-267-9055 Internet: www.pumps.org AOK 8/00 LOK 6/00 HYDRONICS INSTITUTE DIVISION OF GAMA (HYI) 35 Russo Pl. P.O. Box 218 Berkeley Heights, NJ 07922-0218 Ph: 908-464-8200 Fax: 908-464-7818 Internet: www.gamanet.org AOK 8/00 LOK 6/00 IBM CORPORATION (IBM) Publications P.O. Box 29570 Raleigh, NC 27626-0570 Ph: 800-879-2755, Option 1 Fax: 800-445-9269 Internet: www.elink.ibmlink.ibm.com/pbl/pbl AOK 8/00 LOK 6/00 ILLUMINATING ENGINEERING SOCIETY OF NORTH AMERICA (IESNA) 120 Wall St., 17th Floor New York, NY 10005-4001 Ph: 212-248-5000 Fax: 212-248-5017 Internet: www.iesna.org AOK 8/00 LOK 6/00 INDUSTRIAL FASTENERS INSTITUTE (IFI) 1717 East 9th St., Suite 1105 Cleveland, OH 44114-2879 Ph: 216-241-1482 Fax: 216-241-5901 Internet: http://www.industrial-fasteners.org e-mail: indfast@aol.com AOK 8/00

LOK 6/00

INSECT SCREENING WEAVERS ASSOCIATION (ISWA)

P.O. Box 1018 Ossining, NY 10562 Ph: 914-962-9052 Fax: 914-923-3031

AOK 8/00 LOK 6/00

INSTITUTE FOR INTERCONNECTING AND PACKAGING ELECTRONIC CIRCUITS (IPC)

2215 Sanders Rd.

Northbrook, IL 60062-6135

Ph: 847-509-9700 Fax: 847-509-9798

Internet: www.ipc.org
e-mail: orderipc@ipc.org

AOK 8/00 LOK 6/00

INSTITUTE OF CLEAN AIR COMPANIES (ICAC)

1660 L St., NW, Suite 1100 Washington, DC 20036-5603

Ph: 202-457-0911 Fax: 202-331-1388

E-mail: sjenkins@icac.com

Internet: icac.com

AOK 8/00 LOK 6/00

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

445 Hoes Ln, P. O. Box 1331 Piscataway, NJ 08855-1331

Ph: 732-981-0060 OR 800-701-4333

Fax: 732-981-9667
Internet: www.ieee.org

E-mail: customer.service@ieee.org

AOK 8/00 LOK 6/00

INSTITUTE OF ENVIRONMENTAL SCIENCES (IES)

940 East Northwest Highway Mount Prospect, IL 60056

Ph: 847-255-1561 Fax: 847-255-1699

Internet: www.iest.org

INSULATED CABLE ENGINEERS ASSOCIATION (ICEA)

P.O. Box 440

South Yarmouth, MA 02664

Ph: 508-394-4424 Fax: 508-394-1194

E-mail: Internet: www.icea.net

AOK 8/00 LOK 6/00

INTERNATIONAL APPROVAL SERVICES (IAS)

8501 East Pleasant Valley Rd.

Cleveland, OH 44131 Ph: 216-524-4990 Fax: 216-328-8118

Internet: www.iasapprovals.org

AOK 8/00 LOK 6/00

INTERNATIONAL ASSOCIATION OF PLUMBING AND MECHANICAL OFFICIALS (IAPMO)

20001 Walnut Dr., So. Walnut, CA 91789-2825 Ph: 909-595-8449

Fax: 909-594-3690

Fax for Stds: 909-594-5265 Internet: www.iapmo.org

AOK 8/00 LOK 6/00

INTERNATIONAL CONFERENCE OF BUILDING OFFICIALS (ICBO)

5360 Workman Mill Rd. Whittier, CA 90601-2298

Ph: 800-284-4406 Ph: 310-699-0541 Fax: 310-692-3853 Internet: icbo.org

AOK 8/00 LOK 6/00

INTERNATIONAL ELECTROTECHNICAL COMMISSION (IEC)

3, rue de Varembe, Case Postale 131 CH-1211 Geneva 20, Switzerland

Ph: 41-22-919-0211 Fax: 41-22-919-0300

Internet: http://www.iec.ch
e-mail: custserv@iec.ch

AOK 8/00 LOK 6/00

INTERNATIONAL INSTITUTE OF AMMONIA REFRIGERATION (IIAR)

1110 N. Glebe Rd., Suite 250

Arlington, VA 22201 Ph: 703-312-4200 Fax: 703-312-0065

Internet: www.iiar.org
e-mail: iiar@iiar.org

AOK 8/00 LOK 6/00

INTERNATIONAL MUNICIPAL SIGNAL ASSOCIATION (IMSA)

P.O. Box 539

165 East Union St.

Newark, NY 14513-0539

Ph: 315-331-2182 Ph: 800-723-4672 Fax: 315-331-8205

Internet: www.imsasafety.org

AOK 8/00 LOK 6/00

INTERNATIONAL ORGANIZATION FOR STANDARDIZATION (ISO)

1, rue de Varembe'

Case Postale 56

CH-1211 Geneve 20

Switzerland

Ph: 41-22-749-0111
Fax: 41-22-733-3430
Internet: www.iso.ch
e-mail: central@iso.ch

AOK 8/00 LOK 6/00

INTERNATIONAL SLURRY SURFACING ASSOCIATION (ISSA)

1200 Nineteenth St., NW, Suite 300

Washington, DC 20036-2422

Ph: 202-857-1160 Fax: 202-223-4579

Internet: www.slurry.org

e-mail

INTERNATIONAL TELECOMMUNICATION UNION (ITU)

Order from:

U.S. Dept of Commerce

National Technical Information Service

5285 Port Royal Road. Springfield, VA 22161 Ph: 703605-6040

FAX: 703-605-6887

Internet: www.ntis.gov

For documents not avail from Dept of Commerce:

E-Mail: sales@itu.ch Fax: 41.22.730.5194 Internet: www.itu.org

AOK 8/00 LOK 6/00

IRON & STEEL SOCIETY (ISS)

186 Thornhill Rd

Warrendale, PA 15086-7528 Ph: 724-776-1353 Ext 1

Fax: 724-776-0430

E-Mail: custserv@issource.org
Internet: www.issource.org

AOK 8/00 LOK 6/00

ISA (ISA)

67 Alexander Drive

P.O. Box 12277

Research Triangle Park, NC 27709

Ph: 919-549-8411 Fax: 919-549-8288 e-mail: ISA@isa.org

Internet: http://www.isa.org

AOK 8/00 LOK 6/00

KITCHEN CABINET MANUFACTURERS ASSOCIATION (KCMA)

1899 Preston White Dr. Reston, VA 20191-5435

Ph: 703-264-1690 Fax: 703-620-6530

Internet: www.kcma.org

AOK 8/00 LOK 6/00

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

127 Park St., NE

Vienna, VA 22180-4602

Ph: 703-281-6613 Fax: 703-281-6671

Internet: www.mss-hq.com
e-mail: info@mss-hq.com

AOK 8/00 LOK 6/00

MAPLE FLOORING MANUFACTURERS ASSOCIATION (MFMA)

60 Revere Dr., Suite 500 Northbrook, IL 60062 Ph: 847-480-9138

Fax: 847-480-9282

Internet: www.maplefloor.org

AOK 8/00 LOK 6/00

MARBLE INSTITUTE OF AMERICA (MIA)

30 Eden Alley, Suite 301

Columbus, OH 43215 Ph: 614-228-6194 Fax: 614-461-1497

Internet: www.marble-institute.com
e-mail: miaadmin@marble-institute.com

AOK 8/00 LOK 6/00

MATERIAL HANDLING INDUSTRY (MHI)

8720 Red Oak Blvd., Suite 201 Charlotte, NC 28217-3992

Ph: 800-345-1815 or 704-676-1190

Fax: 704-676-1199
Internet: www.mhi.org

AOK 8/00 LOK 6/00

METAL BUILDING MANUFACTURERS ASSOCIATION (MBMA)

1300 Sumner Ave.

Cleveland, OH 44115-2851

Ph: 216-241-7333
Fax: 216-241-0105
Internet: www.mbma.com
e-mail: mbma@mbma.com
AOK 8/00

LOK 6/00

MIDWEST INSULATION CONTRACTORS ASSOCIATION (MICA)

2017 So. 139th Cir. Omaha, NE 68144 Ph: 402-342-3463 Fax: 402-330-9702

Internet: www.micainsulation.org
e-mail: info@micainsulation.org

AOK 8/00 LOK 6/00

MILITARY HANDBOOKS (MIL-HDBK)

Order from:

Standardization Documents Order Desk

Bldq 4D

700 Robbins AV

Philadelphia, PA 19111-5094 Ph: 215-697-5147

Fax: 215-697-5148

Internet: www.dodssp.daps.mil

AOK 8/00 LOK 6/00

MILITARY SPECIFICATIONS (MS)

Order from:

Standardization Documents Order Desk

Building 4, Section D

700 Robbins Ave.

Philadelphia, PA 19111-5094

Ph: 215-697-5147 Fax: 215-697-5148

Internet: www.dodssp.daps.mil

AOK 8/00 LOK 6/00

MILITARY STANDARDS (MIL-STD)

Order from:

Standardization Documents Order Desk

Building 4, Section D

700 Robbins Ave.

Philadelphia, PA 19111-5094

Ph: 215-697-2179 Fax: 215-697-2978

Internet: www.dodssp.daps.mil

AOK 8/00 LOK 6/00

NACE INTERNATIONAL (NACE)

1440 South Creek Drive

Houston, TX 77084-4906

Ph: 281-228-6200 Fax: 281-228-6300

Internet: www.nace.org

AOK 8/00 LOK 6/00

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)

8 S. Michigan Ave, Suite 1000

Chicago, IL 60603 Ph: 312-782-4951 Fax: 312-332-0706

Internet: www.naamm.org

e-mail

NATIONAL ASSOCIATION OF PLUMBING-HEATING-COOLING CONTRACTORS

(NAPHCC)

180 S. Washington Street P.O. Box 6808 Falls Church, VA 22040 Ph: 800-533-7694 Fax: 703-237-7442

Internet: www.naphcc.org

AOK 8/00 LOK 6/00

NATIONAL BOARD OF BOILER AND PRESSURE VESSEL INSPECTORS (NBBPVI)

1055 Crupper Ave.

Columbus, OH 43229-1183

Ph: 614-888-2463 Fax: 614-847-1147

Internet: www.nationalboard.org
e-mail: orders@nationalboard.org

LOK 6/00

NATIONAL CABLE TELEVISION ASSOCIATION (NCTA)

1724 Massachusetts Ave. NW Washington, DC 20036-1969

Ph: 202-775-3629 Fax: 202-775-1055 Internet: www.ncta.com

AOK 8/00 LOK 6/00

NATIONAL COUNCIL ON RADIATION PROTECTION AND MEASUREMENTS (NCRP)

7910 Woodmont Ave., Suite 800

Bethesda, MD 20814-3095

Ph: 800-229-2652 Ph. 301-657-2652 Fax: 301-907-8768

Internet: www.ncrp.com

AOK 8/00 LOK 6/00

NATIONAL DRILLING ASSOCIATION (NDA)

6089 Frantz Rd., Suite 101

Dublin, OH 43017 Ph: 614-798-8080 Fax: 614-798-2255 email: info@nda4U.com

Internet: http://www.nda4U.com

AOK 8/00 LOK 6/00

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

1300 N. 17th St., Suite 1847

```
Rosslyn, VA 22209
Ph: 703-841-3200
Fax: 703-841-3300
Internet: http//www.nema.org/
AOK 8/00
LOK 6/00
```

NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB)

8575 Grovemont Circle Gaithersburg, MD 20877-4121 Ph: 301-977-3698

Fax: 301-977-9589 Internet: www.nebb.org

AOK 8/00 LOK 6/00

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

1 Batterymarch Park P.O. Box 9101 Quincy, MA 02269-9101

Ph: 617-770-3000 Fax: 617-770-0700 Internet: www.nfpa.org

NOTE: The complete set of 1997 NFPA National Fire Codes (13 Vol.)

is available for \$835.00.

AOK 8/00 LOK 8/00

NATIONAL FLUID POWER ASSOCIATION (NFLPA)

3333 N. Mayfair Rd.

Milwaukee, WI 53222-3219

Ph: 414-778-3344 Fax: 414-778-3361 Internet: www.nfpa.com E-mail: nfpa@nfpa.com AOK 8/00

LOK 6/00

NATIONAL HARDWOOD LUMBER ASSOCIATION (NHLA)

P.O. Box 34518

Memphis, TN 38184-0518

Ph: 901-377-1818 Fax: 901-382-6419

e-mail: nhla@natlhardwood.org Internet: natlhardwood.org

AOK 8/00 LOK 6/00

NATIONAL INSTITUTE FOR CERTIFICATION IN ENGINEERING TECHNOLOGIES (NICET)

1420 King Street Alexandria, VA 22314-2794 Ph: 888-476-4238 Internet: www.nicet.org AOK 8/00 LOK 6/00 NATIONAL INSTITUTE FOR OCCUPATIONAL SAFETY AND HEALTH (NIOSH) Mail Stop C-13 4676 Columbia Parkway Cincinnati, OH 45226-1998 Ph: 800-356-4676 Internet: http://www.cdc.gov/niosh/homepage.html To order pubs for which a fee is charged, order from: Superintendent of Documents Government Printing Office Washington, DC 20402-9325 Ph: 202-512-1800 Fax: 202-512-2250 AOK 8/00 LOK 6/00 NATIONAL INSTITUTE OF JUSTICE (NIJ) National Law Enforcement and Corrections Technology Center 2277 Research Blvd. - Mailstop 1E Rockville, MD 20850 Ph: 800-248-2742 or 301-519-5060 Fax: 301-519-5149 Internet: www.nlectc.org e-mail: asknlectc@nlectc.org AOK 8/00 LOK 6/00 NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST) Department of Commerce Gaithersburg, MD 20899-0001 Ph: 301-975-4025 Fax: 301-926-1630 Order Publications From: Superintendent of Documents U.S. Government Printing Office (GPO) Washington, DC 20402 Ph: 202-512-1800 Fax: 202-512-2250 National Technical Information Services (NTIS) 5285 Port Royal Rd.

Springfield, VA 22161 Ph: 800-553-6847 Fax: 703-321-8547 Internet: www.gov/ntis.gov

AOK 8/00 LOK 6/00

NATIONAL OAK FLOORING MANUFACTURERS ASSOCIATION (NOFMA)

P.O. Box 3009

Memphis, TN 38173-0009

Ph: 901-526-5016 Fax: 901-526-7022

Internet: www.nofma.org

AOK 8/00 LOK 6/00

NATIONAL READY-MIXED CONCRETE ASSOCIATION (NRMCA)

900 Spring St.

Silver Spring, MD 20910

Ph: 301-587-1400 Fax: 301-585-4219

Internet: www.nrmca.org

AOK 8/00 LOK 6/00

NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)

10255 W. higgins Rd., Suite 600

Rosemont, IL 60018 Ph: 847-299-9070 Fax: 847-299-1183

Internet: www.nrca.net

AOK 8/00 LOK 6/00

NATIONAL TERRAZZO & MOSAIC ASSOCIATION (NTMA)

110 East Market St., Suite 200 A

Leesburg, Virginia 20176

Ph: 703-779-1022 or 800-323-9736

Fax: 703-779-1026

Internet: www.ntma.com
e-mail: info@ntma.com

AOK 8/00 LOK 6/00

NATIONAL WOOD WINDOW & DOOR ASSOCIATION (NWWDA)

1400 East Touhy Ave., Suite 470

Des Plaines, IL 60018

Ph: 847-299-5200 800-223-2301

Fax: 708-299-1286
Internet: wwwnwwda.org
e-mail: admin@wdma.com

AOK 8/00

LOK 6/00

NAVAL FACILITIES ENGINEERING COMMAND (NAVFAC)

1510 Gilbert St.

Norfolk, VA 23511-2699

Ph: 757-322-4200 Fax: 757-322-4416

Internet: www.efdlant.navfac.navy.mil

AOK 8/00 LOK 6/00

NAVAL FACILITIES ENGINEERING SERVICE CENTER (NFESC)

1100 23rd Avenue

Port Hueneme, CA 93043-4370

Ph: 805-982-4980

Internet: www.nfesc.navy.mil

AOK 8/00 LOK 6/00

NORTH AMERICAN INSULATION MANUFACTURERS ASSOCIATION (NAIMA)

44 Canal Center Plaza, Suite 310

Alexandria, VA 22314

Ph: 703-684-0084 Fax: 703-684-0427

Internet: www.naima.org
e-mail: insulation@naima.org

AOK 8/00

LOK 6/00

NORTHEASTERN LUMBER MANUFACTURERS ASSOCIATION (NELMA)

272 Tuttle Road

P.O. Box 87A

Cumberland Center, ME 04021

Ph: 207-829-6901 Fax: 207-829-4293

Internet: www.nelma.org
e-mail: nelma@javanet.com

AOK 8/00 LOK 6/00

NORTHEAST REGIONAL AGRICULTURAL ENGINEERING SERVICE (NRAES)

Cooperative Extension

152 Riley-Robb Hall

Ithaca, NY 14853-5701 Ph: 607-255-7654

Fax: 607-255-7654

Internet: www.nraes.org
E-mail: nraes@cornell.edu

AOK 8/00

LOK 6/00

NSF INTERNATIONAL (NSF)

ATTN: Publications 789 Dixboro Rd. P.O. Box 130140

Ann Arbor, MI 48113-0140

Ph: 734-769-8010 Fax: 734-769-0109

Toll Free: 800-NSF-MARK Internet: www.nsf.org

AOK 8/00 LOK 6/00

PIPE FABRICATION INSTITUTE (PFI)

PMB 323

611 Pennsylvania Ave. SE Washington, DC 20003 Ph: 514-634-3434

Fax: 514-634-9736

Internet: www.pfi-institute.org
e-mail: pfi@pfi-institute.org

AOK 8/00 LOK 6/00

PLASTIC PIPE AND FITTINGS ASSOCIATION (PPFA)

800 Roosevelt Rd., Bldg C, Suite 20

Glen Ellyn, IL 60137 Ph: 630-858-6540 Fax: 630-790-3095

Internet: www.ppfahome.org

AOK 8/00 LOK 6/00

PLASTICS PIPE INSTITUTE (PPI)

1825 Connecticut Ave. NW Washington, D. C. 20009

Ph: 202-462-9607 Fax: 202-462-9779

Internet: www.plasticpipe.org

AOK 8/00 LOK 6/00

PLUMBING AND DRAINAGE INSTITUTE (PDI)

45 Bristol Dr.

South Easton, MA 02375

Ph: 508-230-3516 or 800-589-8956

Fax: 508-230-3529

Internet: www.pdionline.org

E-Mail: info@pdionline.org
AOK 8/00

LOK 6/00

PLUMBING AND PIPING INDUSTRY COUNCIL (PPIC)

9450 SW Commerce Circle, Suite 310 wilsonville, OR 97070-9626

Ph: 503-682-7919

PORCELAIN ENAMEL INSTITUTE (PEI)

P.O.Box 158541

4004 Hillsboro Pike, Suite 224B

Nashville, TN 37215 Ph: 615-385-5357 Fax: 615-385-5463

Internet: www.porcelainenamel.com

e-mail: penamel@aol.com

AOK 8/00 LOK 6/00

PRECAST/PRESTRESSED CONCRETE INSTITUTE (PCI)

209 West Jackson Blvd. Chicago, IL 60606-6938

Ph: 312-786-0300 Fax: 312-786-0353 Internet: www.pci.org e-mail: info@pci.org AOK 8/00

LOK 6/00

RUBBER MANUFACTURERS ASSOCIATION (RMA)

1400 K St., NW, Suite 900

Washington, DC 20005

Ph: 202-682-4800 Fax: 202-682-4854 Internet: www.rma.org Order Publications from:

The Mail Room
P. O. Box 3147
Medina, OH 44258

Ph: 800-325-5095 EXT 242 or 330-723-2978

Fax: 330-725-0576

AOK 8/00 LOK 6/00

RURAL UTILITIES SERVICE (RUS)

ATTN: Publications

14th and Independence Ave., SW, Room 4028-S Washington, DC 20250 Ph: 202-720-8674 OR 202-720-8679 Fax: 202-205-3654 Internet: www.usda.gov/rus SCREEN MANUFACTURERS ASSOCIATION (SMA) 2850 South Ocean Boulevard, Suite 311 Palm Beach, FL 33480-5535 Ph: 561-533-0991 Fax: 561-533-7466 e-mail: fscottfitzgerald@compuserve.com Internet: www.eren.doe.gov AOK 8/00 LOK 6/00 SHEET METAL & AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA) 4201 Lafayette Center Dr., Chantilly, VA 20151-1209 Ph: 703-803-2980 Fax: 703-803-3732 Internet: http://www.smacna.org e-mail: info@smacna.org AOK 8/00 LOK 6/00 SINGLE PLY ROOFING INSTITUTE (SPRI) 200 Reservoir St., Suite 309A Needham, MA 02494 Ph: 781-444-0242 Fax: 781-444-6111 Internet: www.spri.org e-mail: spri@spri.org AOK 8/00 LOK 6/00 SOCIETY OF AUTOMOTIVE ENGINEERS (SAE) 400 Commonwealth Dr. Warrendale, PA 15096-0001 Ph: 724-776-4841 Fax: 724-776-5760 Internet: http://www.sae.org

SOUTHERN BUILDING CODE CONGRESS INTERNATIONAL (SBCCI)

e-mail: publications@sae.org

AOK 8/00 LOK 6/00 900 Montclair Road

Birmingham, AL 35213-1206

Ph: 205-591-1853 Fax: 205-591-0775

Internet: www.sbcci.org

AOK 8/00 LOK 6/00

SOUTHERN CYPRESS MANUFACTURERS ASSOCIATION (SCMA)

400 Penn Center Boulevard, Suite 530

Pittsburgh, PA 15235

Ph: 412-829-0770 Fax: 412-829-0844

Internet: www.cypressinfo.org

AOK 8/00 LOK 6/00

SOUTHERN PINE INSPECTION BUREAU (SPIB)

4709 Scenic Highway

Pensacola, FL 32504-9094

Ph: 850-434-2611
Fax: 850-433-5594
e-mail: spib@spib.org
Internet: www.spib.org

AOK 8/00 LOK 6/00

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)

40 24th Street, 6th Floor Pittsburgh, PA 15222-4656

Ph: 412-281-2331 Fax: 412-281-9992

Internet: www.sspc.org

AOK 8/00 LOK 6/00

NOTE: SSPC documents, except as noted otherwise, are available only as a part of the 1995 Steel Structures Painting Manual, 7th Edition @ \$115.00.

STEEL DECK INSTITUTE (SDI)

P.O. Box 25

Fox River Grove, IL 60021-0025

Ph: 847-462-1930 Fax: 847-462-1940

Internet: http://www.sdi.org

e-mail: Steve@sdi.org

AOK 8/00 LOK 6/00

STEEL DOOR INSTITUTE (SDOI)

30200 Detroit Rd.

Cleveland, OH 44145-1967

Ph: 440-899-0010 Fax: 440-892-1404

Internet: www.steeldoor.org

AOK 8/00 LOK 6/00

STEEL JOIST INSTITUTE (SJI)

3127 Tenth Ave., North Ext. Myrtle Beach, SC 29577-6760

Ph: 843-626-1995 Fax: 843-626-5565

Internet: www.steeljoist.org

AOK 8/00 LOK 6/00

STEEL TANK INSTITUTE (STI)

570 Oakwood Rd.

Lake Zurich, IL 60047

Ph: 847-438-8265 Fax: 847-438-8766

Internet: www.steeltank.com

AOK 8/00 LOK 6/00

STEEL WINDOW INSTITUTE (SWI)

1300 Sumner Ave.

Cleveland, OH 44115-2851

Ph: 216-241-7333 Fax: 216-241-0105

Internet: www.steelwindows.com

AOK 8/00 LOK 6/00

TILE COUNCIL OF AMERICA (TCA)

100 Clemson Research Blvd

Anderson, SC 29625 Ph: 864-646-8453 FAX: 864-646-2821

Internet: www.tileusa.com

e-mail: literature@tileusa.com

AOK 8/00 LOK 6/00

TRUSS PLATE INSTITUTE (TPI)

583 D'Onofrio Dr., Suite 200

Madison, WI 53719 Ph: 608-833-5900 Fax: 608-833-4360

AOK 8/00 LOK 6/00

TUBULAR EXCHANGE MANUFACTURERS ASSOCIATION (TEMA)

25 N. Broadway

Tarrytown, NY 10591 Ph: 914-332-0040 Fax: 914-332-1541

Internet: www.tema.org

AOK 8/00 LOK 6/00

UNDERWRITERS LABORATORIES (UL)

333 Pfingsten Rd.

Northbrook, IL 60062-2096

Ph: 847-272-8800 Fax: 847-272-8129

Internet: http://www.ul.com/
e-mail: northbrook@us.ul.com

AOK 8/00 LOK 6/00

Note: First price is for the standard only. Second price is for the standard including the Revision Subscription Service.

UNI-BELL PVC PIPE ASSOCIATION (UBPPA)

2655 Villa Creek Dr., Suite 155

Dallas, TX 75234 Ph: 214-243-3902 Fax: 214-243-3907

Internet: www.uni-bell.org
e-mail: info@uni-bell.org

AOK 8/00 LOK 6/00

U. S. ARMY ENVIORNMENTAL HYGIENE AGENCY (USAEHA)

Waste Disposal Engineering Division
Aberdeen Proving Ground, MD 21010-5422

Ph: 410-436-3652

WATER ENVIRONMENT FEDERATION (WEF)

601 Wythe St.

Alexandria, VA 22314-1994

Ph: 703-684-2452

Fax: 703-684-2492
Internet: www.wef.org

AOK 8/00 LOK 6/00

WATER QUALITY ASSOCIATION (WQA)

4151 Naperville Rd. Lisle, IL 60532 Ph: 630-505-0160 Fax: 630-505-9637

Internet: www.wqa.org
e-mail: info@mail.wqa.org

AOK 8/00 LOK 6/00

WEST COAST LUMBER INSPECTION BUREAU (WCLIB)

P.O. Box 23145

Portland, OR 97281 Ph: 503-639-0651 Fax: 503-684-8928

internet: www.wclib.org
e-mail: info@wclib.org

AOK 8/00 LOK 6/00

WESTERN WOOD PRESERVERS INSTITUTE (WWPI)

7017 N.E. Highway 99 # 108

Vancover, WA 98665 Ph: 360-693-9958 Fax: 360-693-9967

Internet: www.awpi.org/wwpi
e-mail: wwpi@teleport.com

AOK 8/00 LOK 6/00

WESTERN WOOD PRODUCTS ASSOCIATION (WWPA)

Yeon Bldg.

522 SW 5th Ave.

Suite 500

Portland, OR 97204-2122

Ph: 503-224-3930
Fax: 503-224-3934
Internet: www.wwpa.org
e-mail: info@wwpa.org

AOK 8/00 LOK 6/00

WOOD MOULDING AND MILLWORK PRODUCERS ASSOCIATION (WMMPA)

507 First Street

Woodland, CA 95695 Ph: 916-661-9591 Fax: 916-661-9586

Internet: www.wmmpa.com

AOK 8/00 LOK 6/00

-- End of Section --

SECTION 01451

CONTRACTOR QUALITY CONTROL

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 3740 (1999b) Minimum Requirements for Agencies
Engaged in the Testing and/or Inspection
of Soil and Rock as Used in Engineering
Design and Construction

ASTM E 329 (1998a) Agencies Engaged in the Testing and/or Inspection of Materials Used in Construction

1.2 PAYMENT

Separate payment will not be made for providing and maintaining an effective Quality Control program, and all costs associated therewith shall be included in the applicable unit prices or lump-sum prices contained in the Bidding Schedule.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

CQC Plan; G WA.

Identifies personnel, procedures, control, instructions, test, records, and forms to be used.

Phase Notification

The Government shall be notified in a specified amount of time in advance of beginning the preparatory control phase.

CQC Mgr Qualification; G WA.

The evaluation of the project to determine the level of CQC System Manager required.

SD-05 Design Data

Notification of Changes

Any changes made by the Contractor.

Punchlist

Near the completion of all work, the CQC System Manager shall prepare a list of items which do not conform to the approved drawings and specifications.

Minutes

Prepared by the Government and signed by both the Contractor and the Contracting Officer and shall become a part of the contract file.

SD-06 Test Reports

Tests

Specified or required tests shall be done by the Contractor to verify that control measures are adequate.

Documentation

Results of tests taken.

Tests Performed

An information copy provided directly to the Contracting Officer.

QC Records; G WA.

Provide factual evidence that required quality control activities and/or tests have been performed.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

The Contractor is responsible for quality control and shall establish and maintain an effective quality control system in compliance with the Contract Clause titled "Inspection of Construction." The quality control system shall consist of plans, procedures, and organization necessary to produce an end product which complies with the contract requirements. The system shall cover all construction operations, both onsite and offsite, and shall be keyed to the proposed construction sequence. The site project superintendent will be held responsible for the quality of work on the job and is subject to removal by the Contracting Officer for non-compliance

with the quality requirements specified in the contract. The site project superintendent in this context shall be the highest level manager responsible for the overall construction activities at the site, including quality and production. The site project superintendent shall maintain a physical presence at the site at all times, except as otherwise acceptable to the Contracting Officer, and shall be responsible for all construction and construction related activities at the site.

3.2 CQC PLAN

3.2.1 General

The Contractor shall furnish for review by the Government, not later than 30 days after receipt of notice to proceed, the Contractor Quality Control (CQC) Plan proposed to implement the requirements of the Contract Clause titled "Inspection of Construction." The plan shall identify personnel, procedures, control, instructions, tests, records, and forms to be used. The Government will consider an interim plan for the first 60 days of operation. Construction will be permitted to begin only after acceptance of the CQC Plan or acceptance of an interim plan applicable to the particular feature of work to be started. Work outside of the features of work included in an accepted interim plan will not be permitted to begin until acceptance of a CQC Plan or another interim plan containing the additional features of work to be started.

3.2.2 Content of the CQC Plan

The CQC Plan shall include, as a minimum, the following to cover all construction operations, both onsite and offsite, including work by subcontractors, fabricators, suppliers, and purchasing agents:

- a. A description of the quality control organization, including a chart showing lines of authority and acknowledgment that the CQC staff shall implement the three phase control system for all aspects of the work specified. The staff shall include a CQC System Manager who shall report to the project superintendent.
- b. The name, qualifications (in resume format), duties, responsibilities, and authorities of each person assigned a CQC function.
- c. A copy of the letter to the CQC System Manager signed by an authorized official of the firm which describes the responsibilities and delegates sufficient authorities to adequately perform the functions of the CQC System Manager, including authority to stop work which is not in compliance with the contract. The CQC System Manager shall issue letters of direction to all other various quality control representatives outlining duties, authorities, and responsibilities. Copies of these letters shall also be furnished to the Government.
- d. Procedures for scheduling, reviewing, certifying, and managing submittals, including those of subcontractors, offsite fabricators, suppliers, and purchasing agents. These procedures

shall be in accordance with Section 01330 SUBMITTAL PROCEDURES.

- e. Control, verification, and acceptance testing procedures for each specific test to include the test name, specification paragraph requiring test, feature of work to be tested, test frequency, and person responsible for each test. The Contractor shall include a copy of his proposed laboratory's latest Corps of Engineers inspection report in the Quality Control Plan. The inspection report details the tests that the lab has been validated to perform under Corps of Engineers contracts. (Laboratory facilities will be approved by the Contracting Officer.)
- f. Procedures for tracking preparatory, initial, and follow-up control phases and control, verification, and acceptance tests including documentation.
- g. Procedures for tracking construction deficiencies from identification through acceptable corrective action. These procedures shall establish verification that identified deficiencies have been corrected.
- h. Reporting procedures, including proposed reporting formats.
- i. A list of the definable features of work. A definable feature of work is a task which is separate and distinct from other tasks, has separate control requirements, and may be identified by different trades or disciplines, or it may be work by the same trade in a different environment. Although each section of the specifications may generally be considered as a definable feature of work, there are frequently more than one definable features under a particular section. This list will be agreed upon during the coordination meeting.

3.2.3 Acceptance of Plan

Acceptance of the Contractor's plan is required prior to the start of construction. Acceptance is conditional and will be predicated on satisfactory performance during the construction. The Government reserves the right to require the Contractor to make changes in his CQC Plan and operations including removal of personnel, as necessary, to obtain the quality specified.

3.2.4 Notification of Changes

After acceptance of the CQC Plan, the Contractor shall notify the Contracting Officer in writing of any proposed change. Proposed changes are subject to acceptance by the Contracting Officer.

3.3 COORDINATION MEETING

After the Preconstruction Conference, before start of construction, and prior to acceptance by the Government of the CQC Plan, the Contractor shall meet with the Contracting Officer or Authorized Representative and discuss the Contractor's quality control system. The CQC Plan shall be submitted

for review a minimum of 14 calendar days prior to the Coordination Meeting. During the meeting, a mutual understanding of the system details shall be developed, including the forms for recording the CQC operations, control activities, testing, administration of the system for both onsite and offsite work, and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. Minutes of the meeting shall be prepared by the Government and signed by both the Contractor and the Contracting Officer. The minutes shall become a part of the contract file. There may be occasions when subsequent conferences will be called by either party to reconfirm mutual understandings and/or address deficiencies in the CQC system or procedures which may require corrective action by the Contractor.

3.4 QUALITY CONTROL ORGANIZATION

3.4.1 Personnel Requirements

The requirements for the CQC organization are a CQC System Manager and sufficient number of additional qualified personnel to ensure safety and contract compliance. The Contractor's CQC staff shall maintain a presence at the site at all times during progress of the work and have complete authority and responsibility to take any action necessary to ensure contract compliance. The CQC staff shall be subject to acceptance by the Contracting Officer. The Contractor shall provide adequate office space, filing systems and other resources as necessary to maintain an effective and fully functional CQC organization. Complete records of all letters, material submittals, show drawing submittals, schedules and all other project documentation shall be promptly furnished to the CQC organization by the Contractor. The CQC organization shall be responsible to maintain these documents and records at the site at all times, except as otherwise acceptable to the Contracting Officer.

3.4.2 CQC System Manager

The Contractor shall identify as CQC System Manager an individual within the onsite work organization who shall be responsible for overall management of CQC and have the authority to act in all CQC matters for the Contractor. The CQC System Manager shall be a construction person with a minimum of five (5) years in related work. This CQC System Manager shall be on the site at all times during construction and shall be employed by the prime Contractor. The CQC System Manager shall be assigned as System Manager but may have duties as project superintendent in addition to quality control. An alternate for the CQC System Manager shall be identified in the plan to serve in the event of the System Manager's absence. The requirements for the alternate shall be the same as for the designated CQC System Manager.

3.5 SUBMITTALS

Submittals, if needed, shall be made as specified in Section 01330 SUBMITTAL PROCEDURES. The CQC organization shall be responsible for certifying that all submittals and deliverables are in compliance with the contract requirements.

3.6 CONTROL

Contractor Quality Control is the means by which the Contractor ensures that the construction, to include that of subcontractors and suppliers, complies with the requirements of the contract. At least three phases of control shall be conducted by the CQC System Manager for each definable feature of work as follows:

3.6.1 Preparatory Phase

This phase shall be performed prior to beginning work on each definable feature of work, after all required plans/documents/materials are approved/accepted, and after copies are at the work site. This phase shall include:

- a. A review of each paragraph of applicable specifications, reference codes, and standards. A copy of those sections of referenced codes and standards applicable to that portion of the work to be accomplished in the field shall be made available by the Contractor at the preparatory inspection. These copies shall be maintained in the field and available for use by Government personnel until final acceptance of the work.
- b. A review of the contract drawings.
- c. A check to assure that all materials and/or equipment have been tested, submitted, and approved.
- d. Review of provisions that have been made to provide required control inspection and testing.
- e. Examination of the work area to assure that all required preliminary work has been completed and is in compliance with the contract.
- f. A physical examination of required materials, equipment, and sample work to assure that they are on hand, conform to approved shop drawings or submitted data, and are properly stored.
- g. A review of the appropriate activity hazard analysis to assure safety requirements are met.
- h. Discussion of procedures for controlling quality of the work including repetitive deficiencies. Document construction tolerances and workmanship standards for that feature of work.
- i. A check to ensure that the portion of the plan for the work to be performed has been accepted by the Contracting Officer.
- j. Discussion of the initial control phase.
- k. The Government shall be notified at least 72 hours in advance of beginning the preparatory control phase. This phase shall include a meeting conducted by the CQC System Manager and attended by the

superintendent, other CQC personnel (as applicable), and the foreman responsible for the definable feature. The results of the preparatory phase actions shall be documented by separate minutes prepared by the CQC System Manager and attached to the daily CQC report. The Contractor shall instruct applicable workers as to the acceptable level of workmanship required in order to meet contract specifications.

3.6.2 Initial Phase

This phase shall be accomplished at the beginning of a definable feature of work. The following shall be accomplished:

- a. A check of work to ensure that it is in full compliance with contract requirements. Review minutes of the preparatory meeting.
- b. Verify adequacy of controls to ensure full contract compliance. Verify required control inspection and testing.
- c. Establish level of workmanship and verify that it meets minimum acceptable workmanship standards. Compare with required sample panels as appropriate.
- d. Resolve all differences.
- e. Check safety to include compliance with and upgrading of the safety plan and activity hazard analysis. Review the activity analysis with each worker.
- f. The Government shall be notified at least 72 hours in advance of beginning the initial phase. Separate minutes of this phase shall be prepared by the CQC System Manager and attached to the daily CQC report. Exact location of initial phase shall be indicated for future reference and comparison with follow-up phases.
- g. The initial phase should be repeated for each new crew to work onsite, or any time acceptable specified quality standards are not being met.

3.6.3 Follow-up Phase

Daily checks shall be performed to assure control activities, including control testing, are providing continued compliance with contract requirements, until completion of the particular feature of work. The checks shall be made a matter of record in the CQC documentation. Final follow-up checks shall be conducted and all deficiencies corrected prior to the start of additional features of work which may be affected by the deficient work. The Contractor shall not build upon nor conceal non-conforming work.

3.6.4 Additional Preparatory and Initial Phases

Additional preparatory and initial phases shall be conducted on the same definable features of work if the quality of on-going work is unacceptable,

if there are changes in the applicable CQC staff, onsite production supervision or work crew, if work on a definable feature is resumed after a substantial period of inactivity, or if other problems develop.

3.7 COMPLETION INSPECTION

3.7.1 Punch-Out Inspection

Near the completion of all work or any increment thereof established by a completion time stated in the Special Clause in Section 00800 of the Solicitation entitled "Commencement, Prosecution, and Completion of Work," or stated elsewhere in the specifications, the CQC System Manager shall conduct an inspection of the work and develop a punchlist of items which do not conform to the approved drawings and specifications. Such a list of deficiencies shall be included in the CQC documentation, as required by paragraph DOCUMENTATION below, and shall include the estimated date by which the deficiencies will be corrected. The CQC System Manager or staff shall make a second inspection to ascertain that all deficiencies have been corrected. Once this is accomplished, the Contractor shall notify the Government that the facility is ready for the Government Pre-Final inspection.

3.7.2 Pre-Final Inspection

The Government will perform pre-final inspection to verify that the facility is complete and ready to be occupied. A Government Pre-Final Punch List may be developed as a result of this inspection. The Contractor's CQC System Manager shall ensure that all items on this list have been corrected before notifying the Government so that a Final inspection with the customer can be scheduled. Any items noted on the Pre-Final inspection shall be corrected in a timely manner. These inspections and any deficiency corrections required by this paragraph shall be accomplished within the time slated for completion of the entire work or any particular increment of the work if the project is divided into increments by separate completion dates.

3.7.3 Final Acceptance Inspection

The Contractor's Quality Control Inspection personnel, plus the superintendent or other primary management person, and the Contracting Officer's Representative shall be in attendance at the final acceptance inspection. Additional Government personnel may also be in attendance. The final acceptance inspection will be formally scheduled by the Contracting Officer based upon results of the Pre-Final inspection. Notice shall be given to the Contracting Officer at least 14 days prior to the final acceptance inspection and shall include the Contractor's assurance that all specific items previously identified to the Contractor as being unacceptable, along with all remaining work performed under the contract, will be complete and acceptable by the date scheduled for the final acceptance inspection. Failure of the Contractor to have all contract work acceptably complete for this inspection will be cause for the Contracting Officer to bill the Contractor for the Government's additional inspection cost in accordance with the contract clause titled "Inspection of Construction".

3.8 DOCUMENTATION

The Contractor shall maintain current records providing factual evidence that required quality control activities and/or tests have been performed. These records shall include the work of subcontractors and suppliers and shall be on an acceptable form that includes, as a minimum, the following information:

- a. Contractor/subcontractor and their area of responsibility.
- b. Operating plant/equipment with hours worked, idle, or down for repair.
- c. Work performed each day, giving location, description, and by whom. When Network Analysis (NAS) is used, identify each phase of work performed each day by NAS activity number.
- d. Test and/or control activities performed with results and references to specifications/drawings requirements. The control phase shall be identified (Preparatory, Initial, Follow-up). List deficiencies noted along with corrective action.
- e. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications/drawings requirements.
- f. Submittals and deliverables reviewed, with contract reference, by whom, and action taken.
- g. Off-site surveillance activities, including actions taken.
- h. Job safety evaluations stating what was checked, results, and instructions or corrective actions.
- i. Instructions given/received and conflicts in plans and/or specifications.
- j. Contractor's verification statement.

These records shall indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. These records shall cover both conforming and deficient features and shall include a statement that equipment and materials incorporated in the work and workmanship comply with the contract. The original and one copy of these records in report form shall be furnished to the Government daily within 24 hours after the date covered by the report, except that reports need not be submitted for days on which no work is performed. As a minimum, one report shall be prepared and submitted for every 7 days of no work and on the last day of a no work period. All calendar days shall be accounted for throughout the life of the contract. The first report following a day of no work shall be for that day only. Reports shall be signed and dated by the CQC System Manager. The report from the CQC System Manager shall include copies of

test reports and copies of reports prepared by all subordinate quality control personnel.

3.9 SAMPLE FORMS

Sample forms enclosed at the end of this section.

3.10 NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the foregoing requirements. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

-- End of Section --

-						
	Contrac Address	ctor's Name	:			
	Dhone N	Number:				į
	Phone i	number.				
	CC	ONSTRUCTION	QUALITY (CONTROL R	REPORT	
		CT NAME:			DATE:	
						T NO.:
SUPERINTENDE	ENT:					
TYPE OF WORK	KERS	NUMBER		CONSTRUC		NUMBER
	<u> </u>					
	ļ					
	 				 .	
			ONTRACTORS			
COMPANY	RESPO	NSIBILITY	FOREM	IAN 	NO.	OF WORKERS
				-		
				į		
		ŗ	TOTALS			
NO. OF WORKE	ERS TODAY	MANHOUR	S TODAY	MANHOU	JRS FOR	THIS PERIOD
CON	TRACT MAT	TERIALS AND			RED TO S	ITE:
WEATHER:		SI	TE CONDITI	ONS:		
DID A DELAY		STOPPAGE O	CCUR TODAY	······································		
HAS ANYTHING DEVELOPED IN THE WORK WHICH MAY LEAD TO A CHANGE OR FINDING OF FACT? IF YES, EXPLAIN.						

SECTION 01451 PAGE 1 OF 3 PAGES

DESCRIPTION OF ALL WORK PERFORMED TODAY (LIST BY DEFINABLE FEATURES OF WORK)
PREPARATORY INSPECTION:
LIST ALL INSPECTIONS BY SUBJECT AND SPECIFICATION LOCATION. ATTACH MINUTES OF MEETING AND LIST OF ALL ATTENDEES.
HAVE ALL REQUIRED SUBMITTALS AND SAMPLES OF CONSTRUCTION BEEN APPROVED.
DO THE MATERIALS AND EQUIPMENT TO BE USED CONFORM TO THE SUBMITTALS?
HAS ALL PRELIMINARY WORK BEEN INSPECTED, TESTED, AND COMPLETED?
TEST REQUIRED AND INSPECTION TECHNIQUES TO BE EXECUTED TO PROVE CONTRACT COMPLIANCE (INCLUDE BOTH EXPECTED AND ACTUAL RESULTS)
HAS A PHASE HAZARD ANALYSIS BEEN PERFORMED?
COMMENTS AND DEFICIENCIES NOTED AND CORRECTIVE ACTIONS TAKEN:

SECTION 01451 PAGE 2 OF 3 PAGES

ALL INSTRUCTIONS RECEIVED FROM QA PERSONNEL AND ACTIONS TAKEN:
JOB SAFETY (INCLUDE MEETINGS HELD AND DEFICIENCIES NOTED WITH CORRECTIVE ACTIONS):
INITIAL INSPECTION:
LIST ALL INSPECTIONS BY SUBJECT AND SPECIFICATION LOCATION. COMMENTS AND/OR DEFICIENCIES NOTED AND CORRECTIVE ACTION TAKEN:
FOLLOW-UP INSPECTION:
LIST ALL INSPECTIONS BY SUBJECT AND SPECIFICATION LOCATION. COMMENTS AND/OR DEFICIENCIES NOTED AND CORRECTIVE ACTION TAKEN.
SIGNATURE:QUALITY CONTROL REPRESENTATIVE/MANAGER
THE ABOVE REPORT IS COMPLETE AND CORRECT. ALL MATERIALS AND EQUIPMENT USED AND ALL WORK PERFORMED DURING THIS REPORTING PERIOD ARE IN COMPLIANCE WITH THE CONTRACT SPECIFICATIONS, AND SUBMITTALS, EXCEPT AS NOTED ABOVE.
SIGNATURE:
CONTRACTOR'S APPROVED AUTHORIZED REPRESENTATIVE

SECTION 01451 PAGE 3 OF 3 PAGES

SECTION 01510

TEMPORARY CONSTRUCTION ITEMS

PART 1 GENERAL

1.1 General

The work covered by this section consists of furnishing all labor, materials, equipment, and services and performing all work required for or incidental to the items herein specified. No separate payment will be made for the construction and services required by this section, and all costs in connection therewith shall be included in the overall cost of the work unless specifically stated otherwise.

1.2 PROJECT SIGN: (AUG 1974)

A project sign shall be provided and erected at a location designated by the Contracting Officer. The sign shall conform to the requirements as shown on Attachment No. 1, a copy of which is attached hereto. The sign shall be erected as soon as possible and within 15 days after the date of receipt of notice to proceed. Upon completion of the project, the sign shall be removed and disposed of by the Contractor. (CENAB)

1.3 SAFETY SIGN (AUG 1974)

A safety sign shall be provided and erected at a location designated by the Contracting Officer. The sign shall conform to the requirements as shown on Attachment No. 2, a copy of which is attached hereto. The sign shall be erected as soon as possible and within 15 days after the date of receipt of notice to proceed. The data required by the sign shall be corrected daily, with light colored metallic or non-metallic numerals. Numerals, including mounting hardware, shall be subject to the approval of the Contracting Officer. Upon completion of the project, the sign shall be removed and disposed of by the Contractor. (CENAB)

1.4 BARRICADES

The Contractor shall erect and maintain temporary barricades to limit public access to hazardous areas. Such barricades shall be required whenever safe public access to paved areas such as roads, parking areas or sidewalks is prevented by construction activities or as otherwise necessary to ensure the safety of both pedestrian and vehicular traffic. Barricades shall be securely placed, clearly visible with adequate illumination to provide sufficient visual warning of the hazardous areas during both day and night. (CENAB)

1.5 MEASUREMENT AND PAYMENT

No separate measurement and payment will be made for the work performed in this Section 01510, TEMPORARY CONSTRUCTION ITEMS, specified herein, and all costs in connection therewith shall be considered a subsidiary obligation of the Contractor, and shall be included in the overall cost of the work.

PART 2 PRODUCT NOT APPLICABLE


PART 3 EXECUTION NOT APPLICABLE

ATTACHMENTS:

Attachment 1 Project Sign

Attachment 2 Safety Sign


-- End of Section --



SIGN MATERIALS

BE RED; LETTERING SHALL BE BLACK; BE INSTALLED FLUSH ON BACK SIDE SIDE WHITE, HOUSE PAINT-2 COATS POST 4"x4";3/4" EXTERIOR PLY-WOOD 4'-0"x6'-0", 2"x2" FRAMING BOTH SIDES AND EDGES; COLORS IN AND PROJECTING IN FRONT. OUT-OIL FOR LETTERING - LAMP BLACK AND BULLETIN RED; CASTLE SHALL WITH MITERED CORNERS. FRAMING THE CROSS SHALL BE GREEN

FURNISHED BY THE GOVERNMENT IN THE CASTLE INSIGNIA SHALL BE PRESSURE SENSITIVE VINYL FOR AFFIXING BY THE CONTRACTOR.



SECTION 01562

ENVIRONMENTAL PROTECTION

PART 1 GENERAL

The work covered by this section consists of furnishing all labor, materials and equipment and performing all work required for the prevention of environmental pollution during and as the result of construction operations under this contract except for those measures set forth in other Technical Provisions of these specifications. For the purpose of this specification, environmental pollution is defined as the presence of chemical, physical, or biological elements or agents which adversely affect human health or welfare; unfavorably alter ecological balances of importances to human life or affect other species of importance to man. The control of environmental pollution requires consideration of air, water, and land.

1.1 APPLICABLE REGULATIONS

In order to prevent, and to provide for abatement and control of any environmental pollution arising from construction activities, the Contractor and his subcontractors in the performance of this contract, shall comply with all applicable Federal, State, and local laws, and regulations concerning environmental pollution control and abatement, and all applicable provisions of the Corps of Engineers Manual, EM 385-1-1, entitled "Safety and Health Requirements Manual" in effect on the date of solicitation as well as the specific requirements stated elsewhere in the contract specifications.

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Implementation; G WA.

Contractor's proposal to put into practice the environmental pollution control.

1.3 NOTIFICATION

The Contracting Officer will notify the Contractor in writing of any non-compliance with the foregoing provisions and the action to be taken. The Contractor shall, after receipt of such notice, immediately take corrective action. Such notice, when delivered to the Contractor or his authorized representative at the site of the work, shall be deemed sufficient notification for the purpose. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order

stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to any such stop orders shall be made the subject of a claim for extension of time or for excess costs or damages by the Contractor unless it was later determined that the Contractor was in compliance.

1.4 SUBCONTRACTORS

Compliance with the provisions of this section by subcontractors will be the responsibility of the Contractor.

1.5 IMPLEMENTATION

Prior to commencement of the work the Contractor will:

1.5.1 Approval

Submit in writing, for approval, his proposals for implementing this section for environmental pollution control;

1.5.2 Environmental Pollution Control

Meet with the representatives of the Contracting Officer to develop mutual understanding relative to compliance with this provision and administration of the environmental pollution control program.

1.6 PROTECTION OF WATER RESOURCES

The Contractor shall not pollute streams, lakes or reservoirs with fuels, oils, bitumens, calcium chloride, acid construction wastes or other harmful materials. It is the responsibility of the Contractor to investigate and comply with all applicable Federal, State, County and Municipal laws concerning pollution of rivers and streams. All work under this contract shall be performed in such a manner that objectionable conditions will not be created in streams through or adjacent to the project areas.

1.7 BURNING

Unless otherwise specified in other sections of the specifications, burning will be allowed only if authorized in writing by the Contracting Officer. However, the specific time, location and manner of burning shall be subject to the approval of the Contracting Officer. Fires shall be guarded at all times and shall be under constant surveillance until they have burned out or have been extinguished. All burning shall be so thorough that the materials will be reduced to ashes.

1.8 DUST CONTROL

The Contractor shall maintain all work areas free from dust which would contribute to air pollution. Approved temporary methods of stabilization consisting of sprinkling, chemical treatment, light bituminous treatment or similar methods will be permitted to control dust. Sprinkling, to be approved, must be repeated at such intervals as to keep all parts of the

disturbed area at least damp at all times, and the Contractor must have sufficient competent equipment on the job to accomplish this if sprinkling is used. Dust control shall be performed as the work proceeds and whenever a dust nuisance or hazard occurs.

1.9 MAINTENANCE OF POLLUTION CONTROL FACILITIES DURING CONSTRUCTION

During the life of this contract, the Contractor shall maintain all facilities constructed for pollution control under this contract as long as the operations creating the particular pollutant are being carried out or until the material concerned has become stabilized to the extent that pollution is no longer being created.

1.10 MEASUREMENT AND PAYMENT

Except as noted in paragraph, PERFORMANCE AND PAYMENT BOND REIMBURSEMENT above, no separate measurement and payment will be made for the work performed in this Section 01562, ENVIRONMENTAL PROTECTION specified herein and all costs in connection therewith shall be considered a subsidiary obligation of the Contractor, and shall be included in the overall cost of the work.

PART 2 PRODUCT NOT APPLICABLE

PART 3 EXECUTION NOT APPLICABLE

-- End of Section --

SECTION 01720

AS-BUILT DRAWINGS - CADD

PART 1 GENERAL

1.1 Preparation

This section covers the preparation of as-built drawings complete, as a requirement of this contract. The terms "drawings," "contract drawings," "drawing files," and "final as-built drawings" refer to a set of computer-aided design and drafting (CADD) contract drawings in electronic file format which are to be used for as-built drawings.

1.2 PROGRESS MARKED UP AS-BUILT PRINTS

The Contractor shall revise one set of paper prints to show the as-built conditions during the prosecution of the project. These as-built marked prints shall be kept current and available on the jobsite at all times. All changes from the contract plans which are made in the work or additional information which might be uncovered in the course of construction shall be accurately and neatly recorded as they occur by means of details and notes. The as-built marked prints will be jointly reviewed for accuracy and completeness by the Contracting Officer and a responsible representative of the construction Contractor prior to submission of each monthly pay estimate. If the Contractor fails to maintain the as-built drawings as specified herein, the Contracting Officer will deduct from the monthly progress payment an amount representing the estimated cost of maintaining the as-built drawings and will continue the monthly deduction of the 10% retainage even after 50% completion of the contract. This monthly deduction will continue until an agreement can be reached between the Contracting Officer and a representative of the Contractor regarding the accuracy and completeness of updated drawings. The prints shall show the following information, but not be limited thereto:

1.2.1 Location and Description

The location and description of any utility lines or other installations of any kind or description known to exist within the construction area. The location includes dimensions to permanent features.

1.2.2 Location and Dimensions

The location and dimensions of any changes within the building or structure.

1.2.3 Corrections

Correct grade, cross section, or alignment of roads, earthwork, structures or utilities if any changes were made from contract plans.

Correct elevations if changes were made in site grading.

1.2.4 Changes

Changes in details of design or additional information obtained from working drawings specified to be prepared and/or furnished by the Contractor; including but not limited to fabrication, erection, installation plans and placing details, pipe sizes, insulation material, dimensions of equipment foundations, etc.

The topography, invert elevations and grades of all drainage installed or affected as a part of the project construction.

All changes or modifications which result from the final inspection.

1.2.5 Options

Where contract drawings or specifications present options, only the option selected for construction shall be shown on the as-built prints.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Progress Prints; G WA.

Preparation of two copies of as-builts from the Contractor to the Contracting Officer for review and approval.

Final Prints; G WA.

SD-03 Product Data

CADD Files.

Shall consist of two sets of completed as-built contract drawings on separate media consisting of both CADD files (compatible with AutoCAD Release 2000 and a CALS Type 1, Group 4, Raster Image File of each contract drawing.

Receipt by the Contractor of the approved marked as-built prints.

1.4 PRELIMINARY SUBMITTAL

At the time of final inspection, the Contractor shall prepare two copies of the progress as-built prints and these shall be delivered to the Contracting Officer for review and approval. These as-built marked prints shall be neat, legible and accurate. The review by Government personnel will be expedited to the maximum extent possible. Upon approval, one copy of the as-built marked prints will be returned to the Contractor for use in preparation of final as-built drawings. If upon review, the as-built marked prints are found to contain errors and/or omissions, they shall be

returned to the Contractor for corrections. The Contractor shall complete the corrections and return the as-built marked prints to the Contracting Officer within ten (10) calendar days.

1.5 DRAWING PREPARATION

1.5.1 As-Built Drawings Approval

Upon approval of the as-built prints submitted, the Contractor will be furnished by the Government one set of contract drawings, with all amendments incorporated, to be used for as-built drawings. These contract drawings will be furnished on CD-ROM. These drawings shall be modified as may be necessary to correctly show all the features of the project as it has been constructed by bringing the contract set into agreement with the approved as-built prints, adding such additional drawings as may be necessary. These drawings are part of the permanent records of this project and the Contractor shall be responsible for the protection and safety thereof until returned to the Contracting Officer. Any drawings damaged or lost by the Contractor shall be satisfactorily replaced by the Contractor at no expense to the Government.

1.5.2 Proficient Personnel

Only personnel proficient in the preparation of engineering CADD drawings to standards satisfactory and acceptable to the Government shall be employed to modify the contract drawings or prepare additional new drawings. All additions and corrections to the contract drawings shall be equal in quality to that of the originals. Line work, line weights, lettering, layering conventions, and symbols shall be the same as the original line work, line weights, lettering, layering conventions, and symbols. If additional drawings are required, they shall be prepared using the specified electronic file format applying the same guidance specified for original drawings. The title block and drawing border to be used for any new as-built drawings shall be identical to that used on the contract drawings. All additions and corrections to the contract drawings shall be accomplished using CADD media files supplied by the Government. These contract drawings will already be compatible with the Using Agency system when received by the Contractor. The Using Agency uses AutoCAD Release 2000 CADD software system. The media files will be supplied on ISO 9660 Format CD-ROM. The Contractor is responsible for providing all program files and hardware necessary to prepare as-built drawings. The Contracting Officer will review all as-built drawings for accuracy and the Contractor shall make all required corrections, changes, additions, and deletions.

1.5.3 Final Revisions

When final revisions have been completed, the cover sheet drawing shall show the wording "RECORD DRAWING AS-BUILT" followed by the name of the General Contractor in letters at least 3/16 inch high. All other contract drawings shall be marked either "As-Built" drawing denoting no revisions on the sheet or "Revised As-Built" denoting one or more revisions. All original contract drawings shall be dated in the revision block (SEE ATTACHMENTS 1 and 2) located at the end of this section. While the title block sample attachments do not depict the contract drawings' title blocks,

the sample revision blocks above these attachments are to be used as guidance in completing the actual contract drawings' revision blocks).

1.6 FINAL REQUIREMENTS

After receipt by the Contractor of the approved marked as-built prints and the original contract drawing files the Contractor will, within 30 days for contracts less than \$5 million or 60 days for contracts \$5 million and above, make the final as-built submittal. The submittal shall consist of the following:

- a) A set of the as-built contract drawings on separate CD's (ISO 9660 Format CD-ROM) consisting of the updated CADD files.
- b) Two sets of full size paper prints (plots) of the completed as-built contract drawings.
 - c) The return of the approved marked as-built prints.

They shall be complete in all details and identical in form and function to the contract drawing files supplied by the Government. Any translations or adjustments necessary to accomplish this is the responsibility of the Contractor. The Government reserves the right to reject any drawing files it deems incompatible with its CADD system. All paper prints, drawing files and storage media submitted will become the property of the Government upon final approval. Failure to submit as-built drawing files and marked prints as required herein shall be cause for withholding any payment due the Contractor under this contract. Approval and acceptance of final as-built drawings shall be accomplished before final payment is made to the Contractor.


1.7 PAYMENT


No separate payment will be made for the as-built drawings required under this contract, and all costs in connection therewith shall be considered a subsidiary obligation of the Contractor.

PART 2 PRODUCT NOT APPLICABLE

PART 3 EXECUTION NOT APPLICABLE

-- End of Section --





Branch

Chief,

Submitted by:

SAMPLE FORMAT OF TITLE BLOCK

SECTION 02220

DEMOLITION

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ENGINEERING MANUALS (EM)

EM 385-1-1

(1996) U.S. Army Corps of Engineers Safety and Health Requirements Manual

1.2 GENERAL REQUIREMENTS

The work includes demolition, salvage of identified items and materials, and removal of resulting rubbish and debris. Rubbish and debris shall be removed from Government property daily, unless otherwise directed, to avoid accumulation at the demolition site. Materials that cannot be removed daily shall be stored in areas specified by the Contracting Officer. In the interest of occupational safety and health, the work shall be performed in accordance with EM 385-1-1, Section 23, Demolition, and other applicable Sections. In the interest of conservation, salvage shall be pursued to the maximum extent possible; salvaged items and materials shall be disposed of as specified.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Work Plan; G WA

The procedures proposed for the accomplishment of the work. The procedures shall provide for safe conduct of the work, including procedures and methods to provide necessary supports, lateral bracing and shoring when required, careful removal and disposition of materials specified to be salvaged, protection of property which is to remain undisturbed, coordination with other work in progress, and timely disconnection of utility services. The procedures shall include a detailed description of the methods and equipment to be used for each operation, and the sequence of operations in accordance with EM 385-1-1.

1.4 DUST CONTROL

The amount of dust resulting from demolition shall be controlled to prevent the spread of dust to occupied portions of the construction site and to avoid creation of a nuisance in the surrounding area. Use of water will not be permitted when it will result in, or create, hazardous or objectionable conditions such as ice, flooding and pollution.

1.5 PROTECTION

1.5.1 Protection of Personnel

During the demolition work the Contractor shall continuously evaluate the condition of the structure being demolished and take immediate action to protect all personnel working in and around the demolition site.

1.5.2 Protection of Existing Property

Before beginning any demolition work, the Contractor shall survey the site and examine the drawings and specifications to determine the extent of the work. The Contractor shall take necessary precautions to avoid damage to existing items to remain in place, to be reused, or to remain the property of the Government; any damaged items shall be repaired or replaced as approved by the Contracting Officer. The Contractor shall coordinate the work of this section with all other work and shall construct and maintain shoring, bracing, and supports as required.

1.5.3 Protection From the Weather

The interior of buildings to remain; salvageable materials and equipment shall be protected from the weather at all times.

1.5.4 Environmental Protection

The work shall comply with the requirements of Section 01562 ENVIRONMENT PROTECTION.

1.6 BURNING

The use of burning at the project site for the disposal of refuse and debris will not be permitted.

1.7 USE OF EXPLOSIVES

Use of explosives will not be permitted.

1.8 AVAILABILITY OF WORK AREA

Work associated with the cleaning of the Air Conveyance System (ACS) shall be performed during non-business hours when the building is not occupied. The Contractor shall provide two weeks advance notice and coordinate the schedule to perform the cleaning of the ACS system.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 EXISTING STRUCTURES

The removal of the existing boiler and the installation of the new boilers shall be through boiler room's double door. The size of the boiler room double door is indicated on the contract drawings. No modification to existing structure is allowed unless pre-authorized by the Contracting Officer.

3.2 UTILITIES

Disconnection of utility services, with related meters and equipment, are specified in Section 01050. When utility lines are encountered that are not indicated on the drawings, the Contracting Officer shall be notified prior to further work in that area.

3.3 DISPOSITION OF MATERIAL

Title to material and equipment to be demolished, except Government salvage and historical items, is vested in the Contractor upon receipt of notice to proceed. The Government will not be responsible for the condition, loss or damage to such property after notice to proceed.

3.3.1 Salvageable Items and Material

Contractor shall salvage items and material to the maximum extent possible.

3.3.1.1 Material Salvaged for the Contractor

Material salvaged for the Contractor shall be stored as approved by the Contracting Officer and shall be removed from Government property before completion of the contract. Material salvaged for the Contractor shall not be sold on the site.

3.4 CLEAN UP

Debris and rubbish shall be removed from basement and similar excavations. Debris shall be removed and transported in a manner that prevents spillage on streets or adjacent areas. Local regulations regarding hauling and disposal shall apply.

-- End of Section --

SECTION 09900

PAINTS AND COATINGS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)

ACGIH TLV-BKLT	(1991-1992) Threshold Limit Values (TLVs)
	for Chemical Substances and Physical
	Agents and Biological Exposure Indices
	(BEIs)

ACGIH TLV-DOC Documentation of Threshold Limit Values and Biological Exposure Indices

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI A13.1 Scheme for Identification of Piping Systems

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D 235	Standard Specification for Mineral Spirits (Petroleum Spirits) (Hydrocarbon Dry Cleaning Solvent)
ASTM D 523	(1999) Standard Test Method for Specular Gloss
ASTM C 669	(1995) Glazing Compounds for Back Bedding and Face Glazing of Metal Sash
ASTM C 920	(1998) Elastomeric Joint Sealants
ASTM D 2092	(1995) Preparation of Zinc-Coated (Galvanized) Steel Surfaces for Painting
ASTM D 2824	(1994) Aluminum-Pigmented Asphalt Roof Coatings, Non-Fibered, Asbestos Fibered, and Fibered Without Asbestos
ASTM D 4214	(1998) Evaluating the Degree of Chalking of Exterior Paint Films
ASTM D 4263	(1983; R 1999) Indicating Moisture in Concrete by the Plastic Sheet Method
ASTM D 4444	(1998) Standard Test Methods for Use and

MPI 11

MPI 13

	Calibration of Hand-Held Moisture Meters
ASTM F 1869	(1998) Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride
CODE OF FEDERAL REGULA	TIONS (CFR)
29 CFR 1910.1000	Air Contaminants
29 CFR 1910.1001	Asbestos, Tremolite, Anthophyllite, and Actinolite
29 CFR 1910.1025	Lead
29 CFR 1926.62	Lead Exposure in Construction
FEDERAL AVIATION ADMIN	ISTRATION (FAA)
FAA AC 70/7460-1	(Rev J) Obstruction Marking and Lighting
FEDERAL STANDARDS (FED	-STD)
FED-STD-313	(Rev. C) Material Safety Data, Transportation Data and Disposal Data for Hazardous Materials Furnished to Government Activities
FED-STD-595	(1989 Rev B) Color
MASTER PAINTERS INSTIT	UTE (MPI)
MPI 1	(2001) Aluminum Paint
MPI 2	(2001) Aluminum Heat Resistant Enamel (up to 427 C and 800 F)
MPI 4	(2001) Interior/Exterior Latex Block Filler
MPI 5	(2001) Exterior Alkyd Wood Primer
MPI 6	(2001) Exterior Latex Wood Primer
MPI 7	(2001) Exterior Oil Wood Primer
MPI 8	(2001) Exterior Alkyd, Flat
MPI 9	(2001) Exterior Alkyd Enamel
MPI 10	(2001) Exterior Latex, Flat

(2001) Exterior Latex, Semi-Gloss

(2001) Exterior Semi-Transparent Stain

	(Solvent Based)
MPI 16	(2001) Exterior Solid Color Latex Stain
MPI 19	(2001) Inorganic Zinc Primer
MPI 21	(2001)Heat Resistant Enamel, Gloss, (Up to 205 C or 400 F)
MPI 22	(2001) High Heat Resistant Coating
MPI 23	(2001) Surface Tolerant Metal Primer
MPI 26	(2001) Cementitious Galvanized Metal Primer
MPI 27	(2001) Exterior/Interior Alkyd Floor Enamel, Gloss
MPI 31	(2001) Polyurethane, Moisture Cured, Clear Gloss
MPI 39	(2001) Interior Latex-based Wood Primer
MPI 42	(2001) Latex Stucco and Masonry Textured Coating
MPI 44	Interior Latex, Gloss Level 2
MPI 45	(2001) Interior Primer Sealer
MPI 46	(2001) Interior Enamel Undercoat
MPI 47	(2001) Interior Alkyd, Semi-Gloss
MPI 48	(2001) Interior Alkyd, Gloss
MPI 49	(2001) Interior Alkyd, Flat
MPI 50	(2001) Interior Latex Primer Sealer
MPI 51	(2001) Interior Alkyd, Eggshell
MPI 52	(2001) Interior Latex, Gloss Level 3
MPI 54	(2001) Interior Latex, Semi-Gloss
MPI 56	(2001) Interior Alkyd Dry Fog/Fall
MPI 57	(2001) Interior Oil Modified Clear Urethane, Satin
MPI 59	(2001) Interior/Exterior Alkyd Porch & Floor Enamel, Low Gloss

MPI 60	(2001) Interior/Exterior Latex Porch & Floor Paint, Low Gloss
MPI 68	(2001) Interior/Exterior Latex Porch & Floor Paint, Gloss
MPI 71	(2001) Polyurethane, Moisture Cured, Clear, Flat
MPI 72	(2001) Polyurethane, Two Component, Pigmented, Gloss
MPI 77	(2001) Epoxy Cold Cured, Gloss
MPI 79	(2001) Marine Alkyd Metal Primer
MPI 90	(2001) Interior Wood Stain, Semi-Transparent
MPI 94	(2001) Exterior Alkyd, Semi-Gloss
MPI 95	(2001) Fast Drying Metal Primer
MPI 101	(2001) Cold Curing Epoxy Primer
MPI 107	(2001) Rust Inhibitive Primer (Water-Based)
MPI 108	(2001) High Build Epoxy Marine Coating
MPI 110	(2001) Interior/Exterior High Performance Acrylic
MPI 113	(2001) Elastomeric Coating
MPI 116	(2001) Epoxy Block Filler
MPI 119	(2001) Exterior Latex, High Gloss (acrylic)
MPI 134	(2001) Waterborne Galvanized Primer
MPI 138	(2001) High Performance Latex, White and Tints - MPI Gloss Level 2
MPI 139	(2001) High Performance Latex, White and Tints - MPI Gloss Level 3
MPI 140	(2001) High Performance Architectural Latex - Gloss Level 4
MPI 141	(2001) High Performance Semigloss Latex, White and Tints - Gloss Level 5
MPI 144	(2001) Institutional Low Odor/VOC Interior Latex, Gloss Level 2

MPI 145	(2001) Institutional Low Odor/VOC Interior Latex, Gloss Level 3
MPI 146	<pre>Institutional Low Odor/VOC Interior Latex - Gloss Level 4 (a 'satin-like' finish)</pre>
MPI 147	(2001) Institutional Low Odor/VOC Interior Latex, Gloss Level 5
COMMERCIAL ITEM DESCRIE	PTION (CID)
CID A-A-2904	Thinner, Paint, Mineral Spirits, Regular and Odorless
MILITARY STANDARDS (MII	J-STD)
MIL-STD-101	(Rev. B) Color Code for Pipelines and for Compressed Gas Cylinders
SCIENTIFIC CERTIFICATION	ON SYSTEMS (SCS)
SCS-EPP-SP01-01	(2001) Environmentally Preferable Product Specification for Architectural and Anti-Corrosive Paints
STEEL STRUCTURES PAINTI	ING COUNCIL (SSPC)
SSPC Guide 6	(1997) Containing Debris Generated During Paint Removal Operations
SSPC Guide 7	(1995) Disposal of Lead-Contaminated Surface Preparation Debris
SSPC QP 1	(1989) Evaluating Qualifications of Painting Contractors (Field Application to Complex Structures)
SSPC PA 1	(2000) Shop, Field, and Maintenance Painting
SSPC PA 3	(1995) Safety in Paint Application
SSPC VIS 1	(1989) Visual Standard for Abrasive Blast Cleaned Steel (Standard Reference Photographs)
SSPC VIS 3	(1993) Visual Standard for Power- and Hand-Tool Cleaned Steel (Standard Reference Photographs)
SSPC VIS 4	(2001) Guide and Reference Photographs for Steel Surfaces Prepared by Waterjetting

SSPC SP 1	(1982) Solvent Cleaning
SSPC SP 2	(1995) Hand Tool Cleaning
SSPC SP 3	(1995) Power Tool Cleaning
SSPC SP 6	(1994) Commercial Blast Cleaning
SSPC SP 7	(1994) Brush-Off Blast Cleaning
SSPC SP 10	(1994) Near-White Blast Cleaning
SSPC SP 12	(1995) Surface Preparation and Cleaning of Steel and Other Hard Materials by High-and Ultra high-Pressure Water Jetting Prior to Recoating
SSPC Paint 18	(1991) Chlorinated Rubber Intermediate Coat Paint

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittals for the Government. The following shall be submitted in accordance with Section 01330 CONTRACT SUBMITTAL PROCEDURES.

SD-02 Shop Drawings

Piping identification

Submit color stencil codes

SD-03 Product Data

Coating; G WA

Manufacturer's Technical Data Sheets

SD-04 Samples

Color; G WA

Submit manufacturer's samples (color chart) of paint colors.

SD-08 Manufacturer's Instructions

Application instructions

Mixing

Detailed mixing instructions, minimum and maximum application temperature and humidity, potlife, and curing and drying times

between coats.

Manufacturer's Material Safety Data Sheets

Submit manufacturer's Material Safety Data Sheets for coatings, solvents, and other potentially hazardous materials, as defined in FED-STD-313.

1.3 REGULATORY REQUIREMENTS

1.3.1 Environmental Protection

In addition to requirements specified elsewhere for environmental protection, provide coating materials that conform to the restrictions of the local Air Pollution Control District and regional jurisdiction. Notify Contracting Officer of any paint specified herein which fails to conform.

1.3.2 Lead Content

Do not use coatings having a lead content over 0.06 percent by weight of nonvolatile content.

1.3.3 Chromate Content

Do not use coatings containing zinc-chromate or strontium-chromate.

1.3.4 Asbestos Content

Materials shall not contain asbestos.

1.3.5 Mercury Content

Materials shall not contain mercury or mercury compounds.

1.3.6 Silica

Abrasive blast media shall not contain free crystalline silica.

1.3.7 Human Carcinogens

Materials shall not contain ACGIH TLV-BKLT and ACGIH TLV-DOC confirmed human carcinogens (A1) or suspected human carcinogens (A2).

1.4 PACKAGING, LABELING, AND STORAGE

Paints shall be in sealed containers that legibly show the contract specification number, designation name, formula or specification number, batch number, color, quantity, date of manufacture, manufacturer's formulation number, manufacturer's directions including any warnings and special precautions, and name and address of manufacturer. Pigmented paints shall be furnished in containers not larger than 5 gallons. Paints and thinners shall be stored in accordance with the manufacturer's written directions, and as a minimum, stored off the ground, under cover, with sufficient ventilation to prevent the buildup of flammable vapors, and at

temperatures between 40 to 95 degrees F.

1.5 SAFETY AND HEALTH

Apply coating materials using safety methods and equipment in accordance with the following:

Work shall comply with applicable Federal, State, and local laws and regulations, and with the ACCIDENT PREVENTION PLAN, including the Activity Hazard Analysis as specified in Section 01525, "Safety Requirements" and in Appendix A of COE EM-385-1-1. The Activity Hazard Analysis shall include analyses of the potential impact of painting operations on painting personnel and on others involved in and adjacent to the work zone.

1.5.1 Safety Methods Used During Coating Application

Comply with the requirements of SSPC PA 3.

1.5.2 Toxic Materials

To protect personnel from overexposure to toxic materials, conform to the most stringent guidance of:

- a. The applicable manufacturer's Material Safety Data Sheets (MSDS) or local regulation.
- b. 29 CFR 1910.1000.
- c. ACGIH TLV-BKLT, threshold limit values.
- d. The appropriate OSHA standard in 29 CFR 1910.1025 and 29 CFR 1926.62 for surface preparation on painted surfaces containing lead. Removal and disposal of coatings which contain lead is specified in Section 13283, "Removal and Disposal of Lead-Containing Paint." Additional guidance is given in SSPC Guide 6 and SSPC Guide 7. Refer to drawings for list of hazardous materials located on this project. Contractor to coordinate paint preparation activities with this specification section.
- e. The appropriate OSHA standards in 29 CFR 1910.1001 for surface preparation of painted surfaces containing asbestos. Removal and disposal of coatings which contain asbestos materials is specified in Section 13281, "Engineering Control of Asbestos Containing Materials." Refer to drawings for list of hazardous materials located on this project. Contractor to coordinate paint preparation activities with this specification section.

1.6 ENVIRONMENTAL CONDITIONS

1.6.1 Coatings

Do not apply coating when air or substrate conditions are:

a. Less than 5 degrees F above dew point;

b. Below 50 degrees F or over 95 degrees F, unless specifically pre-approved by the Contracting Officer and the product manufacturer. Under no circumstances shall application conditions exceed manufacturer recommendations.

1.7 COLOR SELECTION

Colors of finish coats shall be as indicated or specified. Where not indicated or specified, colors shall be selected by the Contracting Officer. Manufacturers' names and color identification are used for the purpose of color identification only. Named products are acceptable for use only if they conform to specified requirements. Products of other manufacturers are acceptable if the colors indicated and the product conforms to specified requirements.

Tint each coat progressively darker to enable confirmation of the number of coats.

The Contractor shall submit his color chart together with a list of all items and areas to be painted for color selection by the Contracting Officer.

1.8 LOCATION AND SURFACE TYPE TO BE PAINTED

1.8.1 Painting Included

Where a space or surface is indicated to be painted, include the following unless indicated otherwise.

- a. Surfaces behind portable objects and surface mounted articles readily detachable by removal of fasteners, such as screws and bolts.
- b. New factory finished surfaces that require identification or color coding and factory finished surfaces that are damaged during performance of the work.
- c. Existing coated surfaces that are damaged during performance of the work.

1.8.1.1 Interior Painting

Includes new surfacesand existing coated surfaces of the building and appurtenances as indicated and existing coated surfaces made bare by cleaning operations. Where a space or surface is indicated to be painted, include the following items, unless indicated otherwise.

- a. Exposed columns, girders, beams, joists, and metal deck; and
- b. Other contiguous surfaces.

1.8.2 Painting Excluded

Do not paint the following unless indicated otherwise.

- a. Surfaces concealed and made inaccessible by panelboards, fixed ductwork, machinery, and equipment fixed in place.
- b. Surfaces in concealed spaces. Concealed spaces are defined as enclosed spaces above suspended ceilings, furred spaces, attic spaces, crawl spaces, elevator shafts and chases.
- c. Steel to be embedded in concrete.
- d. Copper, stainless steel, aluminum, brass, and lead except existing coated surfaces.
- e. Hardware, fittings, and other factory finished items.

1.8.3 Mechanical and Electrical Painting

Includes field coating of interior and exterior new and existing surfaces.

- a. Where a space or surface is indicated to be painted, include the following items unless indicated otherwise.
 - (1) Exposed piping, conduit, and ductwork;
 - (2) Supports, hangers, air grilles, and registers;
 - (3) Miscellaneous metalwork and insulation coverings.
- b. Do not paint the following, unless indicated otherwise:
 - (1) New zinc-coated, aluminum, and copper surfaces under insulation
 - (2) New aluminum jacket on piping
 - (3) New interior ferrous piping under insulation.

PART 2 PRODUCTS

2.1 MATERIALS

Conform to the coating specifications and standards referenced in PART 3. Submit manufacturer's technical data sheets for specified coatings and solvents.

PART 3 EXECUTION

3.1 PROTECTION OF AREAS AND SPACES NOT TO BE PAINTED

Prior to surface preparation and coating applications, remove, mask, or otherwise protect, hardware, hardware accessories, machined surfaces, radiator covers, plates, lighting fixtures, public and private property, and other such items not to be coated that are in contact with surfaces to

be coated. Following completion of painting, workmen skilled in the trades involved shall reinstall removed items. Restore surfaces contaminated by coating materials, to original condition and repair damaged items.

3.2 SURFACE PREPARATION

Remove dirt, splinters, loose particles, grease, oil, disintegrated coatings, and other foreign matter and substances deleterious to coating performance as specified for each substrate before application of paint or surface treatments. Oil and grease shall be removed prior to mechanical cleaning. Cleaning shall be programmed so that dust and other contaminants will not fall on wet, newly painted surfaces. Exposed ferrous metals such as nail heads on or in contact with surfaces to be painted with water-thinned paints, shall be spot-primmed with a suitable corrosion-inhibitive primer capable of preventing flash rusting and compatible with the coating specified for the adjacent areas.

3.2.1 Additional Requirements for Preparation of Surfaces With Existing Coatings

Before application of coatings, perform the following on surfaces covered by soundly-adhered coatings, defined as those which cannot be removed with a putty knife:

- a. Wipe previously painted surfaces to receive solvent-based coatings, except stucco and similarly rough surfaces clean with a clean, dry cloth saturated with mineral spirits, ASTM D 235. Allow surface to dry. Wiping shall immediately precede the application of the first coat of any coating, unless specified otherwise.
- b. Sand existing glossy surfaces to be painted to reduce gloss. Brush, and wipe clean with a damp cloth to remove dust.
- c. The requirements specified are minimum. Comply also with the application instructions of the paint manufacturer.
- d. Previously painted surfaces specified to be repainted, damaged during construction shall be thoroughly cleaned of all grease, dirt, dust or other foreign matter.
- e. Blistering, cracking, flaking and peeling or other deteriorated coatings shall be removed.
- f. Edges of chipped paint shall be feather edged and sanded smooth.
- g. Rusty metal surfaces shall be cleaned as per SSPC requirements. Solvent, mechanical, or chemical cleaning methods shall be used to provide surfaces suitable for painting.
- h. New, proposed coatings shall be compatible with existing coatings.

3.3 PREPARATION OF METAL SURFACES

3.3.1 Existing and New Ferrous Surfaces

a. Ferrous Surfaces including Shop-coated Surfaces and Small Areas That Contain Rust, Mill Scale and Other Foreign Substances: Solvent clean or detergent wash in accordance with SSPC SP 1 to remove oil and grease. Where shop coat is missing or damaged, clean according to SSPC SP 2. Brush-off blast remaining surface in accordance with SSPC SP 7; Shop-coated ferrous surfaces shall be protected from corrosion by treating and touching up corroded areas immediately upon detection.

3.3.2 Non-Ferrous Metallic Surfaces

Aluminum and aluminum-alloy, lead, copper, and other nonferrous metal surfaces.

a. Surface Cleaning: Solvent clean in accordance with SSPC SP 1 and wash with mild non-alkaline detergent to remove dirt and water soluble contaminants.

3.4 APPLICATION

3.4.1 Coating Application

Painting practices shall comply with applicable federal, state and local laws enacted to insure compliance with Federal Clean Air Standards. Apply coating materials in accordance with SSPC PA 1. SSPC PA 1 methods are applicable to all substrates, except as modified herein.

At the time of application, paint shall show no signs of deterioration. Uniform suspension of pigments shall be maintained during application.

Unless otherwise specified or recommended by the paint manufacturer, paint may be applied by brush, roller, or spray. Rollers for applying paints and enamels shall be of a type designed for the coating to be applied and the surface to be coated.

Paints, except water-thinned types, shall be applied only to surfaces that are completely free of moisture as determined by sight or touch.

Thoroughly work coating materials into joints, crevices, and open spaces. Special attention shall be given to insure that all edges, corners, crevices, welds, and rivets receive a film thickness equal to that of adjacent painted surfaces.

Each coat of paint shall be applied so dry film shall be of uniform thickness and free from runs, drops, ridges, waves, pinholes or other voids, laps, brush marks, and variations in color, texture, and finish. Hiding shall be complete.

Touch up damaged coatings before applying subsequent coats. Interior areas shall be broom clean and dust free before and during the application of coating material.

- a. Drying Time: Allow time between coats, as recommended by the coating manufacturer, to permit thorough drying, but not to present topcoat adhesion problems. Provide each coat in specified condition to receive next coat.
- b. Primers, and Intermediate Coats: Do not allow primers or intermediate coats to dry more than 30 days, or longer than recommended by manufacturer, before applying subsequent coats. Follow manufacturer's recommendations for surface preparation if primers or intermediate coats are allowed to dry longer than recommended by manufacturers of subsequent coatings. Each coat shall cover surface of preceding coat or surface completely, and there shall be a visually perceptible difference in shades of successive coats.
- c. Finished Surfaces: Provide finished surfaces free from runs, drops, ridges, waves, laps, brush marks, and variations in colors.

3.4.2 Mixing and Thinning of Paints

Reduce paints to proper consistency by adding fresh paint, except when thinning is mandatory to suit surface, temperature, weather conditions, application methods, or for the type of paint being used. Obtain written permission from the Contracting Officer to use thinners. The written permission shall include quantities and types of thinners to use.

3.4.3 Coating Systems

a. Systems by Substrates: Apply coatings that conform to the respective specifications listed in the following Tables:

Table

- Division 3. Interior Concrete Paint Table
- Division 4. Interior Concrete Masonry Units Paint Table
- Division 5. Interior Metal, Ferrous and Non-Ferrous Paint Table
- b. Minimum Dry Film Thickness (DFT): Apply paints, primers, varnishes, enamels, undercoats, and other coatings to a minimum dry film thickness of 1.5 mil each coat unless specified otherwise in the Tables. Coating thickness where specified, refers to the minimum dry film thickness.
- c. Coatings for Surfaces Not Specified Otherwise: Coat surfaces which have not been specified, the same as surfaces having similar conditions of exposure.
- d. Existing Surfaces Damaged During Performance of the Work, Including New Patches In Existing Surfaces: Coat surfaces with the following:
 - (1) One coat of primer.
 - (2) One coat of undercoat or intermediate coat.

- (3) One topcoat to match adjacent surfaces.
- e. Existing Coated Surfaces To Be Painted: Apply coatings conforming to the respective specifications listed in the Tables herein, except that pretreatments, sealers and fillers need not be provided on surfaces where existing coatings are soundly adhered and in good condition. Do not omit undercoats or primers.

3.5 COATING SYSTEMS FOR METAL

Apply coatings of Tables in Division 5 for Exterior and Interior.

- a. Apply specified ferrous metal primer on the same day that surface is cleaned, to surfaces that meet all specified surface preparation requirements at time of application.
- b. Pipes and Tubing: The semitransparent film applied to some pipes and tubing at the mill is not to be considered a shop coat, but shall be overcoated with the specified ferrous-metal primer prior to application of finish coats.

3.6 COATING SYSTEMS FOR CONCRETE AND CEMENTITIOUS SUBSTRATES

Apply coatings of Tables in Division 3 and 4.

3.7 PIPING IDENTIFICATION

Piping Identification, Including Surfaces In Concealed Spaces: Provide in accordance with MIL-STD-101. Place stenciling in clearly visible locations. On piping not covered by MIL-STD-101, stencil approved names or code letters, in letters a minimum of 1/2 inch high for piping and a minimum of 2 inches high elsewhere. Stencil arrow-shaped markings on piping to indicate direction of flow using black stencil paint.

3.8 INSPECTION AND ACCEPTANCE

In addition to meeting previously specified requirements, demonstrate mobility of moving components, including swinging and sliding doors, cabinets, and windows with operable sash, for inspection by the Contracting Officer. Perform this demonstration after appropriate curing and drying times of coatings have elapsed and prior to invoicing for final payment.

3.9 PAINT TABLES

All DFT's are minimum values.

3.9.1 INTERIOR PAINT TABLES

DIVISION 3: INTERIOR CONCRETE PAINT TABLE

A. Existing, previously painted Concrete, vertical surfaces, not specified otherwise:

DIVISION 3: INTERIOR CONCRETE PAINT TABLE

1. Latex

New; MPI INT 3.1A-G5 (Semigloss) / Existing; MPI RIN 3.1A-G5 (Semigloss)

Primer: Intermediate: Topcoat: MPI 50 MPI 54 MPI 54

System DFT: 4 mils

- B. New and uncoated existing and Existing, previously painted Concrete high-humidity areas not otherwise specified except floors:
- 1. Alkyd

MPI INT 3.1D-G5 (Semigloss) / Existing; RIN 3.1D-G5 (Semigloss)

Primer: Intermediate: Topcoat: MPI 50 MPI 47 MPI 47

System DFT: 4.5 mils

MPI INT 3.1D-G6 (Gloss) / Existing; RIN 3.1D-G6 (Gloss)

Primer: Intermediate: Topcoat: MPI 50 MPI 48 MPI 48

System DFT: 4.5 mils

DIVISION 4: INTERIOR CONCRETE MASONRY UNITS PAINT TABLE

- A. Existing, previously painted Concrete masonry:
- 1. High Performance Architectural Latex

MPI RIN 4.2K-G5 (Semigloss)

Spot Primer: Intermediate: Topcoat: MPI 50 MPI 141 MPI 141

System DFT: 4.5 mils

- B. Existing, previously painted, concrete masonry units in high humidity areas unless otherwise specified:
- 1. Alkyd

MPI RIN 4.2C-G6 (Gloss)

Spot Primer: Intermediate: Topcoat: MPI 50 MPI 48 MPI 48

System DFT: 4.5 mils

2. Epoxy

MPI RIN 4.2D-G6 (Gloss)

Spot Primer: Intermediate: Topcoat: MPI 77 MPI 77 MPI 77

System DFT: 5 mils

DIVISION 5: INTERIOR METAL, FERROUS AND NON-FERROUS PAINT TABLE

INTERIOR STEEL / FERROUS SURFACES

INTERIOR STEEL / FERROUS SURFACES

- A. Metal, Mechanical, Electrical, Surfaces adjacent to painted surfaces (Match surrounding finish), exposed copper piping, and miscellaneous metal items not otherwise specified:
 - 1. Alkyd

MPI INT 5.1E-G6 (Gloss)

Primer: Intermediate: Topcoat: MPI 79 MPI 48 MPI 48

System DFT: 5.25 mils

-- End of Section --

SECTION 15080

THERMAL INSULATION FOR MECHANICAL SYSTEMS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only. At the discretion of the Government, the manufacturer of any material supplied will be required to furnish test reports pertaining to any of the tests necessary to assure compliance with the standard or standards referenced in this specification.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 167	(1999) Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
ASTM A 580/A 580M	(1998) Stainless Steel Wire
ASTM B 209	(1996) Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B 209M	(2000) Aluminum and Aluminum-Alloy Sheet and Plate (Metric)
ASTM C 195	(1995) Mineral Fiber Thermal Insulating Cement
ASTM C 449/C 449M	(1995) Mineral Fiber Hydraulic-Setting Thermal Insulating and Finishing Cement
ASTM C 518	(1998) Steady-State Heat Flux Measurements and Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus
ASTM C 533	(1995) Calcium Silicate Block and Pipe Thermal Insulation
ASTM C 534	(1999) Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form
ASTM C 547	(1995) Mineral Fiber Pipe Insulation
ASTM C 552	(2000) Cellular Glass Thermal Insulation
ASTM C 553	(1999) Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications

ASTM C 591	(1994) Unfaced Preformed Rigid Cellular Polyisocyanurate Thermal Insulation
ASTM C 610	(1999) Molded Expanded Perlite Block and Pipe Thermal Insulation
ASTM C 612	(2000) Mineral Fiber Block and Board Thermal Insulation
ASTM C 647	(1995) Properties and Tests of Mastics and Coating Finishes for Thermal Insulation
ASTM C 665	(1998) Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing
ASTM C 795	(1992; R 1998el) Thermal Insulation for Use in Contact With Austenitic Stainless Steel
ASTM C 916	(1985; R 1996el) Adhesives for Duct Thermal Insulation
ASTM C 920	(1998) Elastomeric Joint Sealants
ASTM C 921	(1989; R 1996) Determining the Properties of Jacketing Materials for Thermal Insulation
ASTM C 1126	(1998) Faced or Unfaced Rigid Cellular Phenolic Thermal Insulation
ASTM C 1136	(1995) Flexible, Low Permeance Vapor Retarders for Thermal Insulation
ASTM C 1290	(1995) Flexible Fibrous Glass Blanket Insulation Used to Externally Insulate HVAC Ducts
ASTM E 84	(2000a) Surface Burning Characteristics of Building Materials
ASTM E 96	(2000) Water Vapor Transmission of Materials

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-69 (1996) Pipe Hangers and Supports - Selection and Application

MIDWEST INSULATION CONTRACTORS ASSOCIATION (MICA)

MICA Insulation Stds (1993) National Commercial & Industrial

Insulation Standards

1.2 SYSTEM DESCRIPTION

Field-applied insulation and accessories on mechanical systems shall be as specified herein; factory-applied insulation is specified under the piping, duct or equipment to be insulated.

1.3 GENERAL QUALITY CONTROL

1.3.1 Standard Products

Materials shall be the standard products of manufacturers regularly engaged in the manufacture of such products and shall essentially duplicate items that have been in satisfactory use for at least 2 years prior to bid opening.

1.3.2 Installer's Qualifications

Qualified installers shall have successfully completed three or more similar type jobs within the last 5 years.

1.3.3 Surface Burning Characteristics

Unless otherwise specified, insulation not covered with a jacket shall have a flame spread index no higher than 75 and a smoke developed index no higher than 150. Insulation systems which are located in air plenums, in ceiling spaces, and in attic spaces shall have a flame spread index no higher than 25 and a smoke developed index no higher than 50. Insulation materials located exterior to the building perimeter are not required to be fire-rated. Flame spread and smoke developed indexes shall be determined by ASTM E 84. Insulation shall be tested in the same density and installed thickness as the material to be used in the actual construction. Material supplied by a manufacturer with a jacket shall be tested as a composite material. Jackets , facings, and adhesives shall have a flame spread index no higher than 25 and a smoke developed index no higher than 50 when tested in accordance with ASTM E 84.

1.3.4 Identification of Materials

Packages or standard containers of insulation, jacket material, cements, adhesives, and coatings delivered for use, and samples required for approval shall have manufacturer's stamp or label attached giving the name of the manufacturer and brand, and a description of the material.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-04 Samples

Thermal Insulation Materials; G WA.

A complete list of materials, including manufacturer's descriptive technical literature, performance data, catalog cuts, and installation instructions. The product number, k-value, thickness and furnished accessories for each mechanical system requiring insulation shall be included. Materials furnished under this section of the specification shall be submitted at one time.

1.5 STORAGE

Materials shall be delivered in the manufacturer's unopened containers. Materials delivered and placed in storage shall be provided with protection from weather, humidity, dirt, dust and other contaminants. Insulation material and supplies that become dirty, dusty, wet, or otherwise contaminated may be rejected by the Contracting Officer.

PART 2 PRODUCTS

2.1 GENERAL MATERIALS

Materials shall be compatible and shall not contribute to corrosion, soften, or otherwise attack surfaces to which applied in either the wet or dry state. Materials to be used on stainless steel surfaces shall meet ASTM C 795 requirements. Materials shall be asbestos free and conform to the following:

2.1.1 Adhesives

2.1.1.1 Acoustical Lining Insulation Adhesive

Adhesive shall be a nonflammable, fire-resistant adhesive conforming to ASTM C 916, Type I.

2.1.1.2 Mineral Fiber Insulation Cement

Cement shall be in accordance with ASTM C 195.

2.1.1.3 Lagging Adhesive

Lagging is the material used for thermal insulation, especially around a cylindrical object. This may include the insulation as well as the cloth/material covering the insulation. Lagging adhesives shall be nonflammable and fire-resistant and shall have a flame spread rating no higher than 25 and a smoke developed rating no higher than 50 when tested in accordance with ASTM E 84. Adhesive shall be pigmented [white] [red] and be suitable for bonding fibrous glass cloth to faced and unfaced fibrous glass insulation board; for bonding cotton brattice cloth to faced and unfaced fibrous glass insulation board; for sealing edges of and bounding fibrous glass tape to joints of fibrous glass board; for bonding lagging cloth to thermal insulation; or for attaching fibrous glass insulation to metal surfaces. Lagging adhesives shall be applied in strict accordance with the manufacturer's recommendations.

2.1.2 Contact Adhesive

Adhesive may be dispersed in a nonhalogenated organic solvent or, dispersed in a nonflammable organic solvent which shall not have a fire point below 200 degrees F. The adhesive shall not adversely affect, initially or in service, the insulation to which it is applied, nor shall it cause any corrosive effect on metal to which it is applied. Any solvent dispersing medium or volatile component of the adhesive shall have no objectionable odor and shall not contain any benzene or carbon tetrachloride. The dried adhesive shall not emit nauseous, irritating, or toxic volatile matters or aerosols when the adhesive is heated to any temperature up to 212 degrees F. The adhesive shall be nonflammable and fire resistant.

2.1.3 Caulking

ASTM C 920, Type S, Grade NS, Class 25, Use A.

2.1.4 Corner Angles

Nominal 0.016 inch aluminum 1×1 inch with factory applied kraft backing. Aluminum shall be ASTM B 209, Alloy 3003, 3105, or 5005.

2.1.5 Finishing Cement

Mineral fiber hydraulic-setting thermal insulating cement ASTM C 449/C 449M. All cements that may come in contact with Austenitic stainless steel must include testing per ASTM C 795.

2.1.6 Fibrous Glass Cloth and Glass Tape

Fibrous glass cloth and glass tape shall have flame spread and smoke developed ratings of no greater than 25/50 when measured in accordance with ASTM E 84. Tape shall be 4 inch wide rolls.

2.1.7 Staples

Outward clinching type monel ASTM A 167, Type 304 or 316 stainless steel. Monel is a nickel rich alloy which has high strength, high ductility, and excellent resistance to corrosion.

2.1.8 Jackets

ASTM C 921, Type I, maximum moisture vapor transmission 0.02 perms, (measured before factory application or installation), minimum puncture resistance 50 Beach units on all surfaces except concealed ductwork, where a minimum puncture resistance of 25 Beach units is acceptable. Minimum tensile strength, 35 pound/inch width. ASTM C 921, Type II, minimum puncture resistance 25 Beach units, tensile strength minimum 20 pound/inch width. Jackets used on insulation exposed in finished areas shall have white finish suitable for painting without sizing. Based on the application, insulation materials which require factory applied jackets are mineral fiber, cellular glass, and phenolic foam. All non-metallic jackets shall have a maximum flame spread index of 25 and a maximum smoke developed

index of 50 when tested in accordance with ASTM E 84.

2.1.8.1 White Vapor Retarder All Service Jacket (ASJ)

For use on hot/cold pipes, ducts, or equipment vapor retarder jackets used on insulation exposed in finished areas shall have white finish suitable for painting without sizing.

2.1.8.2 Aluminum Jackets

Aluminum jackets shall be corrugated, embossed or smooth sheet, 0.016 inch nominal thickness; ASTM B 209, Temper H14, Temper H16, Alloy 3003, 5005, or 3105 with factory applied moisture retarder. Corrugated aluminum jacket shall not be used outdoors. Aluminum jacket securing bands shall be Type 304 stainless steel, 0.015 inch thick, 1/2 inch wide for pipe under 12 inch diameter and 3/4 inch wide for pipe over 12 inch and larger diameter. Aluminum jacket circumferential seam bands shall be 2 x 0.016 inch aluminum matching jacket material. Bands for insulation below ground shall be 3/4 x 0.020 inch) thick stainless steel, or fiberglass reinforced tape. The jacket may, at the option of the Contractor, be provided with a factory fabricated Pittsburg or "Z" type longitudinal joint. When the "Z" joint is used, the bands at the circumferential joints shall be designed by the manufacturer to seal the joints and hold the jacket in place.

2.1.8.3 Polyvinyl Chloride (PVC) Jackets

Polyvinyl chloride (PVC) jacket and fitting covers shall have high impact strength, UV resistant rating or treatment and moderate chemical resistance with minimum thickness 0.030 inch.

2.1.9 Vapor Retarder Coating

The vapor retarder coating shall be fire and water resistant and appropriately selected for either outdoor or indoor service. Color shall be white. The water vapor permeance of the compound shall be determined according to procedure B of ASTM E 96 utilizing apparatus described in ASTM E 96. The coating shall be a nonflammable, fire resistant type. All other application and service properties shall be in accordance with ASTM C 647.

2.1.9.1 Vapor Retarder Required

ASTM C 1136, Type I, maximum moisture vapor transmission 0.02 perms, minimum puncture resistance 50 Beach units on all surfaces except concealed ductwork, where Type II, maximum moisture vapor transmission 0.02 perms, a minimum puncture resistance of 25 Beach units is acceptable.

2.1.9.2 Vapor Retarder Not Required

ASTM C 1136, Type III, maximum moisture vapor transmission 0.10 perms, minimum puncture resistance 50 Beach units on all surfaces except ductwork, where Type IV, maximum moisture vapor transmission 0.10, a minimum puncture resistance of 25 Beach units is acceptable.

2.1.10 Wire

Soft annealed ASTM A 580/A 580M Type 302, 304 or 316 stainless steel, 16 or 18 gauge.

2.2 PIPE INSULATION MATERIALS

Insulation materials shall conform to EPA requirements in accordance with Section 01670 RECYCLED/RECOVERED MATERIALS. Pipe insulation materials shall be limited to those listed herein and shall meet the following requirements:

2.2.1 Aboveground Cold Pipeline

Insulation for minus 30 degrees to plus 60 degrees F for outdoor, indoor, exposed or concealed applications, shall be as follows:

- a. Cellular Glass: ASTM C 552, Type II, and Type III. Supply the insulation with manufacturer's recommended factory applied jacket.
- b. Flexible Elastomeric Cellular Insulation: ASTM C 534, Type I or II. Type II shall have vapor retarder skin on both sides of the insulation.
- c. Phenolic Insulation: ASTM C 1126, Type III. Phenolic insulations shall comply with ASTM C 795 and with the ASTM C 665 paragraph Corrosiveness. Supply the insulation with manufacturer's recommended factory applied jacket.
- d. Mineral Fiber: ASTM C 547
- e. Polyisocyanurate Insulation: ASTM C 591, type I. Supply the insulation with manufacturer's recommended factory applied jacket.

2.2.2 Aboveground Hot Pipeline

Insulation for above 60 degrees F, for outdoor, indoor, exposed or concealed applications shall meet the following requirements. Supply the insulation with manufacturers recommended factory applied jacket.

- a. Mineral Fiber: ASTM C 547, Types I, II or III, supply the insulation with manufacturers recommended factory applied jacket.
- b. Calcium Silicate: ASTM C 533, Type I indoor only, or outdoors above 250 degrees F pipe temperature.
- c. Cellular Glass: ASTM C 552, Type II and Type III. Supply the insulation with manufacturers recommended factory applied jacket.
- d. Flexible Elastomeric Cellular Insulation: ASTM C 534, Type I or II to 200 degrees F service.
- e. Phenolic Insulation: ASTM C 1126 Type III to 250 F service shall comply with ASTM C 795. Supply the insulation with manufacturers recommended factory applied jacket.

- f. Perlite Insulation: ASTM C 610
- g. Polyisocyanurate Insulation: ASTM C 591, Type 1, to 300 degrees F service. Supply the insulation with manufacturer's recommended factory applied jacket.

2.3 DUCT INSULATION MATERIALS

Duct insulation materials shall be limited to those listed herein and shall meet the following requirements:

2.3.1 Rigid Mineral Fiber

ASTM C 612, Type IA, IB, II, III, & IV.

2.3.2 Flexible Mineral Fiber

ASTM C 553, Type I,or Type II up to 250 F. ASTM C 1290 Type III.

2.3.3 Cellular Glass

ASTM C 552, Type I.

2.3.4 Phenolic Foam

ASTM C 1126 Type II, shall comply with ASTM C 795.

2.3.5 Flexible Elastomeric Cellular

ASTM C 534 Type II.

2.3.6 Polyisocyanurate

ASTM C 591, Type 1. Supply the insulation with manufacturer's recommended factory applied jacket.

2.4 EQUIPMENT INSULATION MATERIALS

Equipment insulation materials shall be limited to those listed herein and shall meet the following requirements:

2.4.1 Cold Equipment Insulation

For temperatures below 60 degrees F.

2.4.1.1 Cellular Glass

ASTM C 552, Type I, Type III, or Type IV as required.

2.4.1.2 Flexible Elastomeric Cellular Insulation

ASTM C 534, Type II.

2.4.1.3 Phenolic Foam

ASTM C 1126 Type II shall comply with ASTM C 795.

2.4.1.4 Polyisocyanurate Foam

ASTM C 591, Type I. Supply the insulation with manufacturer's factory applied jacket.

2.4.2 Hot Equipment Insulation

For temperatures above 60 degrees F.

2.4.2.1 Rigid Mineral Fiber

ASTM C 612, Type IA, IB, II, III, IV, or V as required for temperature encountered to 1800 degrees F.

2.4.2.2 Flexible Mineral Fiber

ASTM C 553, Type I, II, III, IV, V, VI or VII as required for temperature encountered to 1200 degrees F.

2.4.2.3 Calcium Silicate

ASTM C 533, Type I, indoors only, or outdoors above 250 degrees F. Pipe shape may be used on diesel engine exhaust piping and mufflers to 1200 degrees F.

2.4.2.4 Cellular Glass

ASTM C 552, Type I, Type III, or Type IV as required.

2.4.2.5 Flexible Elastomeric Cellular Insulation

ASTM C 534, Type II, to 200 degrees F.

2.4.2.6 Phenolic Foam

ASTM C 1126 Type II to 250 degrees F shall comply with ASTM C 795.

2.4.2.7 Molded Expanded Perlite

ASTM C 610.

2.4.2.8 Polyisocyanurate Foam:

ASTM C 591, Type I. Supply the insulation with manufacturer's recommended factory applied jacket.

PART 3 EXECUTION

3.1 APPLICATION - GENERAL

Insulation shall only be applied to unheated and uncooled piping and equipment. Flexible elastomeric cellular insulation shall not be compressed at joists, studs, columns, ducts, hangers, etc. The insulation shall not pull apart after one hour period; any insulation found to pull apart after one hour shall be replaced.

3.1.1 Installation

Except as otherwise specified, material shall be installed in accordance with the manufacturer's written instructions. Insulation materials shall not be applied until tests specified in other sections of this specification are completed. Material such as rust, scale, dirt and moisture shall be removed from surfaces to receive insulation. Insulation shall be kept clean and dry. Insulation shall not be removed from its shipping containers until the day it is ready to use and shall be returned to like containers or equally protected from dirt and moisture at the end of each workday. Insulation that becomes dirty shall be thoroughly cleaned prior to use. If insulation becomes wet or if cleaning does not restore the surfaces to like new condition, the insulation will be rejected, and shall be immediately removed from the jobsite. Joints shall be staggered on multi layer insulation. Mineral fiber thermal insulating cement shall be mixed with demineralized water when used on stainless steel surfaces. Insulation, jacketing and accessories shall be installed in accordance with MICA Insulation Stds standard plates except where modified herein or on the drawings.

3.1.2 Painting and Finishing

Painting shall be as specified in Section 09900 PAINTS AND COATINGS.

3.1.3 Installation of Flexible Elastomeric Cellular Insulation

Flexible elastomeric cellular insulation shall be installed with seams and joints sealed with rubberized contact adhesive. Insulation with pre-applied adhesive is not permitted. Flexible elastomeric cellular insulation shall not be used on surfaces greater than 200 degrees F. Seams shall be staggered when applying multiple layers of insulation. Insulation exposed to weather and not shown to have jacketing shall be protected with two coats of UV resistant finish as recommended by the manufacturer after the adhesive is dry. A brush coating of adhesive shall be applied to both butt ends to be joined and to both slit surfaces to be sealed. The adhesive shall be allowed to set until dry to touch but tacky under slight pressure before joining the surfaces. Insulation seals at seams and joints shall not be capable of being pulled apart one hour after application. Insulation that can be pulled apart one hour after installation shall be replaced.

3.1.4 Welding

No welding shall be done on piping, duct or equipment without written approval of the Contracting Officer. The capacitor discharge welding process may be used for securing metal fasteners to duct.

3.1.5 Pipes/Ducts/Equipment which Require Insulation

Insulation is required on all new hot and coldpipes, ducts, or equipment, except for omitted items, as specified.

3.2 PIPE INSULATION INSTALLATION

3.2.1 Pipe Insulation

3.2.1.1 General

Pipe insulation shall be installed on all new aboveground hot and cold pipeline systems as specified below to form a continuous thermal retarder, including straight runs, fittings and appurtenances unless specified otherwise. Installation shall be with full length units of insulation and using a single cut piece to complete a run. Cut pieces or scraps abutting each other shall not be used.

3.2.1.2 Pipes Passing Through Walls, Roofs, and Floors

- a. Pipe insulation shall be continuous through the sleeve.
- b. An aluminum jacket with factory applied moisture retarder shall be provided over the insulation wherever penetrations require sealing.
- c. Where penetrating interior walls, the aluminum jacket shall extend 2 inches beyond either side of the wall and shall be secured on each end with a band.
- d. Where penetrating exterior walls, the aluminum jacket required for pipe exposed to weather shall continue through the sleeve to a point 2 inches beyond the interior surface of the wall.
- e. Where penetrating roofs, pipe shall be insulated as required for interior service to a point flush with the top of the flashing and sealed with vapor retarder coating. The insulation for exterior application shall butt tightly to the top of flashing and interior insulation. The exterior aluminum jacket shall extend 2 inches down beyond the end of the insulation to form a counter flashing. The flashing and counter flashing shall be sealed underneath with caulking.

3.2.1.3 Pipes Passing Through Hangers

- a. Insulation, whether hot or cold application, shall be continuous through hangers. All horizontal pipes 2 inches and smaller shall be supported on hangers with the addition of a Type 40 protection shield to protect the insulation in accordance with MSS SP-69. Whenever insulation shows signs of being compressed, or when the insulation or jacket shows visible signs of distortion at or near the support shield, insulation inserts as specified below for piping larger than 2 inches shall be installed.
- b. Horizontal pipes larger than 2 inches at 60 degrees F and above shall be supported on hangers in accordance with MSS SP-69, and

Section 15400 PLUMBING, GENERAL PURPOSE.

- c. Horizontal pipes larger than 2 inches and below 60 degrees F shall be supported on hangers with the addition of a Type 40 protection shield in accordance with MSS SP-69. An insulation insert of cellular glass or calcium silicate shall be installed above each shield. The insert shall cover not less than the bottom 180 degree arc of the pipe. Inserts shall be the same thickness as the insulation, and shall extend 2 inches on each end beyond the protection shield. When insulation inserts are required per the above, and the insulation thickness is less than 1 inch, wooden or cork dowels or blocks may be installed between the pipe and the shield to prevent the weight of the pipe from crushing the insulation, as an option to installing insulation inserts. The insulation jacket shall be continuous over the wooden dowel, wooden block, or insulation insert.
- d. Vertical pipes shall be supported with either Type 8 or Type 42 riser clamps with the addition of two Type 40 protection shields in accordance with MSS SP-69 covering the 360 degree arc of the insulation. An insulation insert of cellular glass or calcium silicate shall be installed between each shield and the pipe. The insert shall cover the 360 degree arc of the pipe. Inserts shall be the same thickness as the insulation, and shall extend 2 inches on each end beyond the protection shield. When insulation inserts are required per the above, and the insulation thickness is less than 1 inch, wooden or cork dowels or blocks may be installed between the pipe and the shield to prevent the hanger from crushing the insulation, as an option instead of installing insulation inserts. The insulation jacket shall be continuous over the wooden dowel, wooden block, or insulation insert. The vertical weight of the pipe shall be supported with hangers located in a horizontal section of the pipe. When the pipe riser is longer than 30 feet, the weight of the pipe shall be additionally supported with hangers in the vertical run of the pipe which are directly clamped to the pipe, penetrating the pipe insulation. These hangers shall be insulated and the insulation jacket sealed as indicated herein for anchors in a similar service.
- e. Inserts shall be covered with a jacket material of the same appearance and quality as the adjoining pipe insulation jacket, shall overlap the adjoining pipe jacket 1-1/2 inches, and shall be sealed as required for the pipe jacket. The jacket material used to cover inserts in flexible elastomeric cellular insulation shall conform to ASTM C 1136, Type 1, and is allowed to be of a different material than the adjoining insulation material.

3.2.1.4 Flexible Elastomeric Cellular Pipe Insulation

Flexible elastomeric cellular pipe insulation shall be tubular form for pipe sizes 6 inches and less. Type II sheet insulation used on pipes larger than 6 inches shall not be stretched around the pipe. On pipes larger than 12 inches, adhere insulation directly to the pipe on the lower 1/3 of the pipe. Seams shall be staggered when applying multiple layers of

insulation. Sweat fittings shall be insulated with miter-cut pieces the same size as on adjacent piping. Screwed fittings shall be insulated with sleeved fitting covers fabricated from miter-cut pieces and shall be overlapped and sealed to the adjacent pipe insulation.

3.2.2 Aboveground Cold Pipelines

The following cold pipelines shall be insulated per Table I minus 30 degrees to plus 60 degrees F:

- a. Refrigerant suction lines.
- b. Chilled water.
- c. Dual temperature water, i.e. HVAC hot/chilled water.
- d. Air conditioner condensate drains.

3.2.2.1 Insulation Thickness

Insulation thickness for cold pipelines shall be determined using Table I.

Table I - Cold Piping Insulation Thickness
Pipe Size (inches)

Type of Service	Material	Runouts up to 2 in*	1 in & less	1.25 - 2 in	2.5 - 4 in	5 - 6 in	8 in & larger
Refrigerant suction piping	CG FC PF PC		1.5 1.0 1.0	1.5 1.0 1.0	1.5 1.0 1.0	1.5 1.0 1.0	1.5 1.0 1.0
Chilled water supply & return & dual temp piping	CG FC PF PC	1.5 0.5 1.0	1.5 1.0 1.0	1.5 1.0 1.0	2.0 1.0 1.0	2.0 1.0 1.0	2.0 1.0 1.0

*When runouts to terminal units exceed 12 feet, the entire length of runout shall be insulated like main feed pipe.

LEGEND:

PF - Phenolic Foam

CG - Cellular Glass

MF - Mineral Fiber

FC - Flexible Elastomeric Cellular

PC - Polyisocyanurate Foam

3.2.2.2 Jacket for Mineral Fiber, Cellular Glass, Phenolic Foam, and Polyisocyanurate Foam Insulated Pipe

Insulation shall be covered with a factory applied vapor retarder jacket or field applied seal welded PVC jacket.

- 3.2.2.3 Insulation for Straight Runs (Mineral Fiber, Cellular Glass, Phenolic Foam and Polyisocyanurate Foam)
 - a. Insulation shall be applied to the pipe with joints tightly butted. All butted joints and ends shall be sealed with a vapor retarder coating.
 - b. Longitudinal laps of the jacket material shall overlap not less than 1-1/2 inches. Butt strips 3 inches wide shall be provided for circumferential joints.
 - c. Laps and butt strips shall be secured with adhesive and stapled on 4 inch centers if not factory self-sealing. If staples are used, they shall be sealed per paragraph 3.2.2.3 e.
 - d. Factory self-sealing lap systems may be used when the ambient temperature is between 40 degrees and 120 degrees F during installation. The lap system shall be installed in accordance with manufacturer's recommendations. Stapler shall be used only if specifically recommended by the manufacturer. Where gaps occur, the section shall be replaced or the gap repaired by applying adhesive under the lap and then stapling.
 - e. All Staples, including those used to repair factory self-seal lap systems, shall be coated with a vapor retarder coating. All seams, except those on factory self-seal systems shall be coated with vapor retarder coating.
 - f. Breaks and punctures in the jacket material shall be patched by wrapping a strip of jacket material around the pipe and securing it with adhesive, stapling, and coating with vapor retarder coating. The patch shall extend not less than 1-1/2 inches past the break.
 - g. At penetrations such as thermometers, the voids in the insulation shall be filled and sealed with vapor retarder coating.

3.2.3 Aboveground Hot Pipelines

The hot water pipelines above 60 degrees F shall be insulated per Table II:

3.2.3.1 Insulation Thickness

Insulation thickness for hot pipelines shall be determined using Table II.

LEGEND:

- PF Phenolic Foam
- CG Cellular Glass
- CS Calcium Silicate

MF - Mineral Fiber

FC - Flexible Elastomeric Cellular

PL - Perlite

PC - Polyisocyanurate Foam

Table II - Hot Piping Insulation Thickness
Pipe Size (inches)

Type of	Material	Runouts	1 in	1.25 -	2.5 -	5 -	8 in
Service		up to	&	2	4	6	&
(degrees F)		2 in *	less	in	in	in	larger
Heating hot water, supply & return, & Heating oil (250 F max)	CG PF MF CS PC	1.5 0.5 0.5 1.0	1.5 1.0 1.5 1.5	2.0 1.0 1.5 2.0 1.0	2.0 1.0 2.0 2.5 1.0	2.5 1.0 2.5 2.5 1.0	3.0 1.5 3.0 3.0

^{*} When runouts to terminal units exceed 12 feet, the entire length of runout shall be insulated like the main feed pipe.

3.2.3.2 Jacket for Insulated Hot Pipe, Except Pipe Insulated with Flexible Elastomeric Cellular

Insulation shall be covered, in accordance with manufacturer's recommendations, with a factory applied Type II jacket or field applied aluminum where required or seal welded PVC.

3.2.3.3 Insulation for Straight Runs

- a. Insulation shall be applied to the pipe with joints tightly butted.
- b. Longitudinal laps of the jacket material shall overlap not less than 1-1/2 inches, and butt strips 3 inches wide shall be provided for circumferential joints.
- c. Laps and butt strips shall be secured with adhesive and stapled on 4 inch centers if not factory self-sealing. Adhesive may be omitted where pipe is concealed.
- d. Factory self-sealing lap systems may be used when the ambient temperature is between 40 degrees and 120 degrees F and shall be installed in accordance with manufacturer's instructions. Laps and butt strips shall be stapled whenever there is nonadhesion of the system. Where gaps occur, the section shall be replaced or the gap repaired by applying adhesive under the lap and then stapling.
- e. Breaks and punctures in the jacket material shall be patched by

^{**} Applies to recirculating sections of service or domestic hot water systems and first 8 feet from storage tank for non-recirculating systems.

either wrapping a strip of jacket material around the pipe and securing with adhesive and staple on 4 inch centers (if not factory self-sealing), or patching with tape and sealing with a brush coat of vapor retarder coating. Adhesive may be omitted where pipe is concealed. Patch shall extend not less than 1-1/2 inches past the break.

3.3 DUCT INSULATION INSTALLATION

Except for oven hood exhaust duct insulation, corner angles shall be installed on external corners of insulation on ductwork in exposed finished spaces before covering with jacket. Air conditioned spaces shall be defined as those spaces directly supplied with cooled conditioned air (or provided with a cooling device such as a fan-coil unit) and heated conditioned air (or provided with a heating device such as a unit heater, radiator or convector).

3.4 EQUIPMENT INSULATION INSTALLATION

3.4.1 General

Removable insulation sections shall be provided to cover parts of equipment which must be opened periodically for maintenance including vessel covers, fasteners, flanges and accessories. Equipment insulation shall be omitted on the following:

- a. Handholes.
- b. Boiler manholes.
- c. Cleanouts.
- d. ASME stamps.
- e. Manufacturer's nameplates.

3.4.2 Insulation for Cold Equipment

Cold equipment below 60 degrees F: Insulation shall be furnished on equipment handling media below 60 degrees F including the following:

- a. Refrigeration equipment parts that are not factory insulated.
- b. Drip pans under chilled equipment.
- c. Duct mounted coils.
- d. Air handling equipment parts that are not factory insulated.
- e. Expansion and air separation tanks.

3.4.2.1 Insulation Type

Insulation shall be suitable for the temperature encountered. Thicknesses

shall be as follows:

- a. Equipment handling media between 35 and 60 degrees F: 1.5 inch thick cellular glass, 1 inch thick flexible elastomeric cellular, 1 inch thick phenolic foam, or 1 inch thick polyisocyanurate foam.
- b. Equipment handling media between 0 degree F and 34 degrees F: 3 inch thick cellular glass, 1 1/2 inch flexible elastomeric cellular, 1 1/2 inch thick phenolic foam, or 1 1/2 inch thick polyisocyanurate foam.
- c. Equipment handling media between minus 30 degrees F and 1 degree F: 3 1/2 inch thick cellular glass 1 3/4 inch thick flexible elastomeric cellular, 1 1/2 inch thick phenolic foam, or 1 1/2 inch thick polyisocyanurate foam.
- -- End of Section --

SECTION 15400

PLUMBING, GENERAL PURPOSE

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AIR CONDITIONING AND REFRIGERATION INSTITUTE (ARI)

ARI 700	(1995; Apx C) Specifications for Fluorocarbon and Other Refrigerants
ARI 1010	(1994) Self-Contained, Mechanically Refrigerated Drinking-Water Coolers
AMERICAN NATIONAL STANI	DARDS INSTITUTE (ANSI)
ANSI Z21.10.1	(1993; Z21.10.1a; Z21.10.1b; Z21.10.1c) Gas Water Heaters Vol. I, Storage Water Heaters with Input Ratings of 75,000 Btu Per Hour or Less
ANSI Z21.10.3	(1998) Gas Water Heaters Vol. III, Storage Water Heaters with Input Ratings Above 75,000 Btu Per Hour, Circulating and Instantaneous Water Heaters

ANSI Z21.22 (1986; Z21.22a) Relief Valves and
Automatic Gas Shutoff Devices for Hot
Water Supply Systems

ANSI Z21.56 (1994; Z21.56a) Gas-Fired Pool Heaters

ANSI Z358.1 (1998) Emergency Eyewash and Shower

Equipment

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 47/A 47M	(1999) Ferritic Malleable Iron Castings
ASTM A 53/A 53M	(1999b) Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A 74	(1998) Cast Iron Soil Pipe and Fittings
ASTM A 105/A 105M	(1998) Carbon Steel Forgings for Piping Applications
ASTM A 183	(1983; R 1998) Carbon Steel Track Bolts

	and Nucs
ASTM A 193/A 193M	(1999a) Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service
ASTM A 515/A 515M	(1989; R 1997) Pressure Vessel Plates, Carbon Steel, for Intermediate- and Higher-Temperature Service
ASTM A 516/A 516M	(1990; R 1996) Pressure Vessel Plates, Carbon Steel, for Moderate- and Lower-Temperature Service
ASTM A 518/A 518M	(1999) Corrosion-Resistant High-Silicon Iron Castings
ASTM A 536	(1984; R 1999el) Ductile Iron Castings
ASTM A 733	(1999) Welded and Seamless Carbon Steel and Austenitic Stainless Steel Pipe Nipples
ASTM A 888	(1998el) Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste, and Vent Piping Applications
ASTM B 32	(1996) Solder Metal
ASTM B 42	(1998) Seamless Copper Pipe, Standard Sizes
ASTM B 43	(1998) Seamless Red Brass Pipe, Standard Sizes
ASTM B 75	(1999) Seamless Copper Tube
ASTM B 75M	(1999) Seamless Copper Tube (Metric)
ASTM B 88	(1999) Seamless Copper Water Tube
ASTM B 88M	(1999) Seamless Copper Water Tube (Metric)
ASTM B 111	(1998) Copper and Copper-Alloy Seamless Condenser Tubes and Ferrule Stock
ASTM B 111M	(1998) Copper and Copper-Alloy Seamless Condenser Tubes and Ferrule Stock (Metric)
ASTM B 117	(1997) Operating Salt Spray (FOG) Apparatus
ASTM B 152	(1997a) Copper Sheet, Strip, Plate, and Rolled Bar
ASTM B 152M	(1997a) Copper Sheet, Strip, Plate, and Rolled Bar (Metric)

ASTM B 306	(1999) Copper Drainage Tube (DWV)
ASTM B 370	(1998) Copper Sheet and Strip for Building Construction
ASTM B 584	(1998a) Copper Alloy Sand Castings for General Applications
ASTM B 813	(1993) Liquid and Paste Fluxes for Soldering Applications of Copper and Copper Alloy Tube
ASTM B 828	(1998) Making Capillary Joints by Soldering of Copper and Copper Alloy Tube and Fittings
ASTM C 564	(1997) Rubber Gaskets for Cast Iron Soil Pipe and Fittings
ASTM C 920	(1998) Elastomeric Joint Sealants
ASTM C 1053	(1990; R 1995el) Borosilicate Glass Pipe and Fittings for Drain, Waste, and Vent (DWV) Applications
ASTM D 638	(1999) Tensile Properties of Plastics
ASTM D 638M	(1998) Tensile Properties of Plastics (Metric)
ASTM D 1004	(1994a) Initial Tear Resistance of Plastic Film and Sheeting
ASTM D 1248	(1998) Polyethylene Plastics Molding and Extrusion Materials
ASTM D 1785	(1999) Poly(Vinyl Chloride) (PVC) Plastic Pipe, Schedules 40, 80, and 120
ASTM D 2000	(1999) Rubber Products in Automotive Applications
ASTM D 2235	(1996a) Solvent Cement for Acrylonitrile-Butadiene-Styrene (ABS) Plastic Pipe and Fittings
ASTM D 2239	(1999) Polyethylene (PE) Plastic Pipe (SIDR-PR) Based on Controlled Inside Diameter
ASTM D 2241	(1999a) Poly(Vinyl Chloride) (PVC) Pressure-Rated Pipe (SDR Series)

ASTM D 2447	(1999) Polyethylene (PE) Plastic Pipe, Schedules 40 and 80, Based on Outside Diameter
ASTM D 2464	(1999) Threaded Poly(Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 80
ASTM D 2466	(1999) Poly(Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 40
ASTM D 2467	(1999) Poly(Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 80
ASTM D 2485	(1991; R 1996) Evaluating Coatings for High Temperature Service
ASTM D 2564	(1996a) Solvent Cements for Poly(Vinyl Chloride) (PVC) Plastic Piping Systems
ASTM D 2657	(1997) Heat Fusion Joining Polyolefin Pipe and Fittings
ASTM D 2661	(1997ael) Acrylonitrile-Butadiene-Styrene (ABS) Schedule 40 Plastic Drain, Waste, and Vent Pipe and Fittings
ASTM D 2665	(1998) Poly(Vinyl Chloride) (PVC) Plastic Drain, Waste, and Vent Pipe and Fittings
ASTM D 2672	(1996a) Joints for IPS PVC Pipe Using Solvent Cement
ASTM D 2683	(1998) Socket-Type Polyethylene Fittings for Outside Diameter-Controlled Polyethylene Pipe and Tubing
ASTM D 2737	(1999) Polyethylene (PE) Plastic Tubing
ASTM D 2822	(1991; R 1997el) Asphalt Roof Cement
ASTM D 2846/D 2846M	(1999) Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Hot- and Cold-Water Distribution Systems
ASTM D 2855	(1996) Making Solvent-Cemented Joints with Poly(Vinyl Chloride) (PVC) Pipe and Fittings
ASTM D 2996	(1995) Filament-Wound "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Pipe
ASTM D 3035	(1995) Polyethylene (PE) Plastic Pipe (DR-PR) Based on Controlled Outside

.am	

	Diameter
ASTM D 3122	(1995) Solvent Cements for Styrene-Rubber (SR) Plastic Pipe and Fittings
ASTM D 3138	(1995) Solvent Cements for Transition Joints Between Acrylonitrile-Butadiene-Styrene (ABS) and Poly(Vinyl Chloride) (PVC) Non-Pressure Piping Components
ASTM D 3139	(1998) Joints for Plastic Pressure Pipes Using Flexible Elastomeric Seals
ASTM D 3212	(1996a) Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals
ASTM D 3261	(1997) Butt Heat Fusion Polyethylene (PE) Plastic Fittings for Polyethylene (PE) Plastic Pipe and Tubing
ASTM D 3308	(1997) PTFE Resin Skived Tape
ASTM D 3311	(1994) Drain, Waste, and Vent (DWV) Plastic Fittings Patterns
ASTM D 4060	(1995) Abrasion Resistance of Organic Coatings by the Taber Abraser
ASTM D 4101	(1999) Propylene Plastic Injection and Extrusion Materials
ASTM D 4551	(1996) Poly(Vinyl Chloride) (PVC) Plastic Flexible Concealed Water-Containment Membrane
ASTM E 1	(1998) ASTM Thermometers
ASTM E 96	(1995) Water Vapor Transmission of Materials
ASTM F 409	(1999a) Thermoplastic Accessible and Replaceable Plastic Tube and Tubular Fittings
ASTM F 437	(1999) Threaded Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 80
ASTM F 438	(1999) Socket-Type Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 40
ASTM F 439	(1999) Socket-Type Chlorinated Poly(Vinyl

	Chloride) (CPVC) Plastic Pipe Fittings,	
	Schedule 80	
ASTM F 441/F 441M	(1999) Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe, Schedules 40 and 80	
ASTM F 442/F 442M	(1999) Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe (SDR-PR)	
ASTM F 477	(1999) Elastomeric Seals (Gaskets) for Joining Plastic Pipe	
ASTM F 493	(1997) Solvent Cements for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe and Fittings	
ASTM F 628	(1999el) Acrylonitrile-Butadiene-Styrene (ABS) Schedule 40 Plastic Drain, Waste, and Vent Pipe with a Cellular Core	
ASTM F 877	(2000) Standard Specification for Crosslinked Polyethylene (PEX) Plastic Hot- and Cold Water Distribution Systems	
ASTM F 891	(1998el) Coextruded Poly(Vinyl Chloride) (PVC) Plastic Pipe with a Cellular Core	
ASTM F 1290	(1998a) Electrofusion Joining Polyolefin Pipe and Fittings	
ASTM F 1760	(1997) Coextruded Poly(Vinyl Chloride) (PVC) Non-Pressure Plastic Pipe Having Reprocessed-Recycled Content	
AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)		
ASHRAE 34	(1997) Number Designation and Safety Classification of Refrigerants	
ASHRAE 90.1	(1989; 90.1b; 90.1c; 90.1d; 90.1e; 90.1g; 90.1i; 90.11-1995; 90.1m-1995; 90.1n-1997) Energy Efficient Design of New Buildings Except Low-Rise Residential Buildings	
ASME INTERNATIONAL (ASME)		
ASME A112.1.2	(1991; R 1998) Air Gaps in Plumbing Systems	
ASME A112.6.1M	(1997) Supports for Off-the-Floor Plumbing Fixtures for Public Use	
ASME A112.14.1	(1975; R 1998) Backwater Valves	

ASME A112.18.1M	(1996) Plumbing Fixture Fittings
ASME All2.19.1M	(1994; R 1999) Enameled Cast Iron Plumbing Fixtures
ASME A112.19.2M	(1998) Vitreous China Plumbing Fixtures
ASME A112.19.3M	(1987; R 1996) Stainless Steel Plumbing Fixtures (Designed for Residential Use)
ASME A112.19.4M	(1994; Errata Nov 1996) Porcelain Enameled Formed Steel Plumbing Fixtures
ASME All2.21.1M	(1991; R 1998) Floor Drains
ASME A112.21.2M	(1983) Roof Drains
ASME A112.36.2M	(1991; R 1998) Cleanouts
ASME B1.20.1	(1983; R 1992) Pipe Threads, General Purpose (Inch)
ASME B16.3	(1998) Malleable Iron Threaded Fittings
ASME B16.4	(1998) Gray Iron Threaded Fittings
ASME B16.5	(1996; B16.5a) Pipe Flanges and Flanged Fittings NPS 1/2 thru NPS 24
ASME B16.12	(1998) Cast Iron Threaded Drainage Fittings
ASME B16.15	(1985; R 1994) Cast Bronze Threaded Fittings Classes 125 and 250
ASME B16.18	(1984; R 1994) Cast Copper Alloy Solder Joint Pressure Fittings
ASME B16.21	(1992) Nonmetallic Flat Gaskets for Pipe Flanges
ASME B16.22	(1995; B16.22a1998) Wrought Copper and Copper Alloy Solder Joint Pressure Fittings
ASME B16.23	(1992; Errata Jan 1994) Cast Copper Alloy Solder Joint Drainage Fittings - DWV
ASME B16.24	(1991; R 1998) Cast Copper Alloy Pipe Flanges, Class 150, 300, 400, 600, 900, 1500, and 2500, and Flanged Fittings, Class 150 and 300
ASME B16.29	(1994) Wrought Copper and Wrought Copper Alloy Solder Joint Drainage Fittings - DWV

ASME	B16.34	(1997) Valves - Flanged, Threaded, and Welding End
ASME	B16.39	(1998) Malleable Iron Threaded Pipe Unions Classes 150, 250, and 300
ASME	B31.1	(1998) Power Piping
ASME	B31.5	(1992; B31.5a1994) Refrigeration Piping
ASME	B40.1	(1991) Gauges - Pressure Indicating Dial Type - Elastic Element
ASME	BPV VIII Div 1	(1998) Boiler and Pressure Vessel Code; Section VIII, Pressure Vessels Division 1 - Basic Coverage
ASME	BPV IX	(1998) Boiler and Pressure Vessel Code; Section IX, Welding and Brazing Qualifications
ASME	CSD-1	(1998) Controls and Safety Devices for Automatically Fired Boilers
	AMERICAN SOCIETY OF SAN RESEARCH(ASSE)	ITARY ENGINEERING FOR PLUMBING AND SANITARY
ASSE	1001	(1990) Pipe Applied Atmospheric Type Vacuum Breakers
ASSE	1002	(1986) Water Closet Flush Tank Ball Cocks
ASSE	1003	(1995) Water Pressure Reducing Valves for Domestic Water Supply Systems
ASSE	1005	(1986) Water Heater Drain Valves - 3/4-Inch Iron Pipe Size
ASSE	1006	(1989) Residential Use (Household) Dishwashers
ASSE	1011	(1995) Hose Connection Vacuum Breakers
ASSE	1012	(1995) Backflow Preventers with Intermediate Atmospheric Vent
ASSE	1013	(1993) Reduced Pressure Principle Backflow Preventers
ASSE	1018	(1986) Trap Seal Primer Valves Water Supply Fed
ASSE	1020	(1998) Pressure Vacuum Breaker Assembly (Recommended for Outdoor Usage)

ASSE 1037 (1990; Rev thru Mar 1990) Pressurized Flushing Devices (Flushometers) for

Plumbing Fixtures

AMERICAN WATER WORKS ASSOCIATION (AWWA)

(1999) Standard Methods for the AWWA EWW Examination of Water and Wastewater AWWA B300 (1999) Hypochlorites AWWA B301 (1992; Addenda B301a - 1999) Liquid Chlorine AWWA C105 (1993) Polyethylene Encasement for Ductile-Iron Pipe Systems (1997; addenda C203a - 1999) Coal-Tar AWWA C203 Protective Coatings and Linings for Steel Water Pipelines - Enamel and Tape -Hot-Applied AWWA C606 (1997) Grooved and Shouldered Joints AWWA C700 (1995) Cold-Water Meters - Displacement Type, Bronze Main Case AWWA D100 (1996) Welded Steel Tanks for Water Storage AWWA M20 (1973) Manual: Water Chlorination

AMERICAN WELDING SOCIETY (AWS)

AWS A5.8 (1992) Filler Metals for Brazing and Braze Welding

AWS B2.2 (1991) Brazing Procedure and Performance

Qualification

CAST IRON SOIL PIPE INSTITUTE (CISPI)

CISPI 301 (1997) Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste, and Vent Piping Applications

CISPI 310 (1997) Coupling for Use in Connection with Hubless Cast Iron Soil Pipe and Fittings for Sanitary and Storm Drain, Waste, and

Vent Piping Applications

Principles and Practices

CISPI HSN-85 (1985) Neoprene Rubber Gaskets for Hub and Spigot Cast Iron Soil Pipe and Fittings

CODE OF FEDERAL REGULATIONS (CFR)

10 CFR 430 Energy Conservation Program for Consumer

Products

21 CFR 175 Indirect Food Additives: Adhesives and

Components of Coatings

PL 93-523 (1974; Amended 1986) Safe Drinking Water

Act

COMMERCIAL ITEM DESCRIPTIONS (CID)

CID A-A-240 (Rev A; Canc. Notice 1) Shower Head, Ball

Joint

CID A-A-50012 (Basic) Garbage Disposal Machine,

Commercial

COPPER DEVELOPMENT ASSOCIATION (CDA)

CDA Tube Handbook (1995) Copper Tube Handbook

FOUNDATION FOR CROSS-CONNECTION CONTROL AND HYDRAULIC RESEARCH

(FCCCHR)

FCCCHR-01 (1993) Manual of Cross-Connection Control

HYDRAULIC INSTITUTE (HI)

HI 1.1-1.5 (1994) Centrifugal Pumps

INTERNATIONAL ASSOCIATION OF PLUMBING AND MECHANCIAL OFFICIALS

(IAPMO)

IAPMO Z124.1 (1995) Plastic Bathtub Units

IAPMO Z124.3 (1995) Plastic Lavatories

IAPMO Z124.5 (1997) Plastic Toilet (Water Closets) Seats

IAPMO Z124.9 (1994) Plastic Urinal Fixtures

INTERNAL CODE COUNCIL (ICC)

CABO Al17.1 (1998) Accessible and Usable Buildings and

Facilities

ICC Plumbing Code (2000) International Plumbing Code (IPC)

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS

INDUSTRY (MSS)

MSS SP-25	(1998) Standard Marking System for Valves, Fittings, Flanges and Unions
MSS SP-44	(1996) Steel Pipeline Flanges
MSS SP-58	(1993) Pipe Hangers and Supports - Materials, Design and Manufacture
MSS SP-67	(1995) Butterfly Valves
MSS SP-69	(1996) Pipe Hangers and Supports - Selection and Application
MSS SP-70	(1998) Cast Iron Gate Valves, Flanged and Threaded Ends
MSS SP-71	(1997) Cast Iron Swing Check Valves, Flanges and Threaded Ends
MSS SP-72	(1999) Ball Valves with Flanged or Butt-Welding Ends for General Service
MSS SP-73	(1991; R 1996) Brazing Joints for Copper and Copper Alloy Pressure Fittings
MSS SP-78	(1998) Cast Iron Plug Valves, Flanged and Threaded Ends
MSS SP-80	(1997) Bronze Gate, Globe, Angle and Check Valves
MSS SP-83	(1995) Class 3000 Steel Pipe Unions Socket-Welding and Threaded
MSS SP-85	(1994) Cast Iron Globe & Angle Valves, Flanged and Threaded Ends
MSS SP-110	(1996) Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends
NATIONAL ELECTRICAL MAI	NUFACTURERS ASSOCIATION (NEMA)
NEMA 250	(1997) Enclosures for Electrical Equipment (1000 Volts Maximum)
NATIONAL FIRE PROTECTION	ON ASSOCIATION (NFPA)
NFPA 31	(1997; TIA 97-1) Installation of Oil Burning Equipment
NFPA 54	(1999) National Fuel Gas Code
NFPA 90A	(1999) Installation of Air Conditioning

and Ventilating Systems

NSF INTERNATIONAL (NS

NSF 3		(1996) Commercial Spray-Type Dishwashing and Glasswashing Machines
NSF 5		(1992) Water Heaters, Hot Water Supply Boilers, and Heat Recovery Equipment
NSF 14		(1999) Plastics Piping Components and Related Materials
NSF 61		(1999) Drinking Water System Components - Health Effects (Sections 1-9)
	PLASTIC PIPE AND FITTIN	GS ASSOCIATION (PPFA)

PPFA-01 (1999) Plastic Pipe in Fire Resistive Construction

PLUMBING AND DRAINAGE INSTITUTE (PDI)

PDI G 101	(1996) Testing and Rating Procedure for	
	Grease Interceptors with Appendix of	
	Sizing and Installation Data	

PDI WH 201 (1992) Water Hammer Arresters

SOCIETY OF AUTOMOTIVE ENGINEERS (SAE)

SAE J 1508 (1997) Hose Clamps

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC SP 5/NACE 1 (1994) White Metal Blast Cleaning

UNDERWRITERS LABORATORIES (UL)

UL 174	(1996; Rev thru Oct 1999) Household Electric Storage Tank Water Heaters
UL 430	(1994; Rev thru Nov 1996) Waste Disposers
UL 732	(1995; Rev thru Jan 1999) Oil-Fired Storage Tank Water Heaters
UL 749	(1997; Rev thru Feb 1999) Household Dishwashers
UL 921	(1996) Commercial Electric Dishwashers

1.2 STANDARD PRODUCTS

Specified materials and equipment shall be standard products of a manufacturer regularly engaged in the manufacture of such products. Specified equipment shall essentially duplicate equipment that has performed satisfactorily at least two years prior to bid opening.

1.3 ELECTRICAL WORK

Motors, motor controllers and motor efficiencies shall conform to the requirements of Section 16415 ELECTRICAL WORK, INTERIOR. Electrical motor-driven equipment specified herein shall be provided complete with motors. Equipment shall be rated at 60 Hz, single phase, ac unless otherwise indicated. Where a motor controller is not provided in a motor-control center on the electrical drawings, a motor controller shall be as indicated. Motor controllers shall be provided complete with properly sized thermal-overload protection in each ungrounded conductor, auxiliary contact, and other equipment, at the specified capacity, and including an allowable service factor.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Plumbing System; G WA.

Detail drawings consisting of illustrations, schedules, performance charts, instructions, brochures, diagrams, and other information to illustrate the requirements and operations of each system. Detail drawings for the complete plumbing system including piping layouts and locations of connections; dimensions for roughing-in, foundation, and support points; schematic diagrams and wiring diagrams or connection and interconnection diagrams. Detail drawings shall indicate clearances required for maintenance and operation. Where piping and equipment are to be supported other than as indicated, details shall include loadings and proposed support methods. Mechanical drawing plans, elevations, views, and details, shall be drawn to scale.

Electrical Schematics; G WA.

Complete electrical schematic lineless or full line interconnection and connection diagram for each piece of mechanical equipment having more than one automatic or manual electrical control device.

SD-03 Product Data

Welding; G WA.

A copy of qualified procedures and a list of names and identification symbols of qualified welders and welding operators.

Plumbing Fixture Schedule; G WA.

Catalog cuts of specified plumbing fixtures, valves and related piping .

SD-07 Certificates

Materials and Equipment; G WA.

Where materials or equipment are specified to comply with requirements of AGA, ASME, or NSF proof of such compliance shall be included. The label or listing of the specified agency will be acceptable evidence. In lieu of the label or listing, a written certificate may be submitted from an approved, nationally recognized testing organization equipped to perform such services, stating that the items have been tested and conform to the requirements and testing methods of the specified agency. Where equipment is specified to conform to requirements of the ASME Boiler and Pressure Vessel Code, the design, fabrication, and installation shall conform to the code.

1.5 PERFORMANCE REQUIREMENTS

1.5.1 Welding

Piping shall be welded in accordance with qualified procedures using performance-qualified welders and welding operators. Procedures and welders shall be qualified in accordance with ASME BPV IX. Welding procedures qualified by others, and welders and welding operators qualified by another employer, may be accepted as permitted by ASME B31.1.

1.6 REGULATORY REQUIREMENTS

Plumbing work shall be in accordance with ICC Plumbing Code.

1.7 PROJECT/SITE CONDITIONS

The Contractor shall become familiar with details of the work, verify dimensions in the field, and advise the Contracting Officer of any discrepancy before performing any work.

PART 2 PRODUCTS

2.1 MATERIALS

Materials for various services shall be in accordance with TABLES I and II. Pipe schedules shall be selected based on service requirements. Pipe fittings shall be compatible with the applicable pipe materials.

2.1.1 Pipe Joint Materials

Joints and gasket materials shall conform to the following:

- a. Coupling for Cast-Iron Pipe: for hub and spigot type ASTM A 74, AWWA C606. For hubless type: CISPI 310
 - b. Coupling for Steel Pipe: AWWA C606.
- c. Flange Gaskets: Gaskets shall be made of non-asbestos material in accordance with ASME B16.21. Gaskets shall be flat, 1/16 inch thick, and contain Aramid fibers bonded with Styrene Butadiene Rubber (SBR) or Nitro Butadiene Rubber (NBR). Gaskets shall be the full face or self centering flat ring type. Gaskets used for hydrocarbon service shall be bonded with NBR.
- d. Neoprene Gaskets for Hub and Cast-Iron Pipe and Fittings: CISPI ${\tt HSN-85}$.
- e. Brazing Material: Brazing material shall conform to AWS A5.8, BCuP-5.
- f. Brazing Flux: Flux shall be in paste or liquid form appropriate for use with brazing material. Flux shall be as follows: lead-free; have a 100 percent flushable residue; contain slightly acidic reagents; contain potassium borides; and contain fluorides.
 - g. Solder Material: Solder metal shall conform to ASTM B 32.
- h. Solder Flux: Flux shall be liquid form, non-corrosive, and conform to ASTM B 813, Standard Test 1.
- i. PTFE Tape: PTFE Tape, for use with Threaded Metal or Plastic Pipe, ASTM D 3308.
- j. Rubber Gaskets for Cast-Iron Soil-Pipe and Fittings (hub and spigot type and hubless type): ASTM C 564.
- k. Rubber Gaskets for Grooved Pipe: ASTM D 2000, maximum temperature $230 \ degrees \ F.$
 - 1. Flexible Elastomeric Seals: ASTM D 3139, ASTM D 3212 or ASTM F 477.
- m. Bolts and Nuts for Grooved Pipe Couplings: Heat-treated carbon steel, ASTM A 183.
- n. Flanged fittings including flanges, bolts, nuts, bolt patterns, etc., shall be in accordance with ASME B16.5 class 150 and shall have the manufacturer's trademark affixed in accordance with MSS SP-25. Flange material shall conform to ASTM A 105/A 105M. Blind flange material shall conform to ASTM A 516/A 516M cold service and ASTM A 515/A 515M for hot service. Bolts shall be high strength or intermediate strength with material conforming to ASTM A 193/A 193M.
- 2.1.2 Pipe Insulation Material

Insulation shall be as specified in Section 15080 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

2.2 PIPE HANGERS, INSERTS, AND SUPPORTS

Pipe hangers, inserts, and supports shall conform to MSS SP-58 and MSS SP-69.

2.3 VALVES

Valves shall be provided on supplies to equipment and fixtures. Valves 2-1/2 inches and smaller shall be bronze with threaded bodies for pipe and solder-type connections for tubing. Valves 3 inches and larger shall have flanged iron bodies and bronze trim. Pressure ratings shall be based upon the application. Grooved end valves may be provided if the manufacturer certifies that the valves meet the performance requirements of applicable MSS standard. Valves shall conform to the following standards:

Description	Standard
Butterfly Valves	MSS SP-67
Cast-Iron Gate Valves, Flanged and Threaded Ends	MSS SP-70
Cast-Iron Swing Check Valves, Flanged and Threaded Ends	MSS SP-71
Ball Valves with Flanged Butt-Welding Ends for General Service	MSS SP-72
Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends	MSS SP-110
Cast-Iron Plug Valves, Flanged and Threaded Ends	MSS SP-78
Bronze Gate, Globe, Angle, and Check Valves	MSS SP-80
Steel Valves, Socket Welding and Threaded Ends	ASME B16.34
Cast-Iron Globe and Angle Valves, Flanged and Threaded Ends	MSS SP-85
Backwater Valves	ASME A112.14.1
Vacuum Relief Valves	ANSI Z21.22
Water Pressure Reducing Valves	ASSE 1003
Water Heater Drain Valves	ASSE 1005
Trap Seal Primer Valves	ASSE 1018
Temperature and Pressure Relief Valves	ANSI Z21.22

Description Standard

for Hot Water Supply Systems

Temperature and Pressure Relief Valves ASME CSD-1

for Automatically Fired Hot

Water Boilers Safety Code No., Part CW,
Article 5

2.3.1 Relief Valves

Water heaters and hot water storage tanks shall have a combination pressure and temperature (P&T) relief valve. The pressure relief element of a P&T relief valve shall have adequate capacity to prevent excessive pressure buildup in the system when the system is operating at the maximum rate of heat input. The temperature element of a P&T relief valve shall have a relieving capacity which is at least equal to the total input of the heaters when operating at their maximum capacity. Relief valves shall be rated according to ANSI Z21.22. Relief valves for systems where the maximum rate of heat input is less than 200,000 Btuh shall have 3/4 inch minimum inlets, and 3/4 inch outlets. Relief valves for systems where the maximum rate of heat input is greater than 200,000 Btuh shall have 1 inch minimum inlets, and 1 inch outlets. The discharge pipe from the relief valve shall be the size of the valve outlet.

2.3.2 Thermostatic Mixing Valves

Mixing valves, thermostatic type, pressure-balanced or combination thermostatic and pressure-balanced shall be line size and shall be constructed with rough or finish bodies either with or without plating. Each valve shall be constructed to control the mixing of hot and cold water and to deliver water at a desired temperature regardless of pressure or input temperature changes. The control element shall be of an approved type. The body shall be of heavy cast bronze, and interior parts shall be brass, bronze, corrosion-resisting steel or copper. The valve shall be equipped with necessary stops, check valves, unions, and sediment strainers on the inlets. Mixing valves shall maintain water temperature within 5 degrees F of any setting.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

Piping located in air plenums shall conform to NFPA 90A requirements. Plastic pipe shall not be installed in air plenums. Piping located in shafts that constitute air ducts or that enclose air ducts shall be noncombustible in accordance with NFPA 90A. Valves shall be installed with control no lower than the valve body.

3.1.1 Water Pipe, Fittings, and Connections

3.1.1.1 Utilities

The piping shall be extended to fixtures, outlets, and equipment. The

hot-water and cold-water piping system shall be arranged and installed to permit draining. The supply line to each item of equipment or fixture, except faucets, flush valves, or other control valves which are supplied with integral stops, shall be equipped with a shutoff valve to enable isolation of the item for repair and maintenance without interfering with operation of other equipment or fixtures. Supply piping to fixtures, faucets, hydrants, shower heads, and flushing devices shall be anchored to prevent movement.

3.1.1.2 Cutting and Repairing

The work shall be carefully laid out in advance, and unnecessary cutting of construction shall be avoided. Damage to building, piping, wiring, or equipment as a result of cutting shall be repaired by mechanics skilled in the trade involved.

3.1.1.3 Protection of Fixtures, Materials, and Equipment

Pipe openings shall be closed with caps or plugs during installation. Fixtures and equipment shall be tightly covered and protected against dirt, water, chemicals, and mechanical injury. Upon completion of the work, the fixtures, materials, and equipment shall be thoroughly cleaned, adjusted, and operated. Safety guards shall be provided for exposed rotating equipment.

3.1.1.4 Mains, Branches, and Runouts

Piping shall be installed as indicated. Pipe shall be accurately cut and worked into place without springing or forcing. Structural portions of the building shall not be weakened. Aboveground piping shall run parallel with the lines of the building, unless otherwise indicated. Branch pipes from service lines may be taken from top, bottom, or side of main, using crossover fittings required by structural or installation conditions. Supply pipes, valves, and fittings shall be kept a sufficient distance from other work and other services to permit not less than 1/2 inch between finished covering on the different services. Bare and insulated water lines shall not bear directly against building structural elements so as to transmit sound to the structure or to prevent flexible movement of the lines. Water pipe shall not be buried in or under floors unless specifically indicated or approved. Changes in pipe sizes shall be made with reducing fittings. Use of bushings will not be permitted except for use in situations in which standard factory fabricated components are furnished to accommodate specific accepted installation practice. Change in direction shall be made with fittings, except that bending of pipe 4 inches and smaller will be permitted, provided a pipe bender is used and wide sweep bends are formed. The center-line radius of bends shall be not less than six diameters of the pipe. Bent pipe showing kinks, wrinkles, flattening, or other malformations will not be acceptable.

3.1.1.5 Pipe Drains

Pipe drains indicated shall consist of 3/4 inch hose bibb with renewable seat and ball valve ahead of hose bibb. At other low points, 3/4 inch brass plugs or caps shall be provided. Disconnection of the supply piping

at the fixture is an acceptable drain.

3.1.1.6 Expansion and Contraction of Piping

Allowance shall be made throughout for expansion and contraction of water pipe. Each hot-water and hot-water circulation riser shall have expansion loops or other provisions such as offsets, changes in direction, etc., where indicated and/or required. Risers shall be securely anchored as required or where indicated to force expansion to loops. Branch connections from risers shall be made with ample swing or offset to avoid undue strain on fittings or short pipe lengths. Horizontal runs of pipe over 50 feet in length shall be anchored to the wall or the supporting construction about midway on the run to force expansion, evenly divided, toward the ends. Sufficient flexibility shall be provided on branch runouts from mains and risers to provide for expansion and contraction of piping. Flexibility shall be provided by installing one or more turns in the line so that piping will spring enough to allow for expansion without straining. If mechanical grooved pipe coupling systems are provided, the deviation from design requirements for expansion and contraction may be allowed pending approval of Contracting Officer.

3.1.2 Joints

Installation of pipe and fittings shall be made in accordance with the manufacturer's recommendations. Mitering of joints for elbows and notching of straight runs of pipe for tees will not be permitted. Joints shall be made up with fittings of compatible material and made for the specific purpose intended.

3.1.2.1 Threaded

Threaded joints shall have American Standard taper pipe threads conforming to ASME B1.20.1. Only male pipe threads shall be coated with graphite or with an approved graphite compound, or with an inert filler and oil, or shall have a polytetrafluoroethylene tape applied.

3.1.2.2 Mechanical Couplings

Grooved mechanical joints shall be prepared according to the coupling manufacturer's instructions. Pipe and groove dimensions shall comply with the tolerances specified by the coupling manufacturer. The diameter of grooves made in the field shall be measured using a "go/no-go" gauge, vernier or dial caliper, or narrow-land micrometer. Groove width and dimension of groove from end of the pipe shall be measured and recorded for each change in grooving tool setup to verify compliance with coupling manufacturer's tolerances. Grooved joints shall not be used in concealed locations.

3.1.2.3 Unions and Flanges

Unions, flanges and mechanical couplings shall not be concealed in walls, ceilings, or partitions. Unions shall be used on pipe sizes 2-1/2 inches and smaller; flanges shall be used on pipe sizes 3 inches and larger.

3.1.2.4 Grooved Mechanical Joints

Grooves shall be prepared according to the coupling manufacturer's instructions. Grooved fittings, couplings, and grooving tools shall be products of the same manufacturer. Pipe and groove dimensions shall comply with the tolerances specified by the coupling manufacturer. The diameter of grooves made in the field shall be measured using a "go/no-go" gauge, vernier or dial caliper, narrow-land micrometer, or other method specifically approved by the coupling manufacturer for the intended application. Groove width and dimension of groove from end of pipe shall be measured and recorded for each change in grooving tool setup to verify compliance with coupling manufacturer's tolerances. Grooved joints shall not be used in concealed locations.

3.1.2.5 Copper Tube and Pipe

The tube or fittings shall not be annealed when making connections.

- a. Brazed. Brazed joints shall be made in conformance with AWS B2.2, MSS SP-73, and CDA Tube Handbook with flux and are acceptable for all pipe sizes. Copper to copper joints shall include the use of copper-phosphorus or copper-phosphorus-silver brazing metal without flux. Brazing of dissimilar metals (copper to bronze or brass) shall include the use of flux with either a copper-phosphorus, copper-phosphorus-silver or a silver brazing filler metal.
- b. Soldered. Soldered joints shall be made with flux and are only acceptable for piping 2 inches and smaller. Soldered joints shall conform to ASME B31.5 and CDA Tube Handbook.
- c. Copper Tube Extracted Joint. An extracted mechanical joint may be made in copper tube. Joint shall be produced with an appropriate tool by drilling a pilot hole and drawing out the tube surface to form a collar having a minimum height of three times the thickness of the tube wall. To prevent the branch tube from being inserted beyond the depth of the extracted joint, dimpled depth stops shall be provided. Branch tube shall be notched for proper penetration into fitting to assure a free flow joint. Extracted joints shall be brazed in accordance with NAPHCC Plumbing Code using B-cup series filler metal in accordance with MSS SP-73. Soldered extracted joints will not be permitted.

3.1.3 Dissimilar Pipe Materials

Connections between ferrous and non-ferrous copper water pipe shall be made with dielectric unions or flange waterways. Dielectric waterways shall have temperature and pressure rating equal to or greater than that specified for the connecting piping. Waterways shall have metal connections on both ends suited to match connecting piping. Dielectric waterways shall be internally lined with an insulator specifically designed to prevent current flow between dissimilar metals. Dielectric flanges shall meet the performance requirements described herein for dielectric waterways. Connecting joints between plastic and metallic pipe shall be made with transition fitting for the specific purpose.

3.1.4 Pipe Sleeves and Flashing

Pipe sleeves shall be furnished and set in their proper and permanent location.

3.1.4.1 Sleeve Requirements

Pipes passing through concrete or masonry walls or concrete floors or roofs shall be provided with pipe sleeves fitted into place at the time of construction. Sleeves are not required for supply, drainage, waste and vent pipe passing through concrete slab on grade, except where penetrating a membrane waterproof floor. A modular mechanical type sealing assembly may be installed in lieu of a waterproofing clamping flange and caulking and sealing of annular space between pipe and sleeve. The seals shall consist of interlocking synthetic rubber links shaped to continuously fill the annular space between the pipe and sleeve using galvanized steel bolts, nuts, and pressure plates. The links shall be loosely assembled with bolts to form a continuous rubber belt around the pipe with a pressure plate under each bolt head and each nut. After the seal assembly is properly positioned in the sleeve, tightening of the bolt shall cause the rubber sealing elements to expand and provide a watertight seal between the pipe and the sleeve. Each seal assembly shall be sized as recommended by the manufacturer to fit the pipe and sleeve involved. Sleeves shall not be installed in structural members, except where indicated or approved. Rectangular and square openings shall be as detailed. Each sleeve shall extend through its respective floor, or roof, and shall be cut flush with each surface, except for special circumstances. Pipe sleeves passing through floors in wet areas such as mechanical equipment rooms, lavatories, kitchens, and other plumbing fixture areas shall extend a minimum of 4 inches above the finished floor. Unless otherwise indicated, sleeves shall be of a size to provide a minimum of 1/4 inch clearance between bare pipe or insulation and inside of sleeve or between insulation and inside of sleeve. Sleeves in bearing walls and concrete slab on grade floors shall be steel pipe or cast-iron pipe. Sleeves in nonbearing walls or ceilings may be steel pipe, cast-iron pipe, galvanized sheet metal with lock-type longitudinal seam, or plastic. Except as otherwise specified, the annular space between pipe and sleeve, or between jacket over insulation and sleeve, shall be sealed as indicated with sealants conforming to ASTM C 9. The annular space between pipe and sleeve, between bare insulation and sleeve or between jacket over insulation and sleeve shall not be sealed for interior walls which are not designated as fire rated.

3.1.4.2 Flashing Requirements

Pipes passing through roof shall be installed through a 16 ounce copper flashing, each within an integral skirt or flange. Flashing shall be suitably formed, and the skirt or flange shall extend not less than 8 inches from the pipe and shall be set over the roof or floor membrane in a solid coating of bituminous cement. The flashing shall extend up the pipe a minimum of 10 inches. For cleanouts, the flashing shall be turned down into the hub and caulked after placing the ferrule. Pipes passing through pitched roofs shall be flashed, using lead or copper flashing, with an adjustable integral flange of adequate size to extend not less than 8 inches from the pipe in all directions and lapped into the roofing to

provide a watertight seal. The annular space between the flashing and the bare pipe or between the flashing and the metal-jacket-covered insulation shall be sealed as indicated. Flashing for dry vents shall be turned down into the pipe to form a waterproof joint. Pipes, up to and including 10 inches in diameter, passing through roof or floor waterproofing membrane may be installed through a cast-iron sleeve with caulking recess, anchor lugs, flashing-clamp device, and pressure ring with brass bolts. Flashing shield shall be fitted into the sleeve clamping device. Pipes passing through wall waterproofing membrane shall be sleeved as described above. A waterproofing clamping flange shall be installed.

3.1.5 Supports

3.1.5.1 General

Hangers used to support piping 2 inches and larger shall be fabricated to permit adequate adjustment after erection while still supporting the load. Pipe guides and anchors shall be installed to keep pipes in accurate alignment, to direct the expansion movement, and to prevent buckling, swaying, and undue strain. Piping subjected to vertical movement when operating temperatures exceed ambient temperatures shall be supported by variable spring hangers and supports or by constant support hangers. In the support of multiple pipe runs on a common base member, a clip or clamp shall be used where each pipe crosses the base support member. Spacing of the base support members shall not exceed the hanger and support spacing required for an individual pipe in the multiple pipe run. Threaded sections of rods shall not be formed or bent.

3.1.5.2 Pipe Hangers, Inserts, and Supports

Installation of pipe hangers, inserts and supports shall conform to MSS SP-58 and MSS SP-69, except as modified herein.

- a. Types 5, 12, and 26 shall not be used.
- b. Type 3 shall not be used on insulated pipe.
- c. Type 18 inserts shall be secured to concrete forms before concrete is placed. Continuous inserts which allow more adjustment may be used if they otherwise meet the requirements for type 18 inserts.
- d. Type 19 and 23 C-clamps shall be torqued per MSS SP-69 and shall have both locknuts and retaining devices furnished by the manufacturer. Field-fabricated C-clamp bodies or retaining devices are not acceptable.
- e. Type 20 attachments used on angles and channels shall be furnished with an added malleable-iron heel plate or adapter.
- f. Type 24 may be used only on trapeze hanger systems or on fabricated frames.
- g. Type 39 saddles shall be used on insulated pipe 4 inches and larger when the temperature of the medium is 60 degrees F or higher. Type 39 saddles shall be welded to the pipe.

- h. Type 40 shields shall:
 - (1) Be used on insulated pipe less than 4 inches.
- (2) Be used on insulated pipe 4 inches and larger when the temperature of the medium is 60 degrees F or less.
- (3) Have a high density insert for all pipe sizes. High density inserts shall have a density of 8 pcf or greater.
- i. Horizontal pipe supports shall be spaced as specified in MSS SP-69 and a support shall be installed not over 1 foot from the pipe fitting joint at each change in direction of the piping. Pipe supports shall be spaced not over 5 feet apart at valves. Operating temperatures in determining hanger spacing for PVC or CPVC pipe shall be 120 degrees F for PVC and 180 degrees F for CPVC. Horizontal pipe runs shall include allowances for expansion and contraction.
- j. Vertical pipe shall be supported at each floor, except at slab-on-grade, at intervals of not more than 15 feet nor more than 8 feet from end of risers, and at vent terminations. Vertical pipe risers shall include allowances for expansion and contraction.
- k. Type 35 guides using steel, reinforced polytetrafluoroethylene (PTFE) or graphite slides shall be provided to allow longitudinal pipe movement. Slide materials shall be suitable for the system operating temperatures, atmospheric conditions, and bearing loads encountered. Lateral restraints shall be provided as needed. Where steel slides do not require provisions for lateral restraint the following may be used:
- (1) On pipe 4 inches and larger when the temperature of the medium is 60 degrees F or higher, a Type 39 saddle, welded to the pipe, may freely rest on a steel plate.
- (2) On pipe less than 4 inches a Type 40 shield, attached to the pipe or insulation, may freely rest on a steel plate.
- (3) On pipe 4 inches and larger carrying medium less that 60 degrees F a Type 40 shield, attached to the pipe or insulation, may freely rest on a steel plate.
- 1. Pipe hangers on horizontal insulated pipe shall be the size of the outside diameter of the insulation. The insulation shall be continuous through the hanger on all pipe sizes and applications.
- m. Where there are high system temperatures and welding to piping is not desirable, the type 35 guide shall include a pipe cradle, welded to the guide structure and strapped securely to the pipe. The pipe shall be separated from the slide material by at least 4 inches or by an amount adequate for the insulation, whichever is greater.
- n. Hangers and supports for plastic pipe shall not compress, distort, cut or abrade the piping, and shall allow free movement of pipe except

where otherwise required in the control of expansion/contraction.

3.1.6 Welded Installation

Plumbing pipe weldments shall be as indicated. Changes in direction of piping shall be made with welding fittings only; mitering or notching pipe to form elbows and tees or other similar type construction will not be permitted. Branch connection may be made with either welding tees or forged branch outlet fittings. Branch outlet fittings shall be forged, flared for improvement of flow where attached to the run, and reinforced against external strains. Beveling, alignment, heat treatment, and inspection of weld shall conform to ASME B31.1. Weld defects shall be removed and repairs made to the weld, or the weld joints shall be entirely removed and rewelded. After filler metal has been removed from its original package, it shall be protected or stored so that its characteristics or welding properties are not affected. Electrodes that have been wetted or that have lost any of their coating shall not be used.

3.2 IDENTIFICATION SYSTEMS

3.2.1 Pipe Color Code Marking

Color code marking of piping shall be as specified in Section 09900 PAINTING, GENERAL.

3.3 PAINTING

Painting of pipes, hangers, supports, and other iron work, either in concealed spaces or exposed spaces, is specified in Section 09900 PAINTING, GENERAL.

3.4 TESTS

3.4.1 Plumbing System

The following tests shall be performed on the plumbing system in accordance with ICC Plumbing Code.

- a. Drainage and Vent Systems Tests.
- b. Water Supply Systems Tests.

3.4.2 Defective Work

If inspection or test shows defects, such defective work or material shall be replaced or repaired as necessary and inspection and tests shall be repeated. Repairs to piping shall be made with new materials. Caulking of screwed joints or holes will not be acceptable.

3.5 TABLES

TABLE I
PIPE AND FITTING MATERIALS FOR
DRAINAGE, WASTE, AND VENT PIPING SYSTEMS

					SERVIC	 E	
It	em # Pipe and Fitting Materials	A	В	С			F
1	Grooved pipe couplings, ferrous and non-ferrous pipe ASTM A 536 and ASTM A 47/A 47M	X	X		Х	Х	
2	Ductile iron grooved joint fittings for ferrous pipe ASTM A 536 and ASTM A 47/A 47M for use with Item 5	X	Х		Х	Х	
3	Bronze sand casting grooved joint pressure fittings for non-ferrous pipe ASTM B 584, for use with Item 5	X	X		Х	X	
4	Wrought copper grooved joint pressure pressure fittings for non-ferrous pipe ASTM B 75 C12200, ASTM B 152, ASTM B 152M, C11000, ASME B16.22 ASME B16.22 for use with Item 5	Х	X				
5	Malleable-iron threaded fittings, galvanized ASME B16.3 for use with Item 10				X	X	
6	Steel pipe, seamless galvanized, ASTM A 53/A 53M, Type S, Grade B	Х			X	X	
7	Seamless red brass pipe, ASTM B 43		Х	X			
8	Bronzed flanged fittings, ASME B16.24 for use with Items 11 and 14				X	X	
9	Cast copper alloy solder joint pressure fittings, ASME B16.18 for use with Item 14				Х	Х	
10	Seamless copper pipe, ASTM B 42				Х		
11	Cast bronze threaded fittings, ASME B16.15				X	X	
12	Copper drainage tube, (DWV),	Х*	Х	х*	X	Х	

TABLE I
PIPE AND FITTING MATERIALS FOR
DRAINAGE, WASTE, AND VENT PIPING SYSTEMS

					SERVIC	 E	
Ite	m # Pipe and Fitting Materials	A	В	С	D	E	F
	ASTM B 306						
13	Wrought copper and wrought alloy solder-joint drainage fittings. ASME B16.29	X	X	X	X	Х	
14	Cast copper alloy solder joint drainage fittings, DWV, ASME B16.23	Х	X	Х	Х	Х	
15	Acrylonitrile-Butadiene-Styrene (ABS) plastic drain, waste, and vent pipe and fittings ASTM D 2661, ASTM F 628	X	Х	Х	Х	Х	X
16	Polyvinyl Chloride plastic drain, waste and vent pipe and fittings, ASTM D 2665, ASTM F 891, (Sch 40) ASTM F 1760	Х	Х	Х	Х	X	Х
17	Process glass pipe and fittings, ASTM C 1053						Х
18	High-silicon content cast iron pipe and fittings (hub and spigot, and mechan ASTM A 518/A 518M	nical	X joint)	,		X	X
19	Polypropylene (PP) waste pipe and fittings, ASTM D 4101						Х
20	Filament-wound reinforced thermosetting resin (RTRP) pipe, ASTM D 2996						Х

SERVICE:

- A Underground Building Soil, Waste and Storm Drain
- B Aboveground Soil, Waste, Drain In Buildings
- C Underground Vent
- D Aboveground Vent
- E Interior Rainwater Conductors Aboveground
- F Corrosive Waste And Vent Above And Belowground
- * Hard Temper

TABLE II
PIPE AND FITTING MATERIALS FOR PRESSURE PIPING SYSTEMS

	TILE AND FITTING PARENTAGE FOR				
				VICE	
Ιt		А	В		
1			X		
	<pre>b. Same as "a" but not galvanized for use with Item 4b</pre>			X	
2	Grooved pipe couplings, ferrous pipe ASTM A 536 and ASTM A 47/A 47M, non-ferrous pipe, ASTM A 536 and ASTM A 47/A 47M,	Х	Х	Х	
3	Ductile iron grooved joint fittings for ferrous pipe ASTM A 536 and ASTM A 47/A 47M, for use with Item 2	X	X	X	
4	Steel pipe: a. Seamless, galvanized, ASTM A 53/A 53M, Type S, Grade B	X	Х	Х	X
	b. Seamless, black,ASTM A 53/A 53M,Type S, Grade B			Х	
5	Seamless red brass pipe, ASTM B 43	X	X		X
6	Bronze flanged fittings, ASME B16.24 for use with Items 5 and 7	X	X		X
7	Seamless copper pipe, ASTM B 42	X	X		X
8	Seamless copper water tube, ASTM B 88, ASTM B 88M	X**	X**	X**	X***
9	Cast bronze threaded fittings, ASME B16.15 for use with Items 5 and 7	Х	Х		X
10	Wrought copper and bronze solder-joint pressure fittings,	X	X	X	X

TABLE II
PIPE AND FITTING MATERIALS FOR PRESSURE PIPING SYSTEMS

				RVICE	
Ite	m No. Pipe and Fitting Materials	А	В	С	
	ASME B16.22 for use with Items 5 and 7				
11	Cast copper alloy solder-joint pressure fittings, ASME B16.18 for use with Items 8 and 9	X	X	Х	Х
12	Bronze and sand castings grooved joint pressure fittings for non-ferrous pipe ASTM B 584, for use with Item 2	X	X	Х	
13	Steel pipeline flanges, MSS SP-44	X	X		
14	Fittings: brass or bronze; ASME B16.15, and ASME B16.18 ASTM B 828	X	Х		
15	Carbon steel pipe unions, socket-welding and threaded, MSS SP-83	X	X	Х	
16	Malleable-iron threaded pipe unions ASME B16.39	X	X		
17	Nipples, pipe threaded ASTM A 733	X	X	Х	
18	Crosslinked Polyethylene (PEX) Plastic Pipe ASTM F 877.	X			X

- A Cold Water Aboveground
- B Hot Water 180 degrees F Maximum Aboveground
- C Compressed Air Lubricated
- D Cold Water Service Belowground

Indicated types are minimum wall thicknesses.

- ** Type L Hard
- $\mbox{***}$ Type K Hard temper with brazed joints only or type K-soft temper without joints in or under floors
 - **** In or under slab floors only brazed joints

-- End of Section --

SECTION 15569

OIL-FIRED FORCED HOT-WATER HEATING SYSTEM

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AIR MOVEMENT AND CONTROL ASSOCIATION (AMCA)

AMCA 801 (1992) Industrial Process/Power Generation
Fans: Specification Guidelines

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z21.13 (1991; Z21.13a; Z21.13b) Gas-Fired
Low-Pressure Steam and Hot Water Boilers

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A 53/A 53M	(1999b) Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A 105/A 105M	(1998) Carbon Steel Forgings for Piping Applications
ASTM A 167	(1999) Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
ASTM A 183	(1983; R 1998) Carbon Steel Track Bolts and Nuts
ASTM A 193/A 193M	(1999a) Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service
ASTM A 234/A 234M	(1999) Piping Fittings of Wrought Carbon Steel and Alloy Steel for Moderate and High Temperature Services
ASTM A 366/A 366M	(1997el) Steel, Sheet, Carbon, Cold-Rolled, Commercial Quality
ASTM A 515/A 515M	(1989; R 1997) Pressure Vessel Plates, Carbon Steel, for Intermediate- and Higher-Temperature Service
ASTM A 516/A 516M	(1990; R 1996) Pressure Vessel Plates,

Carbon Steel, for Moderate- and

	Lower-Temperature Service
ASTM A 536	(1984; R 1999el) Ductile Iron Castings
ASTM A 653/A 653M	(1999a) Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM B 32	(1996) Solder Metal
ASTM B 62	(1993) Composition Bronze or Ounce Metal Castings
ASTM B 75	(1999) Seamless Copper Tube
ASTM B 75M	(1999) Seamless Copper Tube (Metric)
ASTM B 88	(1999) Seamless Copper Water Tube
ASTM B 88M	(1999) Seamless Copper Water Tube (Metric)
ASTM B 813	(1993) Liquid and Paste Fluxes for Soldering Applications of Copper and Copper Alloy Tube
ASTM B 828	(1998) Making Capillary Joints by Soldering of Copper and Copper Alloy Tube and Fittings
ASTM C 27	(1998) Fireclay and High-Alumina Refractory Brick
ASTM C 34	(1996) Structural Clay Load-Bearing Wall Tile
ASTM C 155	(1997) Standard Classification of Insulating Firebrick
ASTM C 401	(1991; R 1995el) Alumina and Alumina-Silicate Castable Refractories
ASTM D 596	(1991; R 1995) Reporting Results of Analysis of Water
ASTM D 1784	(1999a) Rigid Poly(Vinyl Chloride) (PVC) Compounds and Chlorinated Poly(Vinyl Chloride) (CPVC) Compounds
ASTM D 2000	(1999) Rubber Products in Automotive Applications
ASTM F 872	(1984; R 1990) Filter Units, Air Conditioning: Viscous-Impingement Type, Cleanable

ASTM F 876	(1999a) Crosslinked Polyethylene (PEX) Tubing
ASTM F 1097	(1991; R 1996) Mortar, Refractory (High-Temperature, Air-Setting)
ASTM F 1139	(1988; R 1998) Standard Specification for Steam Traps and Drains
ASME INTERNATIONAL (ASM	ME)
ASME B1.20.1	(1983; R 1992) Pipe Threads, General Purpose (Inch)
ASME B16.3	(1998) Malleable Iron Threaded Fittings
ASME B16.4	(1998) Gray Iron Threaded Fittings
ASME B16.5	(1996; B16.5a) Pipe Flanges and Flanged Fittings NPS 1/2 thru NPS 24
ASME B16.9	(1993) Factory-Made Wrought Steel Buttwelding Fittings
ASME B16.11	(1996) Forged Fittings, Socket-Welding and Threaded
ASME B16.15	(1985; R 1994) Cast Bronze Threaded Fittings Classes 125 and 250
ASME B16.18	(1984; R 1994) Cast Copper Alloy Solder Joint Pressure Fittings
ASME B16.21	(1992) Nonmetallic Flat Gaskets for Pipe Flanges
ASME B16.22	(1995; B16.22a1998) Wrought Copper and Copper Alloy Solder Joint Pressure Fittings
ASME B16.26	(1988) Cast Copper Alloy Fittings for Flared Copper Tubes
ASME B16.34	(1997) Valves - Flanged, Threaded, and Welding End
ASME B16.39	(1998) Malleable Iron Threaded Pipe Unions Classes 150, 250, and 300
ASME B19.3	(1991; B19.3a; B19.3b) Safety Standard for Compressors for Process Industries
ASME B31.1	(1998) Power Piping

ASME B31.5 (1992; B31.5a1994) Refrigeration Piping ASME B40.1 (1991) Gauges - Pressure Indicating Dial Type - Elastic Element ASME BPV IV (1998) Boiler and Pressure Vessel Code; Section IV, Heating Boilers ASME BPV VIII Div 1 (1998) Boiler and Pressure Vessel Code; Section VIII, Pressure Vessels Division 1 - Basic Coverage ASME BPV IX (1998) Boiler and Pressure Vessel Code; Section IX, Welding and Brazing Qualifications ASME CSD-1 (1998) Controls and Safety Devices for Automatically Fired Boilers ASME PTC 10 (1997) Compressors and Exhausters AMERICAN WATER WORKS ASSOCIATION (AWWA) AWWA C606 (1997) Grooved and Shouldered Joints AMERICAN WELDING SOCIETY (AWS) AWS A5.8 (1992) Filler Metals for Brazing and Braze Welding AWS B2.2 (1991) Brazing Procedure and Performance Qualification COMMERCIAL ITEM DESCRIPTIONS (CID) CID A-A-1419 (Rev D; Canc. Notice 1) Filter Element, Air Conditioning (Viscous-Impingement and Dry Types, Replaceable) COPPER DEVELOPMENT ASSOCIATION (CDA) CDA Tube Handbook (1995) Copper Tube Handbook EXPASION JOINT MANUFACTURERS ASSOCIATION (EJMA) EJMA Stds (1998; 7th Edition) EJMA Standards HYDRONICS INSTITUTE DIVISION OF GAMA (HYI) HYI-01 (1998) I=B=R Ratings for Boilers, Baseboard Radiation and Finned Tube (Commercial) Radiation HYI-400 (1998) I=B=R Product Floor Heating

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-25	(1998) Standard Marking System for Valves, Fittings, Flanges and Unions	
MSS SP-58	(1993) Pipe Hangers and Supports - Materials, Design and Manufacture	
MSS SP-69	(1996) Pipe Hangers and Supports - Selection and Application	
MSS SP-70	(1998) Cast Iron Gate Valves, Flanged and Threaded Ends	
MSS SP-71	(1997) Gray Iron Swing Check Valves, Flanges and Threaded Ends	
MSS SP-72	(1999) Ball Valves with Flanged or Butt-Welding Ends for General Service	
MSS SP-73	(1991; R 1996) Brazing Joints for Copper and Copper Alloy Pressure Fittings	
MSS SP-78	(1998) Cast Iron Plug Valves, Flanged and Threaded Ends	
MSS SP-80	(1997) Bronze Gate, Globe, Angle and Check Valves	
MSS SP-85	(1994) Cast Iron Globe & Angle Valves, Flanged and Threaded Ends	
MSS SP-110	(1996) Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends	
NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)		
NEMA 250	(1997) Enclosures for Electrical Equipment (1000 Volts Maximum)	
NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)		
NFPA 31	(1997 TIA 97-1) Installation of Oil Burning Equipment	
NFPA 54	(1999) National Fuel Gas Code	
NFPA 70	(1999) National Electrical Code	
NFPA 211	(2000) Chimneys, Fireplaces, Vents, and Solid Fuel-Burning Appliances	

NFPA 8501 (1997) Single Burner Boiler Operation

UNDERWRITERS LABORATORIES (UL)

UL 296	(1994; Rev Sep 1998) Oil Burners
UL 726	(1995; Rev thru Jan 1999) Oil-Fired Boiler Assemblies
UL 795	(1999) Commercial-Industrial Gas Heating Equipment
UL 1738	(1993; Rev thru Mar 1998) Venting Systems for Gas-Burning Appliances, Categories II, III and IV
UL Gas&Oil Dir	(1999) Gas and Oil Equipment Directory

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittals for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Heating System; G WA Piping Installation; G WA

Detail drawings consisting of equipment layout including installation details and electrical connection diagrams; combustion and safety control diagrams; ductwork layout showing the location of supports and hangers, and piping layout showing the location of guides and anchors, and typical support details. Drawings shall include any information required to demonstrate that the system has been coordinated and will properly function as a unit and shall show equipment relationship to other parts of the work, including clearances required for operation and maintenance.

SD-03 Product Data

Manufacturer's Catalog Data; G WA

Manufacturer's catalog data shall be included with the detail drawings for the following items:

Boilers
Fuel Burning Equipment
Combustion Control Equipment
Pumps
Fittings and Accessories

The data shall show model, size, options, etc., that are intended for consideration. Data submitted shall be adequate to demonstrate compliance with contract requirements.

Spare Parts Data; G WA

Spare parts data for each different item of material and equipment, after approval of the detail drawings and no later than 2 months prior to the date of beneficial occupancy. The data shall include a complete list of parts and supplies, with current unit prices and source of supply, and a list of the parts recommended by the manufacturer to be replaced after 1 and 3 years of service.

Tests; G WA

Proposed test schedules for the heating system and fuel system tests, at least 2 weeks prior to the start of related testing.

Rigging Plan; G WA

A detailed rigging plan on how the Contractor intends to remove the existing boiler and install the new boiler shall be submitted for approval.

SD-06 Test Reports

Heating System Tests; G WA Fuel System Tests; G WA

Test reports for the heating system tests and the fuel system test, upon completion of testing complete with results.

SD-07 Certificates

Boiler Emissions

Written certification by the boiler manufacturer that each boiler furnished complies with Federal, state, and local regulations for emissions. The certification shall also include a description of applicable emission regulations.

SD-10 Operation and Maintenance Data

Boiler System; G WA.

Six complete manuals listing step-by-step procedures required for system startup, operation, shutdown, and routine maintenance, at least 2 weeks prior to field training. The manuals shall include the manufacturer's name, model number, parts list, simplified wiring and control diagrams, troubleshooting guide, and recommended service organization (including address and telephone number) for each item of equipment.

1.3 GENERAL REQUIREMENTS

1.3.1 Standard Products

Materials and equipment shall be the standard products of a manufacturer regularly engaged in the manufacture of the products and shall essentially duplicate items that have been in satisfactory use for at least 2 years prior to bid opening. Equipment shall be supported by a service organization that is, in the opinion of the Contracting Officer, reasonably convenient to the site.

1.3.2 Asbestos Prohibition

Asbestos and asbestos-containing products shall not be used.

1.3.3 Nameplates

Each major component of equipment shall have the manufacturer's name, address, type or style, model or serial number, and catalog number on a plate secured to the equipment. Each pressure vessel shall have an approved ASME stamp.

1.3.4 Equipment Guards

Belts, pulleys, chains, gears, couplings, projecting setscrews, keys, and other rotating parts exposed to personnel contact shall be fully enclosed or guarded in accordance with OSHA requirements. High temperature equipment and piping exposed to contact by personnel or where it creates a potential fire hazard shall be properly guarded or covered with insulation of a type specified.

1.3.5 Verification of Dimensions

The Contractor shall become familiar with details of the work, verify dimensions in the field, and shall advise the Contracting Officer of any discrepancy before performing any work or ordering any materials.

1.3.6 Welding

Boilers and piping shall be welded and brazed in accordance with qualified procedures using performance-qualified welders and welding operators. Procedures and welders shall be qualified in accordance with ASME BPV IX. Welding procedures qualified by others, and welders and welding operators qualified by another employer may be accepted as permitted by ASME B31.1.

1.4 PERMITS

It shall be the Contractor's responsibility to obtain all construction permits and licenses required for the successful completion and startup of the project.

1.5 MANUFACTURER'S SERVICES

Services of a manufacturer's representative who is experienced in the installation, adjustment, and operation of the equipment specified shall be provided. The representative shall supervise the installing, adjusting, and testing of the equipment.

1.6 DELIVERY AND STORAGE

Equipment delivered and placed in storage shall be protected from the weather, humidity and temperature variations, dirt and dust, and other contaminants.

PART 2 PRODUCTS

2.1 BOILERS

Each boiler shall have the output capacity in British thermal units per hour (Btuh) as indicated when fired with the specified fuels. The boiler shall be furnished complete with the oil burning equipment, boiler fittings and trim, automatic controls, forced draft fan, electrical wiring, insulation, piping connections, and protective jacket. The boiler shall be completely assembled and tested at the manufacturer's plant. Boiler auxiliaries including fans, motors, drives, and similar equipment shall be provided with at least 10 percent excess capacity to allow for field variations in settings and to compensate for any unforeseen increases in pressure losses in appurtenant piping and ductwork. However, the boiler safety devices shall not be sized for a 10 percent excess capacity. The boiler and its accessories shall be designed and installed to permit ready accessibility for operation, maintenance, and service. Boilers shall be designed, constructed, and equipped in accordance with ASME BPV IV. Each boiler shall be of the firetube type and designed for water service as specified herein. The boiler capacity shall be based on the ratings shown in HYI-01 or as certified by the American Boiler Manufacturers Association.

2.1.1 Firetube Boiler

Boiler shall be self-contained, four-pass, packaged type, complete with all accessories, mounted on a structural steel base. When the boilers are operating at maximum output, the heat output rates shall not be greater than 6,700 Btu/hr per square ft of fireside heating surface.

2.1.2 Hot Water Heating Boilers

The hot water heating boiler shall be capable of operating at the specified maximum continuous capacity without damage or deterioration to the boiler, its setting, firing equipment, or auxiliaries. The rated capacity shall be the capacity at which the boiler will operate continuously while maintaining at least the specified minimum efficiency. The boiler design conditions shall be as follows:

- a. Boiler design pressure 30 psig.
- b. Operating pressure at boiler outlet 10 psig.
- c. Hot water temperature 160 degrees F.

- d. Temperature differential between boiler discharge and system return 20 degrees F.
- e. Water pressure drop 10 psig.
- f. Outdoor ambient air temperature 98 degrees F (max), 7 degrees F (min).
- q. Site elevation 135 feet.
- h. Rated capacity 5,021,000 Btuh or 150 horsepower when fired with #2 oil.
- i. Oil fired boilers with a capacity of greater than or equal to 300,000 Btuh shall have a thermal efficiency of at least 83 percent when fired at the maximum and minimum ratings allowed by the controls.

2.2 FUEL BURNING EQUIPMENT

Boiler shall be designed to burn commercial no. 2 oil. Each boiler shall comply with Federal, state, and local emission regulations.

2.2.1 Burners

2.2.1.1 Oil-Fired Burners and Controls

Oil-fired burners and controls for oil-fired units firing No. 2 oil shall be atomizing, forced-draft type in conformance with UL 726. Oil-fired units less than 12,500,000 Btuh input shall conform to ASME CSD-1. Turndown range shall be 4:1 when firing #2 oil.

2.2.1.2 Air Atomizer

Air atomizer shall be of the inside mix type utilizing air mixing with the oil inside the nozzle. No moving parts shall be required within the atomizer assembly. Unit shall be capable of completely atomizing the oil through a minimum capacity range of 4 to 1 without changing nozzles or sprayer plates and when supplied with air at a maximum pressure of 15 psig. Capacity of unit shall be adjustable. Unit shall be furnished with a blowout valve so that air may be blown through the oil passages to clear them of any accumulation. A diffuser designed to stabilize the flame shall be mounted near the furnace end of the atomizer in such a position that oil will not strike it.

2.2.2 Draft Fans

Fans conforming to AMCA 801 forced-draft shall be furnished as an integral part of boiler design. Fans shall be centrifugal with backward-curved blades or axial flow type. Each fan shall be sized for output volume and static pressure rating sufficient for pressure losses, excess air requirements at the burner, leakages, temperature, and elevation corrections for worst ambient conditions, all at full combustion to meet

net-rated output at normal firing conditions, plus an overall excess air volume of 10 percent against a 20 percent static overpressure. Noise levels for fans shall not exceed 85 decibels in any octave band at a 3 foot station. Forced draft fan bearings shall be air cooled.

2.2.2.1 Draft Fan Control

Forced-draft centrifugal fans shall have inlet vane controls or shall have variable speed control where indicated. Inlet vanes shall be suitable for use with combustion control equipment.

2.2.2.2 Draft Fan Drives

Fans shall be driven by electric motors. Electric motor shall be totally enclosed fan-cooled, suitable for installation in a Class II, Division 1, Group F, hazardous location conforming to NFPA 70. Motor starter shall be watertight explosion-proof enclosure and shall be furnished with four auxiliary interlock contacts.

2.2.3 Draft Damper

Boilers shall be provided with automatic dampers, draft hoods, or barometric dampers as recommended by the boiler manufacturer to maintain proper draft in the boiler. Draft damper shall be provided in a convenient and accessible location in the flue gas outlet from the boiler. Automatic damper shall be arranged for automatic operation by means of a damper regulator.

2.3 COMBUSTION CONTROL EQUIPMENT

Combustion control equipment shall be provided as a system by a single manufacturer. Field installed automatic combustion control system shall be installed in accordance with the manufacturer's recommendations and under the direct supervision of a representative of the control manufacturer. The boiler water temperature shall be controlled by a water temperature controller. The equipment shall operate electrically.

2.3.1 Electrical controls

Electrical control devices shall be rated at 120volts and shall be connected as specified in Section 16415 ELECTRICAL WORK, INTERIOR.

2.3.2 Water Temperature Controller

The controller shall be of sturdy construction and shall be protected against dust and dampness. The thermostatic element shall be inserted in a separable socket installed in the upper part of the boiler near the water outlet. Fixed position (on-off) and three position (high-low-off) controller shall operate on a 10 degree F differential over an adjustable temperature range of approximately 140 to 220 degrees F. Modulating controllers shall control the fuel burning equipment to maintain set boiler water temperature within 2 percent.

2.3.3 Boiler Combustion Controls and Positioners

- a. Oil fired boiler units shall be provided with modulating combustion controls with spark ignited No. 2 oil pilot. Modulating controls shall be provided with a means for manually controlling the firing rate.
- b. Modulating control function shall be accomplished using positioning type controls. Air flow ratio and fuel control valve shall be controlled by relative positions of operative levers on a jackshaft responding to a water temperature controller. Positioning type combustion control equipment shall include draft controls with synchronized fuel feed and combustion air supply controls, and shall maintain the proper air/fuel ratio. The desired furnace draft shall be maintained within 0.01 inch of water column.

2.3.4 Combustion Safety Controls and Equipment

Combustion safety controls and equipment shall be UL listed, microprocessor-based distributed process controller. The system shall include mounting hardware, wiring and cables, and associated equipment. The controller shall be mounted completely wired, programmed, debugged, and tested to perform all of its functions. The controller shall process the signals for complete control and monitoring of the boiler including provision for a slow worm-up of a cold boiler. This shall include maintaining boiler status, starting and stopping all control functions, sequencing control functions and signaling alarm conditions. The program shall be documented and include cross references in description of coils and contacts. Microprocessor shall be able to perform self diagnostics and contain a message center to provide operator with status and failure mode information. Controllers for each boiler shall be mounted on a separate, free standing panel adjacent to the boiler or for packaged boilers on the boiler supporting structure. Control systems and safety devices for automatically fired boilers shall conform to ASME CSD-1. Electrical combustion and safety controls shall be rated at 120 volts, single phase, 60 Hz and shall be connected as specified in Section 16415 ELECTRICAL WORK, INTERIOR. A 4 inch diameter alarm bell shall be provided and shall be located where indicated or directed. The alarm bell shall ring when the boiler is shut down by any safety control or interlock. Indicating lights shall be provided on the control panel. A red light shall indicate flame failure, and a green light shall indicate that the main fuel valve is open. The following shutdown conditions shall require a manual reset before the boiler can automatically recycle:

- a. Flame failure.
- b. Failure to establish pilot flame.
- c. Failure to establish main flame.
- d. Supplementary low-water cutoff.
- e. High temperature cutoff.

2.3.4.1 Low-water Cutoff

Low water cutoff shall be float actuated switch or electrically actuated probe type low-water cutoff. Float chamber shall be provided with a blow-down connection. Cutoff shall cause a safety shutdown and sound an alarm when the boiler water level drops below a safe minimum level. A safety shutdown due to low water shall require manual reset before operation can be resumed and shall prevent recycling of the burner. The cutoff shall be in strict accordance to the latest version of code, ASME CSD-1 Controls and Safety Devices for Automatically Fired Boilers.

c. Supplementary Low-Water Cutoff: Supplementary low-water cutoff of the electrically operated probe type or float activated type shall be provided in addition to the low-water cutoff required above on each boiler. Supplementary low-water cutoff shall be mounted directly in the boiler shell and shall be set below the low-water cutoff required above.

2.3.4.2 Water Flow Interlock

Hot water boiler limit controls shall be provided to include protection for low boiler water flow and high boiler water temperature. The limit controls shall be interlocked with the combustion control system to effect boiler alarm and shutdown. The controls shall not allow boiler startup unless hot water flow is proven.

2.4 PUMPS

2.4.1 Fuel Oil Pumping and Heating Sets

The integrated, shop-fabricated oil pumping shall be UL approved. Two positive displacement oil meters shall be provided. One meter shall be located on the fuel supply line. The other meter shall be located on the fuel return line. Fuel pump shall be electric-motor driven with a capacity of approximately twice the maximum burning rate of the boiler.

2.4.2 Hot Water and Boiler Circulating Pumps

Two existing hot water circulating pumps (one operating/one standby) shall be used for circulating hot water through the boiler and the hydronic heating system. The Contractor shall coordinate and implement all required interlocks between the pumps and the boiler.

2.5 COLD WATER CONNECTIONS

Connections shall be provided which includes consecutively in line a strainer, backflow prevention device, and water pressure regulator in that order in the direction of the flow. The backflow prevention device shall be provided as indicated and in compliance with Section 15400, PLUMBING, GENERAL PURPOSE. Cold water fill connections shall be made to the water supply system as indicated. Necessary pipe, fittings, and valves required for water connections between the boiler and cold water main shall be provided. The pressure regulating valve shall be of a type that will not stick or allow pressure to build up on the low side. The valve shall be set to maintain a terminal pressure of approximately, 5 psi in excess of the static head on the system and shall operate within a 2 psi tolerance regardless of cold water supply piping pressure and without objectionable

noise under any condition of operation.

2.6 FITTINGS AND ACCESSORIES

Boiler fittings and accessories shall be installed with each boiler in accordance with ASME BPV IV, unless otherwise specified.

2.6.1 Conventional Breeching and Stacks

2.6.1.1 Breeching

The boiler shall be connected to the stack or flue by breeching constructed of black steel sheets not less than 0.0478 inch thick nor less than thickness of stack, whichever is larger. Plastic materials polyetherimide (PEI) and polyethersulfone (PES) are forbidden to be used for vent piping of combustion gases. The clear distance between any portion of the breeching surface and any combustible material shall not be less than that specified in NFPA 211. Joints and seams shall be securely fastened and made airtight. Suitable hinged and gasketed cleanouts shall be provided, which will permit cleaning the entire smoke connection without dismantling. Flexible-type expansion joints shall be provided as required and shall not require packing.

2.6.1.2 Stacks

Existing stack is relatively new and may be used with the new boiler provided the existing stack is compatible with the new boiler. If new stack is required, a prefabricated double wall stack system shall extend above the room to a minimum height required by code at no additional cost to the government. The stack shall be 20 feet in height when assembled on the boiler and measured from the ground line. The inner stack shall be 304 stainless steel having a thickness of not less than 0.035 inch. The outer stack shall be sheet steel having a thickness of not less than 0.025 inch. A method of maintaining concentricity between the inner and outer stacks shall be incorporated. The joint between stack sections shall be sealed to prevent the gas leakage. The stack shall be provided with a rain hood and roof penetration shall be sealed to prevent rain from entering the boiler room.

2.6.2 Steel Sheets

2.6.2.1 Galvanized Steel

Galvanized steel shall be ASTM A 653/A 653M.

2.6.2.2 Uncoated Steel

Uncoated steel shall be ASTM A 366/A 366M, composition, condition, and finish best suited to the intended use. Gauge numbers specified refer to manufacturer's standard gauge.

2.6.3 Gaskets

Gaskets shall be nonasbestos material in accordance with ASME B16.21, full

face or self-centering type. The gaskets shall be of the spiral wound type with graphite filler material.

2.6.4 Steel Pipe and Fittings

2.6.4.1 Steel Pipe

Steel pipe shall be ASTM A 53/A 53M, Type E or S, Grade A or B, black steel, standard weight.

2.6.4.2 Steel Pipe Fittings

Fittings shall have the manufacturer's trademark affixed in accordance with MSS SP-25 so as to permanently identify the manufacturer.

2.6.4.3 Steel Flanges

Flanged fittings including flanges, bolts, nuts, bolt patterns, etc. shall be in accordance with ASME B16.5 class 150 and shall have the manufacturers trademark affixed in accordance with MSS SP-25. Flange material shall conform to ASTM A 105/A 105M. Flanges for high temperature water systems shall be serrated or raised-face type. Blind flange material shall conform to ASTM A 516/A 516M cold service and ASTM A 515/A 515M for hot service. Bolts shall be high strength or intermediate strength with material conforming to ASTM A 193/A 193M.

2.6.4.4 Welded Fittings

Welded fittings shall conform to ASTM A 234/A 234M with WPA marking. Buttwelded fittings shall conform to ASME B16.9, and socket-welded fittings shall conform to ASME B16.11.

2.6.4.5 Cast-Iron Fittings

Fittings shall be ASME B16.4, Class 125, type required to match connecting piping.

2.6.4.6 Malleable-Iron Fittings

Fittings shall be ASME B16.3, type as required to match connecting piping.

2.6.4.7 Unions

Unions shall be ASME B16.39, Class 150.

2.6.4.8 Threads

Pipe threads shall conform to ASME B1.20.1.

2.6.5 Copper Tubing and Fittings

2.6.5.1 Copper Tubing

Tubing shall be ASTM B 88, ASTM B 88M, Type K or L. Adapters for copper

tubing shall be brass or bronze for brazed fittings.

2.6.5.2 Solder-Joint Pressure Fittings

Wrought copper and bronze solder-joint pressure fittings shall conform to ASME B16.22 and ASTM B 75. Cast copper alloy solder-joint pressure fittings shall conform to ASME B16.18 and ASTM B 828.

2.6.5.3 Flared Fittings

Cast copper alloy fittings for flared copper tube shall conform to ASME B16.26 and ASTM B62.

2.6.5.4 Adapters

Adapters may be used for connecting tubing to flanges and to threaded ends of valves and equipment. Extracted brazed tee joints produced with an acceptable tool and installed as recommended by the manufacturer may be used.

2.6.5.5 Threaded Fittings

Cast bronze threaded fittings shall conform to ASME B16.15.

2.6.5.6 Brazing Material

Brazing material shall conform to AWS A5.8.

2.6.5.7 Brazing Flux

Flux shall be in paste or liquid form appropriate for use with brazing material. Flux shall be as follows: lead-free; have a 100 percent flushable residue; contain slightly acidic reagents; contain potassium borides, and contain fluorides. Silver brazing materials shall be in accordance with AWS A5.8.

2.6.5.8 Solder Material

Solder metal shall conform to ASTM B 32 95-5 tin-antimony.

2.6.5.9 Solder Flux

Flux shall be either liquid or paste form, non-corrosive and conform to ASTM B 813.

2.6.6 Valves

Valves shall be Class 125 and shall be suitable for the application. Grooved ends per AWWA C606 may be used for water service only. Valves in nonboiler external piping shall meet the material, fabrication and operating requirements of ASME B31.1. The connection type of all valves shall match the same type of connection required for the piping on which installed.

2.6.6.1 Gate Valves

Gate valves 2-1/2 inches and smaller shall conform to MSS SP-80 bronze rising stem, threaded, solder, or flanged ends. Gate valves 3 inches and larger shall conform to MSS SP-70 cast iron bronze trim, outside screw and yoke, flanged, or threaded ends.

2.6.6.2 Globe Valves

Globe valves 2-1/2 inches and smaller shall conform to MSS SP-80, bronze, threaded, soldered, or flanged ends. Globe valves 3 inches and larger shall conform to MSS SP-85, cast iron, bronze trim, flanged, or threaded ends.

2.6.6.3 Check Valves

Check valves 2-1/2 inches and smaller shall conform to MSS SP-80, bronze, threaded, soldered, or flanged ends. Check valves 3 inches and larger shall conform to MSS SP-71, cast iron, bronze trim, flanged, or threaded ends.

2.6.6.4 Angle Valves

Angle valves 2-1/2 inches and smaller shall conform to MSS SP-80 bronze, threaded, soldered, or flanged ends. Angle valves 3 inches and larger shall conform to MSS SP-85, cast iron, bronze trim, flanged, or threaded ends.

2.6.6.5 Ball Valves

Ball valves 1/2 inch and larger shall conform to MSS SP-72 or MSS SP-110, ductile iron or bronze, threaded, soldered, or flanged ends.

2.6.6.6 Plug Valves

Plug valves 2 in. and larger shall conform to MSS SP-78. Plug valves smaller than 2 in. shall conform to ASME B16.34.

2.6.6.7 Balancing Valves

Balancing valves shall have meter connections with positive shutoff valves. An integral pointer shall register the degree of valve opening. Valves shall be calibrated so that flow rate can be determined when valve opening in degrees and pressure differential across valve is known. Each balancing valve shall be constructed with internal seals to prevent leakage and shall be supplied with preformed insulation. Valves shall be suitable for 250 degrees F temperature and working pressure of the pipe in which installed. Valve bodies shall be provided with tapped openings and pipe extensions with shutoff valves outside of pipe insulation. The pipe extensions shall be provided with quick connecting hose fittings for a portable meter to measure the pressure differential. One portable differential meter shall be furnished. The meter suitable for the operating pressure specified shall be complete with hoses, vent, and shutoff valves, and carrying case. In lieu of the balancing valve with integral metering connections, a ball

valve or plug valve with a separately installed orifice plate or venturi tube may be used for balancing.

2.6.6.8 Butterfly Valves

Butterfly valves shall be 2-flange type or lug wafer type, and shall be bubbletight at 150 psig. Valve bodies shall be cast iron, malleable iron, or steel. ASTM A 167, Type 404 or Type 316, corrosion resisting steel stems, bronze, or corrosion resisting steel discs, and synthetic rubber seats shall be provided. Valves smaller than 8 inches shall have throttling handles with a minimum of seven locking positions. Valves 8 inches and larger shall have totally enclosed manual gear operators with adjustable balance return stops and position indicators. Valves in insulated lines shall have extended neck to accommodate insulation thickness.

2.6.6.9 Drain valves

Drain valves shall be provided at each drain point of blowdown as recommended by the boiler manufacturer. Piping shall conform to ASME BPV IV and ASTM A 53/A 53M.

2.6.6.10 Safety Valves

Safety valves shall have steel bodies and shall be equipped with corrosion-resistant trim and valve seats. The valves shall be properly guided and shall be positive closing so that no leakage can occur. Adjustment of the desired back-pressure shall cover the range between 2 and 10 psig. The adjustment shall be made externally, and any shafts extending through the valve body shall be provided with adjustable stuffing boxes having renewable packing. Boiler safety valves of proper size and of the required number, in accordance with ASME BPV IV, shall be installed. Each discharge pipe for hot water service shall be pitched away from the valve seat.

2.6.7 Strainers

Basket and "Y" type strainers shall be the same size as the pipelines in which they are installed. The strainer bodies shall be heavy and durable, fabricated of cast iron, and shall have bottoms drilled and tapped with a gate valve attached for blowdown purposes. Strainers shall be designed for 150 psig service and 250 degrees F. The bodies shall have arrows clearly cast on the sides indicating the direction of flow. Each strainer shall be equipped with an easily removable cover and sediment screen.

2.6.8 Pressure Gauges

Gauges shall conform to ASME B40.1 and shall be provided with throttling type needle valve or a pulsation dampener and shutoff valve. Minimum dial size shall be 3-1/2 inches. A pressure gauge shall be provided for each boiler in a visible location on the boiler. Pressure gauges shall be provided with readings in psi. Pressure gauges shall have an indicating pressure range that is related to the operating pressure of the fluid in accordance with the following table:

Operating Pressure (psi) Pressure Range (psi)

76-150 0-200 16-75 0-100

2-15 0-30 (retard)

2.6.9 Thermometers

Thermometers shall be provided with wells and separable corrosion-resistant steel sockets. Thermometers for inlet water and outlet water for each hot water boiler shall be provided in a visible location on the boiler. Thermometers shall have brass, malleable iron, or aluminum alloy case and frame, clear protective face, permanently stabilized glass tube with indicating-fluid column, white face, black numbers, and a minimum 9 inch scale. The operating range of the thermometers shall be 32 - 212 degrees Fahrenheit. The thermometers shall be provided with readings in degrees Fahrenheit.

2.6.10 Air Vents

2.6.10.1 Manual Air Vents

Manual air vents shall be brass or bronze valves or cocks suitable for the pressure rating of the piping system and furnished with threaded plugs or caps.

2.6.10.2 Automatic Air Vents

Automatic air vents shall be 3/4 inch quick-venting float and vacuum air valves. Each air vent valve shall have a large port permitting the expulsion of the air without developing excessive back pressure, a noncollapsible metal float which will close the valve and prevent the loss of water from the system, an air seal that will effectively close and prevent the re-entry of air into the system when subatmospheric pressures prevail therein, and a thermostatic member that will close the port against the passage of steam from the system. The name of the manufacturer shall be clearly stamped on the outside of each valve. The air vent valve shall be suitable for the pressure rating of the piping system.

2.7 ELECTRICAL EQUIPMENT

Electric motor-driven equipment shall be provided complete with motors, motor starters, and necessary control devices. Electrical equipment, motor control devices, motor efficiencies and wiring shall be as specified in Section 16415 ELECTRICAL WORK, INTERIOR. Motors which are not an integral part of a packaged boiler shall be rated for high efficiency service. Motors which are an integral part of the packaged boiler shall be the highest efficiency available by the manufacturer of the packaged boiler. Motor starters shall be provided complete with properly sized thermal overload protections and other appurtenances necessary for the motor control specified. Starters shall be furnished in explosion-proof, Class I, division I enclosures. Manual or automatic control and protective or signal devices required for the operation specified and any control wiring

required for controls and devices but not shown shall be provided.

2.7.1 Motor Ratings

Motors shall be suitable for the voltage and frequency provided. Motors 1/2 hp and larger shall be three-phase, unless otherwise indicated. Motors shall be of sufficient capacity to drive the equipment at the specified capacity without exceeding the nameplate rating on the motor.

2.7.2 Motor Controls

Motor controllers shall be provided complete with properly sized thermal overload protection. Manual or automatic control and protective or signal devices required for the operation specified and any wiring required to such devices shall be provided. Where two-speed or variable-speed motors are indicated, solid-state variable-speed controllers may be provided to accomplish the same function. Solid state variable speed controllers shall be utilized for fractional through 10 hp ratings. Adjustable frequency drives shall be used for larger motors.

2.8 INSULATION

Shop and field-applied insulation shall be as specified in Section 15080 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

2.9 TOOLS

Special tools shall be furnished. Special tools shall include uncommon tools necessary for the operation and maintenance of boilers, burners, pumps, fans, controls, meters, special piping systems, and other equipment. Small hand tools shall be furnished within a suitable cabinet, mounted where directed.

2.9.1 Breeching Cleaner

A cleaner shall be provided to clean the breeching. The cleaner shall have a jointed handle of sufficient length to clean the breeching without dismantling.

2.9.2 Tube Brush

If a firetube boiler is being furnished, a tube brush, with steel bristles and jointed handle of sufficient length to clean full length of firetubes, shall be provided.

2.9.3 Wrenches

Wrenches shall be provided as required for specialty fittings such as manholes, handholes, and cleanouts. One set of extra gaskets shall be provided for all manholes and handholes, for pump barrels, and other similar items of equipment. Gaskets shall be packaged and properly identified.

2.10 FUEL OIL STORAGE SYSTEM

Existing fuel storage system shall be used to supply fuel to the new boiler.

2.11 BOILER MANAGEMENT CONTROL

In addition to the boiler control already specified, the Contractor shall furnish, install, and place in operating condition a micro-computer based Boiler Management Control as described herein. The system shall be compatible with Frreye boiler management control Washington Aqueduct has at its other boiler plants..

2.11.1 Major Functions

The boiler management system shall provide the following major functions:

- a. Automatic Prepurge, Pilot Flame Establishing Period, Main Flame Establishing Period, Run, and Postpurge.
- b. Flame proving and lockout on flame failure during pilot flame proving, main flame proving, or run.
 - c. Low fire damper motor position for flame ignition trials.
- d. Full modulating control of fuel and combustion air as well as firing rate control.
- e. First out annunciation and diagnostic via a liquid crystal display (LCD).
 - f. Non-volatile lockout and history files.
 - g. Capability for remote or local communication to a personal computer.
 - u. Ability to be able to be installed in a continuous 0.5G environment.

2.11.2 Sequence of Operation

2.11.2.1 Safety Provisions

The Boiler Management Control shall provide the following safety provisions:

- a. Dynamic Self Check safety circuit. The Boiler Management Control's micro-computer should test itself and related hardware for proper circuit operation.
- b. Examine all load terminals to assure it is capable of recognizing the true status of external controls, limits, and interlocks. If any input fails this test the boiler room control should lockout on safety shutdown.
- c. Closed Loop Logic test of all safety critical loads (oil main valve, ignition transformer, and pilot valve) and must be able to lockout on safety shutdown if any safety critical load is identified as operating improperly.

- d. A Dynamic Safety Relay and contract. The control shall check the proper operation of the safety circuit, ability to open and close relay contact. This is intended to act such that the Boiler Management Control is capable of de-energized all safety critical terminals (oil main valve and ignition transformer).
- e. Dynamic Amplifier Check of the flame signal amplifier. The control flame signal amplifier must be able to recognize a no flame signal during the Dynamic Amplifier check.
- f. Safety-Start check and expanded check to include monitoring flame signal during standby.
- g. Dynamic Gas & Oil Pressure Sensor check. This is intended to check that the oil pressure limit sensor can signal zero oil pressure when gas or oil pressure is not present at the oil pressure limit sensing element.
- h. Monitoring the damper motor via a feedback circuit to assure the damper motor is at the required position within 60 seconds, the damper motor is slewing properly, and the damper motor is within 0 to 90 degrees and ensures proper amount of prepurge air.
 - i. Tamper resistant timing and safety logic.
- j. Require reprogramming when being swapped with another boiler room control or being moved to another boiler plant.

2.11.3 Annunciation

The Boiler Room Management Control shall provide the following annunciation and diagnostic:

- a. First out annunciation plus time in sequence of fault occurrence.
- b. Indication of sequence failures at start-up or during normal sequence operation.
- c. Test itself for failure, detect and isolate an alarm, and report internal circuit failure.
- d. The ability of reading limit sensor voltages and resistance at connector interface.
 - e. English text description of the system fault.
 - f. System fault history log.

PART 3 EXECUTION

3.1 ERECTION OF BOILER AND AUXILIARY EQUIPMENT

Boiler and auxiliary equipment shall be installed in accordance with manufacturer's written instructions. Proper provision shall be made for expansion and contraction between boiler foundation and floor. Boilers

and firing equipment shall be supported from the foundations by structural steel completely independent of all brickwork. Boiler supports shall permit free expansion and contraction of each portion of the boiler without placing undue stress on any part of the boiler or setting. Boiler breeching shall be as indicated with full provision for expansion and contraction between all interconnected components.

3.2 PIPING INSTALLATION

Unless otherwise specified, nonboiler external pipe and fittings shall conform to the requirements of ASME B31.1. Pipe installed shall be cut accurately to suit field conditions, shall be installed without springing or forcing, and shall properly clear windows, doors, and other openings. Cutting or other weakening of the building structure to facilitate piping installation will not be permitted. Pipes shall be free of burrs, oil, grease and other foreign material and shall be installed to permit free expansion and contraction without damaging the building structure, pipe, pipe joints, or pipe supports. Changes in direction shall be made with fittings, except that bending of pipe 4 inches and smaller will be permitted provided a pipe bender is used and wide sweep bends are formed. The centerline radius of bends shall not be less than 6 diameters of the pipe. Bent pipe showing kinks, wrinkles, flattening, or other malformations will not be accepted. Vent pipes shall be carried through the roof as directed and shall be properly flashed. Unless otherwise indicated, horizontal supply mains shall pitch down in the direction of flow with a grade of not less than 1 inch in 40 feet. Open ends of pipelines and equipment shall be properly capped or plugged during installation to keep dirt or other foreign materials out of the systems. Pipe not otherwise specified shall be uncoated. Unless otherwise specified or shown, final connections to equipment shall be made with malleable-iron unions for steel pipe 2-1/2 inches or less in diameter and with flanges for pipe 3 inches or more in diameter. Unions for copper pipe or tubing shall be brass or bronze. Reducing fittings shall be used for changes in pipe sizes. In horizontal hot water lines, reducing fittings shall be eccentric type to maintain the top of the lines at the same level to prevent air binding.

3.2.1 Hot Water Piping and Fittings

Pipe shall be black steel or copper tubing. Fittings for steel piping shall be black malleable iron or cast iron to suit piping. Fittings adjacent to valves shall suit valve material. Grooved mechanical fittings will not be allowed for water temperatures above 230 degrees F.

3.2.2 Vent Piping and Fittings

Vent piping shall be black steel. Fittings shall be black malleable iron or cast iron to suit piping.

3.2.3 Gauge Piping

Piping shall be copper tubing.

3.2.4 Joints

Joints between sections of steel pipe and between steel pipe and fittings shall be threaded, grooved, flanged or welded as indicated or specified. Except as otherwise specified, fittings 1 inch and smaller shall be threaded; fittings 1-1/4 inches and up to but not including 3 inches shall be either threaded, grooved, or welded; and fittings 3 inches and larger shall be either flanged, grooved, or welded. Pipe and fittings 1-1/4 inches and larger installed in inaccessible conduit or trenches beneath concrete floor slabs shall be welded. Connections to equipment shall be made with black malleable-iron unions for pipe 2-1/2 inches or smaller in diameter and with flanges for pipe 3 inchesinches or larger in diameter. Joints between sections of copper tubing or pipe shall be flared, soldered, or brazed.

3.2.4.1 Threaded Joints

Threaded joints shall be made with tapered threads properly cut and shall be made perfectly tight with a stiff mixture of graphite and oil or with polytetrafluoroethylene tape applied to the male threads only and in no case to the fittings.

3.2.4.2 Welded Joints

Welded joints shall be in accordance with paragraph GENERAL REQUIREMENTS unless otherwise specified. Changes in direction of piping shall be made with welding fittings only; mitering or notching pipe to form elbows and tees or other similar type construction will not be permitted. Branch connections may be made with either welding tees or forged branch outlet fittings, either being acceptable without size limitation. Branch outlet fittings, where used, shall be forged, flared for improved flow characteristics where attached to the run, reinforced against external strains, and designed to withstand full pipe bursting strength. Socket weld joints shall be assembled so that the space between the end of the pipe and the bottom of the socket is no less than 1/16 inch and no more than 1/8 inch.

3.2.4.3 Flared and Brazed Copper Pipe and Tubing

Tubing shall be cut square, and burrs shall be removed. Both inside of fittings and outside of tubing shall be cleaned thoroughly with sand cloth or steel wire brush before brazing. Annealing of fittings and hard-drawn tubing shall not occur when making connections. Installation shall be made in accordance with the manufacturer's recommendations. Mitering of joints for elbows and notching of straight runs of pipe for tees will not be permitted. Brazed joints shall be made in conformance with AWS B2.2, MSS SP-73, and CDA Tube Handbook with flux. Copper-to-copper joints shall include the use of copper-phosphorous or copper-phosphorous-silver brazing metal without flux. Brazing of dissimilar metals (copper to bronze or brass) shall include the use of flux with either a copper-phosphorous, copper-phosphorous-silver or a silver brazing filler metal. Joints for flared fittings shall be of the compression pattern. Swing joints or offsets shall be provided in all branch connections, mains, and risers to provide for expansion and contraction forces without undue stress to the fittings or to short lengths of pipe or tubing. Flared or brazed copper

tubing to pipe adapters shall be provided where necessary for joining threaded pipe to copper tubing.

3.2.4.4 Soldered Joints

Soldered joints shall be made with flux and are only acceptable for lines 2 inches and smaller. Soldered joints shall conform to ASME B31.5 and CDA Tube Handbook.

3.2.4.5 Copper Tube Extracted Joint

An extruded mechanical tee joint may be made in copper tube. Joint shall be produced with an appropriate tool by drilling a pilot hole and drawing out the tube surface to form a collar having a minimum height of three times the thickness of the tube wall. To prevent the branch tube from being inserted beyond the depth of the extracted joint, dimpled depth stops shall be provided. The branch tube shall be notched for proper penetration into fitting to assure a free flow joint. Extracted joints shall be brazed using a copper phosphorous classification brazing filler metal. Soldered joints will not be permitted.

3.2.5 Flanges and Unions

Flanges shall be faced true, provided with 1/16 inch thick gaskets, and made square and tight. Where steel flanges mate with cast-iron flanged fittings, valves, or equipment, they shall be provided with flat faces and full face gaskets. Union or flange joints shall be provided in each line immediately preceding the connection to each piece of equipment or material requiring maintenance such as coils, pumps, control valves, and other similar items. Dielectric pipe unions shall be provided between ferrous and nonferrous piping to prevent galvanic corrosion. The dielectric unions shall have metal connections on both ends. The ends shall be threaded, flanged, or brazed to match adjacent piping. The metal parts of the union shall be separated so that the electrical current is below 1 percent of the galvanic current which would exist upon metal-to-metal contact. Gaskets, flanges, and unions shall be installed in accordance with manufacturer's recommendations.

3.2.6 Branch Connections

3.2.6.1 Branch Connections for Hot Water Systems

Branches from the main shall pitch up or down as shown to prevent air entrapment. Connections shall ensure unrestricted circulation, eliminate air pockets, and permit complete drainage of the system. Branches shall pitch with a grade of not less than 1 inch in 10 feet. When indicated, special flow fittings shall be installed on the mains to bypass portions of the water through each radiator. Special flow fittings shall be standard catalog products and shall be installed as recommended by the manufacturer.

3.2.7 Flared, Brazed, and Soldered Copper Pipe and Tubing

Copper tubing shall be flared, brazed, or soldered. Tubing shall be cut square, and burrs shall be removed. Both inside of fittings and outside of

tubing shall be cleaned thoroughly with sand cloth or steel wire brush before brazing. Annealing of fittings and hard-drawn tubing shall not occur when making connections. Installation shall be made in accordance with the manufacturer's recommendations. Mitering of joints for elbows and notching of straight runs of pipe for tees will not be permitted. Joints for flared fittings shall be of the compression pattern. Swing joints or offsets shall be provided on branch connections, mains, and risers to provide for expansion and contraction forces without undue stress to the fittings or to short lengths of pipe or tubing. Pipe adapters shall be provided where necessary for joining threaded pipe to copper tubing. Brazed joints shall be made in conformance with MSS SP-73, and CDA Tube Handbook. Copper-to-copper joints shall include the use of copper-phosphorous or copper-phosphorous-silver brazing metal without flux. Brazing of dissimilar metals (copper to bronze or brass) shall include the use of flux with either a copper-phosphorous, copper-phosphorous-silver, or a silver brazing filler metal. Soldered joints shall be made with flux and are only acceptable for lines 2 inches or smaller. Soldered joints shall conform to ASME B31.5 and shall be in accordance with CDA Tube Handbook.

3.2.8 Copper Tube Extracted Joint

An extracted mechanical tee joint may be made in copper tube. Joint shall be produced with an appropriate tool by drilling a pilot hole and drawing out the tube surface to form a collar having a minimum height of three times the thickness of the tube wall. To prevent the branch tube from being inserted beyond the depth of the extracted joint, dimpled depth stops shall be provided. The branch tube shall be notched for proper penetration into fitting to assure a free flow joint. Extracted joints shall be brazed using a copper phosphorous classification brazing filler metal. Soldered joints will not be permitted.

3.2.9 Supports

Hangers used to support piping 2 inches and larger shall be fabricated to permit adequate adjustment after erection while still supporting the load. Pipe guides and anchors shall be installed to keep pipes in accurate alignment, to direct the expansion movement, and to prevent buckling, swaying, and undue strain. Piping subjected to vertical movement when operating temperatures exceed ambient temperatures shall be supported by variable spring hangers and supports or by constant support hangers. Threaded rods which are used for support shall not be formed or bent.

3.2.9.1 Pipe Hangers, Inserts, and Supports

Pipe hangers, inserts, and supports shall conform to MSS SP-58 and MSS SP-69.

3.2.9.2 Multiple Pipe Runs

In the support of multiple pipe runs on a common base member, a clip or clamp shall be used where each pipe crosses the base support member. Spacing of the base support member shall not exceed the hanger and support spacing required for any individual pipe in the multiple pipe run. The clips or clamps shall be rigidly attached to the common base member. A clearance of 1/8 inch shall be provided between the pipe insulation and the

clip or clamp for piping which may be subjected to thermal expansion.

3.2.10 Anchors

Anchors shall be provided where necessary to localize expansion or to prevent undue strain on piping. Anchors shall consist of heavy steel collars with lugs and bolts for clamping and attaching anchor braces, unless otherwise indicated. Anchor braces shall be installed in the most effective manner to secure the desired results, using turnbuckles where required. Supports, anchors, or stays shall not be attached where they will injure the structure or adjacent construction during installation or by the weight of expansion of the pipeline.

3.2.11 Valves

Valves shall be installed where indicated, specified, and required for functioning and servicing of the systems. Valves shall be safely accessible. Swing check valves shall be installed upright in horizontal lines and in vertical lines only when flow is in the upward direction. Gate and globe valves shall be installed with stems horizontal or above. Valves to be brazed shall be disassembled prior to brazing and all packing removed. After brazing, the valves shall be allowed to cool before reassembling.

3.2.12 Air Vents

Air vents shall be installed where shown or directed. Air vents shall be installed in piping at all system high points. The vent shall remain open until water rises in the tank or pipe to a predetermined level at which time it shall close tight. An overflow pipe from the vent shall be run to a point designated by the Contracting Officer's representative. The inlet to the air vent shall have a gate valve or ball valve.

3.2.13 Drains

A drain connection with a 1 inch gate valve or 3/4 inch hose bib shall be installed at the lowest point in the return main near the boiler. In addition, threaded drain connections with threaded cap or plug shall be installed on the heat exchanger coil on each unit heater or unit ventilator and wherever required for thorough draining of the system.

3.3 COLOR CODE MARKING AND FIELD PAINTING

Color code marking of piping shall be as specified in Section 09900 PAINTING GENERAL. Ferrous metal not specified to be coated at the factory shall be cleaned, prepared, and painted as specified in Section 09900 PAINTING, GENERAL. Exposed pipe covering shall be painted as specified in Section 09900 PAINTING, GENERAL. Aluminum sheath over insulation shall not be painted.

3.4 TEST OF BACKFLOW PREVENTION ASSEMBLIES

Backflow prevention assemblies shall be tested in accordance with Section 15400, PLUMBING, GENERAL PURPOSE.

3.5 HEATING SYSTEM TESTS

Before any covering is installed on pipe or heating equipment, the entire new heating system's piping and fittings, shall be hydrostatically tested and proved tight at a pressure of 1-1/2 times the design working pressure. Before pressurizing system for test, items or equipment (e.g., vessels, instruments, controls, relief valves) rated for pressures below the test pressure shall be blanked off or replaced with spool pieces. Before final operating test, test blanks and spool pieces shall be removed; and protected instruments and equipment shall be reconnected. With equipment items protected, the system shall be pressurized to test pressure. Pressure shall be held for a period of time sufficient to inspect all welds, joints, and connections for leaks, but not less than 2 hours. No loss of pressure will be allowed. Leaks shall be repaired and repaired joints shall be retested.

3.6 CLEANING

3.6.1 Boilers and Piping

After the hydrostatic tests have been made and before the system is balanced and operating tests are performed, the boilers and feed water piping shall be thoroughly cleaned by filling the system with a solution consisting of either 1 pound of caustic soda or 1 pound of trisodium phosphate per 50 gallons of water. The proper safety precautions shall be observed in the handling and use of these chemicals. The water shall be heated to approximately 150 degrees F and the solution circulated in the system for a period of 48 hours. The system shall then be drained and thoroughly flushed out with fresh water. Strainers and valves shall be thoroughly cleaned. Prior to operating tests, air shall be removed from all water systems by operating the air vents.

3.7 FIELD TRAINING

The Contractor shall conduct a training course for the operating staff as designated by the Contracting Officer. The training period shall consist of a total of two hours of normal working time and shall start after the system is functionally completed but prior to final acceptance tests. The field instructions shall cover all of the items contained in the approved operation and maintenance instructions, as well as demonstrations of routine maintenance operations and boiler safety devices. The Contracting Officer shall be notified at least 14 days prior to date of proposed conduction of the training course.

-- End of Section --

SECTION 15700

UNITARY HEATING AND COOLING EQUIPMENT

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AIR CONDITIONING AND REFRIGERATION INSTITUTE (ARI)

ARI 210/240	(1994) Unitary Air-Conditioning and Air-Source Heat Pump Equipment
ARI 270	(1995) Sound Rating of Outdoor Unitary Equipment
ARI 310/380	(1993) Packaged Terminal Air-Conditioners and Heat Pumps
ARI 320	(1998) Water-Source Heat Pumps
ARI 325	(1998) Ground Water-Source Heat Pumps
ARI 340/360	(1993) Commercial and Industrial Unitary Air-Conditioning and Heat Pump Equipment
ARI 350	(1986) Sound Rating of Non-Ducted Indoor Air-Conditioning Equipment
ARI 370	(1986) Sound Rating of Large Outdoor Refrigerating and Air-Conditioning Equipment
ARI 410	(1991) Forced-Circulation Air-Cooling and Air-Heating Coils
ARI 460	(2000) Remote Mechanical-Draft Air-Cooled Refrigerant Condensers
ARI 490	(1998) Remote Mechanical-Draft Evaporative Refrigerant Condensers
ARI 495	(1999) Refrigerant Liquid Receivers
ARI 500	(1990) Variable Capacity Positive Displacement Refrigerant Compressors and Compressor Units for Air-Conditioning and Heat Pump Applications
ARI 700	(1999) Specifications for Fluorocarbons

and Other Refrigerants

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM A	123/A 123M	(1997ael) Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A	153/A 153M	(1998) Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A	307	(1997) Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength
ASTM B	117	(1997) Operating Salt Spray (Fog) Apparatus
ASTM C	1071	(1998) Thermal and Acoustical Insulation (Glass Fiber, Duct Lining Material)
ASTM D	520	(1984; R 1995el) Zinc Dust Pigment
ASTM E	84	(1999) Surface Burning Characteristics of Building Materials
ASTM E	437	(1992; R 1997) Industrial Wire Cloth and Screens (Square Opening Series)
ASTM F	104	(1995) Nonmetallic Gasket Materials
ASTM F	872	(1984; R 1990) Filter Units, Air Conditioning: Viscous-Impingement Type, Cleanable
	AMERICAN SOCIETY OF HEATENGINEERS (ASHRAE)	FING, REFRIGERATING AND AIR-CONDITIONING
ASHRAE	15	(1994) Safety Code for Mechanical Refrigeration
ASHRAE	34	(1997) Number Designation and Safety Classification of Refrigerants
ASHRAE	52.1	(1992) Gravimetric and Dust-Spot Procedures for Testing Air-Cleaning Devices Used in General Ventilation for Removing Particulate Matter
ASHRAE	64	(1995) Methods of Testing Remote Mechanical-Draft Evaporative Refrigerant Condensers
ASHRAE	127	(1988) Method of Testing for Rating

Air-Conditioners

Computer and Data Processing Room Unitary

AMERICAN WELDING SOCIETY (AWS)

AWS Z49.1 (1999) Safety in Welding and Cutting

ASME INTERNATIONAL (ASME)

ASME BPV VIII Div 1 (1998) Boiler and Pressure Vessel Code;

Section VIII, Pressure Vessels Division 1

- Basic Coverage

ASME BPV IX (1998) Boiler and Pressure Vessel Code;

Section IX, Welding and Brazing

Qualifications

ASSOCIATION OF HOME APPLIANCE MANUFACTURERS (AHAM)

AHAM Directory (1997) Directory of Certified Room Air

Conditioners

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA ICS 6 (1993) Industrial Control and Systems,

Enclosures

NEMA MG 1 (1998) Motors and Generators

NEMA MG 2 (1989) Safety Standard for Construction

and Guide for Selection, Installation, and

Use of Electric Motors and Generators

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 54 (1999) National Fuel Gas Code

NFPA 70 (1999) National Electrical Code

NFPA 90A (1999) Installation of Air Conditioning

and Ventilating Systems

UNDERWRITERS LABORATORIES (UL)

UL 207 (1993; Rev thru Oct 1997)

Refrigerant-Containing Components and

Accessories, Nonelectrical

UL 484 (1993; Rev thru Feb 1999) Room Air

Conditioners

UL 586 (1996; Rev thru Aug 99) High-Efficiency,

Particulate, Air Filter Units

UL 900 (1994; Rev thru Nov 1999) Test Performance

of Air Filter Units

UL 1995

(1995; Rev thru Aug 1999) Heating and Cooling Equipment

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Drawings; G WA.

Drawings provided in adequate detail to demonstrate compliance with contract requirements. Drawings shall consist of:

- a. Equipment layouts which identify assembly and installation details.
- b. Plans and elevations which identify clearances required for maintenance and operation.
- c. Wiring diagrams which identify each component individually and interconnected or interlocked relationships between components.

SD-03 Product Data

Unitary Equipment; G WA

Manufacturer's standard catalog data, at least 5 weeks prior to the purchase or installation of a particular component, highlighted to show material, size, options, performance charts and curves, etc. in adequate detail to demonstrate compliance with contract requirements. Data shall include manufacturer's recommended installation instructions and procedures. If vibration isolation is specified for a unit, vibration isolator literature shall be included containing catalog cuts and certification that the isolation characteristics of the isolators provided meet the manufacturer's recommendations. Data shall be submitted for each specified component.

Spare Parts Data; G WA

Spare parts data for each different item of equipment specified, after approval of detail drawings and not later than two months prior to the date of beneficial occupancy. The data shall include a complete list of parts and supplies, with current unit prices and source of supply, a recommended spare parts list for 1 year of operation, and a list of the parts recommended by the manufacturer to be replaced on a routine basis.

Verification of Dimensions

A letter, at least 2 weeks prior to beginning construction, including the date the site was visited, conformation of existing conditions, and any discrepancies found.

Demonstrations

A schedule, at least 2 weeks prior to the date of the proposed training course, which identifies the date, time, and location for the training.

SD-06 Test Reports

Refrigerant Tests, Charging, and Start-Up; G WA

Six copies of each test containing the information described below in bound $8-1/2 \times 11$ inch booklets. Individual reports shall be submitted for the refrigerant system tests.

- a. The date the tests were performed.
- b. A list of equipment used, with calibration certifications.
- c. Initial test summaries.
- d. Repairs/adjustments performed.
- e. Final test results.

System Performance Tests; G WA

Six copies of the report shall be provided provided. The report shall document compliance with the specified performance criteria upon completion and testing of the system. The report shall indicate the number of days covered by the tests and any conclusions as to the adequacy of the system. The report shall also include the following information and shall be taken at least three different times at outside dry-bulb temperatures that are at least 5 degrees F apart:

- a. Date and outside weather conditions.
- b. The load on the system based on the following:
 - (1) The refrigerant used in the system.
 - (2) Condensing temperature and pressure.
 - (3) Suction temperature and pressure.
 - (4) Ambient, condensing and coolant temperatures.
- (5) Running current, voltage and proper phase sequence for each phase of all motors.
- c. The actual on-site setting of operating and safety controls.
- d. Thermostatic expansion valve superheat value as determined

by field test.

- e. Subcooling.
- f. High and low refrigerant temperature switch set-points
- g. Low oil pressure switch set-point.
- h. Defrost system timer and thermostat set-points.
- i. Moisture content.
- j. Capacity control set-points.
- k. Field data and adjustments which affect unit performance and energy consumption.
- 1. Field adjustments and settings which were not permanently marked as an integral part of a device.

SD-07 Certificates

Unitary Equipment

Where the system, components, or equipment are specified to comply with requirements of ARI, ASHRAE, ASME, or UL, proof of such compliance shall be provided. The label or listing of the specified agency shall be acceptable evidence. In lieu of the label or listing, a written certificate from an approved, nationally recognized testing organization equipped to perform such services, stating that the items have been tested and conform to the requirements and testing methods of the specified agency may be submitted.

SD-10 Operation and Maintenance Data

Operation & Maintenance Manuals; G WA

Six complete copies of an operation & maintenance manual listing step-by-step procedures required for system startup, operation, abnormal shutdown, emergency shutdown, normal shutdown, routine maintenance procedures and trouble shooting guides shall be provided at least 4 weeks prior to the first training course. The booklets shall include the manufacturer's name, model number, and parts list. The manuals shall include the manufacturer's name, model number, service manual, and a brief description of all equipment and their basic operating features.

1.3 SAFETY REQUIREMENTS

Exposed moving parts, parts that produce high operating temperature, parts which may be electrically energized, and parts that may be a hazard to operating personnel shall be insulated, fully enclosed, guarded, or fitted with other types of safety devices. Safety devices shall be installed so

that proper operation of equipment is not impaired. Welding and cutting safety requirements shall be in accordance with AWS Z49.1.

1.4 DELIVERY, STORAGE, AND HANDLING

Stored items shall be protected from the weather, humidity and temperature variations, dirt and dust, or other contaminants. Proper protection and care of all material both before and during installation shall be the Contractor's responsibility. Any materials found to be damaged shall be replaced at the Contractor's expense. During installation, piping and similar openings shall be capped to keep out dirt and other foreign matter.

1.5 PROJECT/SITE CONDITIONS

1.5.1 Verification of Dimensions

The Contractor shall become familiar with all details of the work, verify all dimensions in the field, and advise the Contracting Officer of any discrepancy before performing any work.

1.5.2 Drawings

Because of the small scale of the drawings, it is not possible to indicate all offsets, fittings, and accessories that may be required. The Contractor shall carefully investigate the plumbing, electrical, structural and finish conditions that would affect the work to be performed and arrange such work accordingly, furnishing required offsets, fittings, and accessories to meet such conditions.

PART 2 PRODUCTS

2.1 STANDARD COMMERCIAL PRODUCTS

Materials and equipment shall be standard products of a manufacturer regularly engaged in the manufacturing of such products, which are of a similar material, design and workmanship. The standard products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2 year use shall include applications of equipment and materials under similar circumstances and of similar size. The 2 years experience shall be satisfactorily completed by a product which has been sold or is offered for sale on the commercial market through advertisements, manufacturer's catalogs, or brochures. Products having less than a 2 year field service record shall be acceptable if a certified record of satisfactory field operation, for not less than 6000 hours exclusive of the manufacturer's factory tests, can be shown. Products shall be supported by a service organization. System components shall be environmentally suitable for the indicated locations.

2.2 NAMEPLATES

Major equipment including compressors, condensers, receivers, heat exchanges, fans, and motors shall have the manufacturer's name, address, type or style, model or serial number, and catalog number on a plate secured to the item of equipment. Plates shall be durable and legible

throughout equipment life and shall be fixed in prominent locations with nonferrous screws or bolts.

2.3 ELECTRICAL WORK

Electrical equipment, motors, motor efficiencies, and wiring shall be in accordance with Section 16415 ELECTRICAL WORK, INTERIOR. Electrical motor driven equipment specified shall be provided complete with motors, controls. Electrical characteristics shall be as shown, and unless otherwise indicated, all motors of 1 horsepower and above with open, dripproof, totally enclosed, or explosion proof fan cooled enclosures, shall be high efficiency type. Field wiring shall be in accordance with manufacturer's instructions. Each motor shall conform to NEMA MG 1 and NEMA MG 2 and be of sufficient size to drive the equipment at the specified capacity without exceeding the nameplate rating of the motor. Motors shall be continuous duty with the enclosure specified. Motor starters shall be provided complete with thermal overload protection and other appurtenances necessary for the motor control indicated. Motors shall be furnished with a magnetic across-the-line or reduced voltage type starter as required by the manufacturer. Motor duty requirements shall allow for maximum frequency start-stop operation and minimum encountered interval between start and stop. Motors shall be sized for the applicable loads. Motor torque shall be capable of accelerating the connected load within 20 seconds with 80 percent of the rated voltage maintained at motor terminals during one starting period. Motor bearings shall be fitted with grease supply fittings and grease relief to outside of enclosure. Manual or automatic control and protective or signal devices required for the operation specified and any control wiring required for controls and devices specified, but not shown, shall be provided.

2.4 UNITARY EQUIPMENT, SPLIT SYSTEM

Unit shall be an air-cooled, split system which employs a remote condensing unit, and interconnecting refrigerant piping. Unit shall be the air-conditioning type conforming to applicable Underwriters Laboratories (UL) standards including UL 1995 and shall have UL label. Unit shall be rated in accordance with ARI 340/360. Unit shall be provided with necessary fans, air filters, liquid receiver, internal dampers, mixing boxes, and cabinet construction as specified in paragraph "System Components". The remote unit shall be as specified in paragraph REMOTE CONDENSER OR "CONDENSING UNIT". Condenser or outdoor fans shall be the manufacturer's standard for the unit specified and may be either propeller or centrifugal scroll type. Fan and condenser motors shall have totally enclosed enclosures.

The remote condensing unit shall be self contained, packaged, factory-assembled, and pre-wired unit suitable for outdoor use consisting of cabinet, compressors, condensing coil and fans, subcooling circuits, and controls.

2.4.1 Air-to-Refrigerant Coil

Coils shall have copper tubes of 3/8 inch minimum diameter with copper or aluminum fins that are mechanically bonded or soldered to the tubes. Coils

shall be protected with a minimum 3 mil thick phenolic orvinyl coating. Casing shall be galvanized steel or aluminum. Contact of dissimilar metals shall be avoided. Coils shall be tested in accordance with ASHRAE 15 at the factory and be suitable for the working pressure of the installed system. Each coil shall be dehydrated and sealed after testing and prior to evaluation and charging. Each unit shall be provided with a factory operating charge of refrigerant and oil or a holding charge. Unit shipped with a holding charge shall be field charged. Separate expansion devices shall be provided for each compressor circuit.

2.4.2 Compressor

Compressor shall be direct drive, hermetic reciprocating, or scroll type capable of operating at partial load conditions. Compressor shall be capable of continuous operation down to the lowest step of unloading as specified. Compressors of 10 tons and larger shall be provided with capacity reduction devices to produce automatic capacity reduction of at least 50 percent. If standard with the manufacturer, two or more compressors may be used in lieu of a single compressor with unloading capabilities, in which case the compressors will operate in sequence, and each compressor shall have an independent refrigeration circuit through the condenser and evaporator. Each compressor shall start in the unloaded position. Each compressor shall be provided with vibration isolators, crankcase heater, thermal overloads, lubrication pump, high and low pressure safety cutoffs and protection against short cycling.

2.4.3 Refrigeration Circuit

Refrigerant-containing components shall comply with ASHRAE 15 and be factory tested, cleaned, dehydrated, charged, and sealed. Refrigerant charging valves and connections, and pumpdown valves shall be provided for each circuit. Filter-drier shall be provided in each liquid line and be reversible-flow type.

2.4.4 Unit Controls

Unit shall be internally prewired with a 120 volt control circuit powered by an internal transformer. Terminal blocks shall be provided for power wiring and external control wiring. Unit shall have cutoffs for high and low pressure, and low oil pressure for compressors with positive displacement oil pumps, supply fan failure, and safety interlocks on all service panels. Adjustable-cycle timers shall prevent short-cycling. Multiple compressors shall be staged by means of a time delay. Unit shall be internally protected by fuses or a circuit breaker in accordance with UL 1995.

2.5 REMOTE CONDENSER OR CONDENSING UNIT

Each remote condenser coil shall be fitted with a manual isolation valve and an access valve on the coil side. Saturated refrigerant condensing temperature shall not exceed 120 degrees F at 95 degrees F ambient. Fan and cabinet construction shall be provided as specified in paragraph "System Components". Fan and condenser motors shall have totally enclosed enclosures.

2.5.1 Air-Cooled Condenser

Unit shall be rated in accordance with ARI 460 and conform to the requirements of UL 1995. Unit shall be factory fabricated, tested, packaged, and self-contained. Unit shall be complete with casing, propeller or centrifugal type fans, heat rejection coils, connecting piping and wiring, and all necessary appurtenances.

2.5.1.1 Connections

Interconnecting refrigeration piping, electrical power, and control wiring between the condensing unit and the indoor unit shall be provided as required and as indicated. Electrical and refrigeration piping terminal connections between condensing unit and evaporator units shall be provided.

2.5.1.2 Head Pressure Control and Liquid Subcooling

Low ambient control for multi-circuited units serving more than one evaporator coil shall provide independent condenser pressure controls for each refrigerant circuit. Controls shall be set to produce a minimum of 95 degrees F saturated refrigerant condensing temperature. Unit shall be provided with a liquid subcooling circuit which shall ensure proper liquid refrigerant flow to the expansion device over the specified application range of the condenser. Unit shall be provide with manufacturer's standard liquid subcooling. Subcooling circuit shall be liquid sealed.

2.5.1.3 Condensing Coil

Coils shall have copper tubes of 3/8 inch minimum diameter with copper or aluminum fins that are mechanically bonded or soldered to the tubes. Coils shall be protected with a minimum 3 mil thick phenolic or vinyl coating. Casing shall be galvanized steel or aluminum. Contact of dissimilar metals shall be avoided. Coils shall be tested in accordance with ASHRAE 15 at the factory and be suitable for the working pressure of the installed system. Each coil shall be dehydrated and sealed after testing and prior to evaluation and charging. Each unit shall be provided with a factory operating charge of refrigerant and oil or a holding charge. Unit shipped with a holding charge shall be field charged. Separate expansion devices shall be provided for each compressor circuit.

2.5.1.4 Unit Controls

The control system shall be complete with required accessories for regulating condenser pressure by fan cycling, solid-state variable fan speed, modulating condenser coil or fan dampers, flooding the condenser, or a combination of the above. Unit mounted control panels or enclosures shall be constructed in accordance with applicable requirements of NFPA 70 and housed in NEMA ICS 6, Class 1 or 3A enclosures. Controls shall include control transformer, fan motor solid-state speed control, time delay start-up, overload protective devices, interface with local and remote components, and intercomponent wiring to terminal block points.

2.6 AIR-CONDITIONERS FOR ELECTRONIC DATA PROCESSING (EDP) SPACES

Unit shall be a split-system with a remote condenser and shall be designed and constructed for automatic control of space conditions. Unit shall be in accordance with ASHRAE 127 and UL 1995. Unit shall be rated in accordance with ARI 210/240. The system shall be designed and constructed for maximum reliability and ease of maintenance. Unit shall be provided with necessary fans, air filters, coil frost protection, internal dampers, mixing boxes, supplemental heat, and cabinet construction. Evaporator or supply fans shall be double-width, double inlet, forward curved centrifugal scroll type. Condenser or outdoor fans shall be manufacturer's standard for unit specified. Fan and condenser motors shall have totally enclosed enclosures. The unit shall automatically monitor and adjust temperature and humidity in a communication room and shall consist of a cooling unit (placed indoors) and a condenser unit placed outdoors. The indoor unit noise level shall be below 50 dB when measured at 3 feet from the unit. An easily removable dust-trapping air filter shall be provided to create a clean room environment. The unit shall have built in antifrost, self-check, electronic protection and other safety devices required for operating at low ambient conditions.

2.6.1 Air-to-Refrigerant Coils

Coils shall be tested in accordance with ASHRAE 15 at the factory and be suitable for the working pressure of the installed system. Each coil shall be dehydrated and sealed after testing and prior to evaluation and charging. Each unit shall be provided with a factory operating charge of refrigerant and oil or a holding charge. Units shipped with a holding charge shall be field charged.

2.6.2 Compressor

Compressor shall be direct drive, semi-hermetic or hermetic reciprocating, or scroll type capable of operating at partial load conditions. Compressor shall be capable of continuous operation down to the lowest step of unloading as specified.

2.6.3 Unit Controls

The split-system air conditioning unit shall be provided with simple-to-use control panel incorporating an "on-off" switch, two speed fan, 24-hour programmable timer, and indicator lights that monitor compressor functions. Unit shall have 115 volt control circuit with fusing and control power transformer.

2.6.3.1 Space Temperature

Space temperature shall be controlled within plus or minus 1-1/2 degrees F of the set point over a range of 60 to 90 degrees F. Space relative humidity shall be controlled within plus or minus 5 percent of the set point over a range of 20 to 80 percent.

2.6.3.2 Safety Controls

Safety controls shall include the following:

- a. Fused, unfused or line-break circuit breaker disconnects, as indicated or required.
- b. Automatic pump-out or pump-down liquid flooding controls.
- c. High refrigerant pressure cutout.
- d. Low refrigerant pressure cutout where automatic pump-down is not provided.
- e. Accessible hermetic and open compressor low oil pressure cutout.

2.6.4 Cabinet Construction

Cabinet shall be totally enclosed. Enclosure surfaces shall be pulsation free, with hinged and removable doors and panels for vertical side or front access to unit components. Routine maintenance access to compressor and system control components shall be possible without unit shut-down.

2.7 UNITARY EQUIPMENT COMPONENTS

2.7.1 Refrigerant and Oil

Refrigerant shall be one of the fluorocarbon gases. Refrigerants shall have number designations and safety classifications in accordance with ASHRAE 34. Refrigerants shall meet the requirements of ARI 700 as a minimum. Refrigerants shall have an Ozone Depletion Potential (ODP) of less than or equal to 0.05 (R-22, R-123 and R-134a all meet this requirement). Contractor shall provide and install a complete charge of refrigerant for the installed system as recommended by the manufacturer. Except for factory sealed units, two complete charges of lubricating oil for each compressor crankcase shall be furnished. One charge shall be used during the system performance testing period. Following the satisfactory completion of the performance testing, the oil shall be drained and replaced with a second charge. Lubricating oil shall be of a type and grade recommended by the manufacturer for each compressor. Where color leak indicator dye is incorporated, charge shall be in accordance with manufacturer's recommendation.

2.7.2 Fans

Fan wheel shafts shall be supported by either maintenance-accessible lubricated antifriction block-type bearings, or permanently lubricated ball bearings. Unit fans shall be selected to produce the cfm required at the fan total pressure. Motor starters, if applicable, shall be magnetic across-the-line type with a totally enclosed enclosure. Thermal overload protection shall be of the manual or automatic-reset type. Fan wheels or propellers shall be constructed of aluminum or galvanized steel. Centrifugal fan wheel housings shall be of galvanized steel, and both centrifugal and propeller fan casings shall be constructed of aluminum or galvanized steel. Steel elements of fans, except fan shafts, shall be hot-dipped galvanized after fabrication or fabricated of mill galvanized steel. Mill-galvanized steel surfaces and edges damaged or cut during

fabrication by forming, punching, drilling, welding, or cutting shall be recoated with an approved zinc-rich compound. Fan wheels or propellers shall be statically and dynamically balanced. Direct-drive fan motors shall be of the multiple-speed variety. Belt-driven fans shall have adjustable sheaves to provide not less than 20 percent fan-speed adjustment. The sheave size shall be selected so that the fan speed at the approximate midpoint of the sheave adjustment will produce the specified air quantity. Centrifugal scroll-type fans shall be provided with streamlined orifice inlet and V-belt drive. Each drive will be independent of any other drive. Propeller fans shall be direct-drive or V-belt drive type. V-belt driven fans shall be mounted on a corrosion protected drive shaft supported by either maintenance-accessible lubricated antifriction block-type bearings, or permanently lubricated ball bearings. Each drive will be independent of any other drive. Drive bearings shall be protected with water slingers or shields. V-belt drives shall be fitted with guards where exposed to contact by personnel.

2.7.3 Coil Frost Protection

Each circuit shall be provided with a coil frost protection system which is a manufacturer's standard. The coil frost protection system shall use a temperature sensor in the suction line of the compressor to shut the compressor off when coil frosting occurs. Timers shall be used to prevent the compressor from rapid cycling.

2.7.4 Pressure Vessels

Pressure vessels shall conform to ASME BPV VIII Div 1 or UL 207, as applicable for maximum and minimum pressure or temperature encountered. Where referenced publications do not apply, pressure components shall be tested at 1-1/2 times design working pressure. Refrigerant wetted carbon steel surfaces shall be pickled or abrasive blasted free of mill scale, cleaned, dried, charged, and sealed.

2.7.4.1 Hot Gas Muffler

Unit shall be selected by the manufacturer for maximum noise attenuation.

2.7.4.2 Liquid Receiver

A liquid receiver shall be provided when a system's condenser or compressor does not contain a refrigerant storage capacity of at least 20 percent in excess of a fully charged system. Receiver shall be designed, filled, and rated in accordance with the recommendations of ARI 495, except as modified herein. Receiver shall be fitted to include an inlet connection; an outlet drop pipe with oil seal and oil drain where necessary; two bull's-eye liquid level sight glass in same vertical plane, 90 degrees apart and perpendicular to axis of receiver or external gauge glass with metal guard and automatic stop valves. Receiver shall be provided with a relief valve of capacity and setting in accordance with ASHRAE 15.

2.7.4.3 Oil Separator

Separator shall be the high efficiency type and be provided with removable

flanged head for ease in removing float assembly and removable screen cartridge assembly. Pressure drop through a separator shall not exceed 10 psi during the removal of hot gas entrained oil. Connections to compressor shall be as recommended by the compressor manufacturer. Separator shall be provided with an oil float valve assembly or needle valve and orifice assembly, drain line shutoff valve, sight glass, and strainer.

2.7.4.4 Oil Reservoir

Reservoir capacity shall equal one charge of all connected compressors. Reservoir shall be provided with an external liquid gauge glass, plugged drain, and isolation valves. Vent piping between the reservoir and the suction header shall be provided with a 5 psi pressure differential relief valve. Reservoir shall be provided with the manufacturer's standard filter on the oil return line to the oil level regulators.

2.7.5 Cabinet Construction

Casings for the specified unitary equipment shall be constructed of galvanized steel or aluminum sheet metal and galvanized or aluminum structural members. Minimum thickness of single wall exterior surfaces shall be 18 gauge galvanized steel or 0.071 inch thick aluminum on units with a capacity above 20 tons and 20 gauge galvanized steel or 0.064 inch thick aluminum on units with a capacity less than 20 tons. Casing shall be fitted with lifting provisions, access panels or doors, fan vibration isolators, electrical control panel, corrosion-resistant components, structural support members, insulated condensate drip pan and drain, and internal insulation in the cold section of the casing. Where double-wall insulated construction is proposed, minimum exterior galvanized sheet metal thickness shall be 20 gauge. Provisions to permit replacement of major unit components shall be incorporated. Penetrations of cabinet surfaces, including the floor, shall be sealed. Unit shall be fitted with a drain pan which extends under all areas where water may accumulate. Drain pan shall be fabricated from Type 300 stainless steel, galvanized steel with protective coating as required, or an approved plastic material. Pan insulation shall be water impervious. Extent and effectiveness of the insulation of unit air containment surfaces shall prevent, within limits of the specified insulation, heat transfer between the unit exterior and ambient air, heat transfer between the two conditioned air streams, and condensation on surfaces. Insulation shall conform to ASTM C 1071. Paint and finishes shall comply with the requirements specified in paragraph FACTORY COATING.

2.7.5.1 Indoor Cabinet

Indoor cabinets shall be suitable for the specified indoor service and enclose all unit components.

2.7.5.2 Outdoor Cabinet

Outdoor cabinets shall be suitable for outdoor service with a weathertight, insulated and corrosion-protected structure. Cabinets constructed exclusively for indoor service which have been modified for outdoor service are not acceptable.

2.8 ACCESSORIES

2.8.1 Purge System

Refrigeration systems which operate at pressures below atmospheric pressure shall be provided with a purge system. Purge systems shall automatically remove air, water vapor, and non-condensible gases from the system's refrigerant. Purge systems shall condense, separate, and return all refrigerant back to the system. An oil separator shall be provided with the purge system if required by the manufacturer. Purge system shall not discharge to occupied areas, or create a potential hazard to personnel. Purge system shall include a purge pressure gauge, number of starts counter, and an elapsed time meter. Purge system shall include lights or an alarm which indicate excessive purge or an abnormal air leakage into the system.

2.8.2 Refrigerant Leak Detector

Detector shall be the continuously-operating, halogen-specific type. Detector shall be appropriate for the refrigerant in use. Detector shall be specifically designed for area monitoring and shall include a single sampling point installed where indicated. Detector design and construction shall be compatible with the temperature, humidity, barometric pressure and voltage fluctuations of the operating area. Detector shall have an adjustable sensitivity such that it can detect refrigerant at or above 3 parts per million (ppm). Detector shall be supplied factory-calibrated for the appropriate refrigerant(s). Detector shall be provided with an alarm relay output which energizes when the detector detects a refrigerant level at or above the TLV-TWA (or toxicity measurement consistent therewith) for the refrigerant in use. The detector's relay shall be capable of initiating corresponding alarms and ventilation system as indicated on the drawings. Detector shall be provided with a failure relay output that energizes when the monitor detects a fault in its operation.

2.8.3 Refrigerant Relief Valve/Rupture Disc Assembly

The assembly shall be a combination pressure relief valve and rupture disc designed for refrigerant usage. The assembly shall be in accordance with ASME BPV VIII Div 1 and ASHRAE 15. The assembly shall be provided with a pressure gauge assembly which will provide local indication if a rupture disc is broken. Rupture disc shall be the non-fragmenting type.

2.8.4 Refrigerant Signs

Refrigerant signs shall be a medium-weight aluminum type with a baked enamel finish. Signs shall be suitable for indoor or outdoor service. Signs shall have a white background with red letters not less than 0.5 inches in height.

2.8.4.1 Installation Identification

Each new refrigeration system shall be provided with a refrigerant sign

which indicates the following as a minimum:

- a. Contractor's name
- b. Refrigerant number and amount of refrigerant.
- c. The lubricant identity and amount.
- d. Field test pressure applied.

2.8.4.2 Controls and Piping Identification

Refrigerant systems containing more than 110 lb of refrigerant shall be provided with refrigerant signs which designate the following as a minimum:

- a. Valves or switches for controlling the refrigerant flow and the refrigerant compressor.
- b. Pressure limiting device(s).

2.9 FABRICATION

2.9.1 Factory Coating

Unless otherwise specified, equipment and component items, when fabricated from ferrous metal, shall be factory finished with the manufacturer's standard finish.

2.9.2 Factory Applied Insulation

Refrigeration equipment shall be provided with factory installed insulation on surfaces subject to sweating including the suction line piping. Where motors are the gas-cooled type, factory installed insulation shall be provided on the cold-gas inlet connection to the motor per manufacturer's standard practice. Factory insulated items installed outdoors are not required to be fire-rated.

PART 3 EXECUTION

3.1 INSTALLATION

Work shall be performed in accordance with the manufacturer's published diagrams, recommendations, and equipment warranty requirements. Where equipment is specified to conform to the requirements of ASME BPV VIII Div 1 and ASME BPV IX, the design, fabrication, and installation of the system shall conform to ASME BPV VIII Div 1 and ASME BPV IX.

3.1.1 Equipment

Refrigeration equipment and the installation thereof shall conform to ASHRAE 15. Necessary supports shall be provided for all equipment, appurtenances, and pipe as required, including frames or supports for compressors, pumps, cooling towers, condensers, and similar items. Compressors shall be isolated from the building structure. If mechanical

vibration isolators are not provided, vibration absorbing foundations shall be provided. Each foundation shall include isolation units consisting of machine and floor or foundation fastenings, together with intermediate isolation material. Other floor-mounted equipment shall be set on not less than a 6 inch concrete pad doweled in place.

3.1.2 Field Applied Insulation

Field applied insulation shall be as specified in Section 15080 THERMAL INSULATION FOR MECHANICAL SYSTEMS, except as defined differently herein..

3.1.3 Field Painting

Painting required for surfaces not otherwise specified, and finish painting of items only primed at the factory are specified in Section 09900 PAINTING, GENERAL.

3.2 REFRIGERANT TESTS, CHARGING, AND START-UP

Split-system refrigerant piping systems shall be tested and charged as specified in Section 15182 REFRIGERANT PIPING. Packaged refrigerant systems which are factory charged shall be checked for refrigerant and oil capacity to verify proper refrigerant levels per manufacturer's recommendations. Following charging, packaged systems shall be tested for leaks with a halide torch or an electronic leak detector.

3.2.1 Refrigerant Leakage

If a refrigerant leak is discovered after the system has been charged, the leaking portion of the system shall immediately be isolated from the remainder of the system and the refrigerant pumped into the system receiver or other suitable container. Under no circumstances shall the refrigerant be discharged into the atmosphere.

3.2.2 Contractor's Responsibility

The Contractor shall, at all times during the installation and testing of the refrigeration system, take steps to prevent the release of refrigerants into the atmosphere. The steps shall include, but not be limited to, procedures which will minimize the release of refrigerants to the atmosphere and the use of refrigerant recovery devices to remove refrigerant from the system and store the refrigerant for reuse or reclaim. At no time shall more than 3 ounces of refrigerant be released to the atmosphere in any one occurrence. Any system leaks within the first year shall be repaired in accordance with the requirements herein at no cost to the Government including material, labor, and refrigerant if the leak is the result of defective equipment, material, or installation.

3.3 SYSTEM PERFORMANCE TESTS

Before each refrigeration system is accepted, tests to demonstrate the general operating characteristics of all equipment shall be conducted by a registered professional engineer or an approved manufacturer's start-up representative experienced in system start-up and testing, at such times as

directed. Tests shall cover a period of not less than 8 hours for each system and shall demonstrate that the entire system is functioning in accordance with the drawings and specifications. Corrections and adjustments shall be made as necessary and tests shall be re-conducted to demonstrate that the entire system is functioning as specified. Prior to acceptance, service valve seal caps and blanks over gauge points shall be installed and tightened. Any refrigerant lost during the system startup shall be replaced. If tests do not demonstrate satisfactory system performance, deficiencies shall be corrected and the system shall be retested. Tests shall be conducted in the presence of the Contracting Officer. Water and electricity required for the tests will be furnished by the Government. Any material, equipment, instruments, and personnel required for the test shall be provided by the Contractor. Field tests shall be coordinated with Section 15990 TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS.

3.4 DEMONSTRATIONS

Contractor shall conduct a training course for the operating staff as designated by the Contracting Officer. The training period shall consist of a total 2 hours of normal working time and start after the system is functionally completed but prior to final acceptance tests. The field posted instructions shall cover all of the items contained in the approved operation and maintenance manuals as well as demonstrations of routine maintenance operations.

-- End of Section --

SECTION 15896

CLEANING OF THE AIR DISTRIBUTION SYSTEM

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERINS (ASHRAE)

ASHRAE 62

(1989) Ventilation for Acceptable Indoor Air Quality

ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA

(1991) Building Air Quality

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL STD 282

(1956) Military Standard

NATIONAL AIR DUCT CLEANERS ASSOCIATION (NADCA)

NADCA 01

(1992) Mechanical Cleaning of Non-Porous Air Conveyance System Components

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 CONTRACT SUBMITTAL PROCEDURES.

SD-02 Shop Drawings

Work Plan; G WA

The procedures proposed for accomplishing the work shall be submitted for approval. The procedures shall provide for the safe conduct of work, careful removal and cleaning of materials specified and protection of existing property. The procedures shall include a detailed description of the methods and equipment to be used for each operation, and the sequence of operations. The work plan shall be broken down into a daily plan showing between what hours the contractor plans to work for the duration of the cleaning process. It shall also show the specific tasks to be performed each day and which rooms will be affected.

Access Panels/Doors; G WA

The exact locations for all ceiling and duct access panels and doors must be approved and shall be clearly shown on the as-built drawing. The materials and methods used for making and attaching the access panels to the ceiling as well as the cut sheets for the access doors on the ducts shall be submitted.

SD-03 Product Data

Materials; G WA

The Contractor shall submit a Material Safety Date Sheet on all chemicals and compounds used in the cleaning and sanitizing of the Air Conveyance system.

1.3 DEFINITIONS

1.3.1 Air Conveyance System (ACS)

The air conveyance system is any interior surface of a building's air distribution system for conditioned spaces and/or occupied zones (See ASHRAE 62). This includes the entire air moving system from the points that the air enters the system to the points where the air is discharged from the system. The return air grilles, air ducts (except ceiling plenums) to the air-handling unit (AHU), the interior surface of the AHU, supply air ducts, turning vanes and supply diffusers are all considered part of the ACS.

1.3.2 Dirt and Debris

Any solid materials, including particulate substances, in the ACS not intended to be present. ACS cleaning is intended to remove dirt, dust, mold, and other such contaminants from the system.

1.3.3 DOP Testing

The percentage removal of 0.3 micrometer particles of dioctylphthalate (DOP) is used to rate high efficiency air filters, those with efficiencies above 98 percent. (See MS-STD-282)

1.3.4 Non-Porous ACS Surface

Any surface of the ACS in contract with the air stream, which cannot be penetrated by either solutions or air. This would exclude materials such as wood, fiberboard, thermal insulation, and concrete.

1.3.5 Particulate Collection Equipment

A device used for collecting and containing particulate material.

1.3.6 Visibly Clean

Determined by internal Visual Inspection, that all portions or components

of the ACS are both free of any Debris.

1.3.7 Visual Inspection

Examination of the cleaned components of the ACS to evaluate the effectiveness of the cleaning process using the human eye or another optical instrument.

1.4 COORDINATION

Cleaning of the Air Conveyance System as specified in this section shall be performed during non-business hours. The Contractor shall provide two weeks advance notice before starting the cleaning process. The duct cleaning subcontractor shall coordinate and provide all required appropriate ceiling access panel with the Prime Contractor and the Government. He shall be responsible for providing all access to the ducts and moving furniture as required to perform his work. After each work period, offices shall be cleaned and returned to their original condition.

PART 2 PRODUCTS

2.1 EQUIPMENT

The Contractor shall furnish all labor, materials and equipment required to clean the air conveyance system (ACS) shown on the contract drawings. All work shall be performed in accordance with National Air Duct Cleaners Association (NADCA) standards.

2.1.1 Containment

Debris removed during cleaning shall be collected. Precautions shall be taken to ensure that dust, dirt and other contaminants are not otherwise dispersed outside the ACS during the cleaning process. After ACS cleaning, any areas that could be affected by the cleaning contractor's work must be as clean or cleaner than their condition prior to the commencement of the cleaning operation.

2.1.2 Particulate Collection

All Particulate Collection Equipment will be equipped with a high efficiency particulate arrestance (HEPA) filter. Prior to cleaning any ductwork, it shall first be placed under negative pressure utilizing a fan powered, high efficiency dust and particulate collection system in areas where contaminants are being removed. The collection system shall be portable self-contained unit, with appropriate compartments to adequately prevent dirt and debris loosened during cleaning operations from entering the conditioned spaces by capturing this debris within the collection device.

2.1.3 Filtration Integrity

The filtration within the collection system shall be, as a minimum, three stage filtration labeled and certified to be no less than 99.97% efficient on particles .3 microns and greater at the rate flow of air (EPA-Building

Air Quality). All debris and contaminants collected during the cleaning process shall be discarded into the Contractor's collection containers outside of the building. The Contractor is responsible for properly disposing of all collected dust, dirt and other debris in accordance with local, State and Federal regulations.

2.1.4 Controlling Odors

All reasonable measures shall be taken to control offensive odors and/or mist vapors during the cleaning process.

2.1.5 Component Cleaning

Cleaning methods shall be employed such that all Non-Porous ACS Surface components must be Visibly Clean. Upon completion, all components must be returned to those settings recorded just prior to cleaning operations.

2.1.6 Air-Volume Control Devices

Dampers and any air-directed mechanical devices inside the ACS must have their position marked prior to cleaning and, upon completion, must be restored to their marked position.

2.1.7 Access Openings - Duct

The Contractor may cut access openings in sheet metal ducts as needed to facilitate cleaning. Such openings shall be sealed using access doors with neoprene gasket material to insure against subsequent air leakage. No access panels or plates are to be used which require fastening by means of sheet metal screws, or tape.

2.1.8 Access Openings - Ceiling

When required, the Contractor may cut access openings in the ceiling to facilitate cleaning, provided the size and location is approved by the Contracting Officer. The Contractor shall provide a door for the opening, which shall be flush with the ceiling, the same color as the ceiling and accessible for future use.

2.2 HEALTH AND SAFETY

2.2.1 Safety Requirements

The cleaning Contractor shall comply with all applicable Federal, State, and local requirements for protecting the safety of the Contractor's employees, building occupants, and the environment. In particular, all applicable standards of the Occupational Safety and Health Administration (OSHA) should be followed.

2.2.2 Health Requirements

No processes or materials shall be employed in such a manner that they will create adverse health affects to the building occupants, cleaning contractors, or general public.

2.2.3 Disposal of Debris

All debris removed from the ACS shall be disposed of in accordance with all applicable Federal, State, and local requirements.

PART 3 EXECUTION

3.1 MECHANICAL CLEANING

3.1.1 Air Handling Unit (AHU)

Prior to the cleaning of the AHU, temporary filter media is to be fitted to all terminal end outlets to prevent dirt and debris from entering the occupied spaces. The AHU shall be deactivated, locked, and tagged.

- a. Fresh air plenums shall be brushed, washed and/or vacuumed thoroughly. Inlet louvers, mixing dampers and turning vanes shall be scraped or wire brushed as necessary. All debris shall be removed from plenum areas.
- b. Remove filters, if metal is corroded, then hand scrape, and/or wire brush the filter holding frames.
- c. Vacuum, wash or wire brush by hand all sides, floors and ceiling panels in each of the plenums or chambers within the AHU.
- d. remove corrosion from around coil frames and drain pans; hand brush and vacuum clean as necessary.
- e. Utilizing a high pressure water cleaning system with suitable biodegradable coil cleaning agent, thoroughly clean coil faces ensuring all contaminants and material are removed taking precautions not to damage coil fins. If fins are bent during cleaning process then straighten (as best as possible) utilizing a coil comb or similar device. If fins are damaged prior to cleaning note damaged areas and report to customer.
- f. Vacuum clean and hand wash fan casing and motors so that all dirt and excess grease is removed. Do not pressure wash motors.
- g. Hand scrape or brush fan impellers and remove all loose contaminants from within the fan casing.
 - h. Where insulation is damaged or fragile, the Contractor shall:
 - (1) Encapsulate with Foster 40-10 or equivalent.
 - (2) Remove and replace damaged areas.
- (3) Encapsulate all insulation whether damaged or not whichever is specified by customer.
- i. After completely cleaning the AHU, sanitize interior as specified in item $3. \,$
 - j. Contractor shall ensure that all filters are replaced and installed

properly. New filters will be furnished by customer. Contractor shall immediately notify customer of any missing or damaged access doors and/or filters or any other problems affecting the ACS.

3.1.2 Supply, Return and Exhaust Ductwork

Contamination shall be removed from the air distribution system and all work shall conform to the following specifications:

- a. Prior to cleaning any ductwork, it shall first be placed under negative pressure as described in paragraph 2.1.1. The AHU shall be deactivated, locked and tagged.
- b. By inserting air lances combined with mechanical agitators or rotary brushes through the installed access doors, gently move all loose contaminants from the interior surfaces of the ductwork to the point of collection. Where ductwork has internal insulation or other fragile components take precautions not to disrupt or damage these sensitive areas. Inspection may be conducted by the Contracting Officer's Representative during any stage of the cleaning process to ensure that methods utilized will keep liners intact.
- c. Duct mounted volume, fire and zone damper sets are to be marked to their current setting, inspected and cleaned as necessary. Contractor shall indicate locations of all damaged dampers on contract drawings and inform customer prior to testing and balancing of the HVAC system is performed.
- d. The grilles, registers, and diffusers (GRD) shall be removed, vacuum cleaned, washed, dried and the replaced. When GRD are restricted by a façade, welded or otherwise not removable they may be cleaned in place. Contractor shall mark and return damper setting to its original setting.

3.2 GENERAL

Monitoring of the Contractor's performance of work may be conducted by the Contracting Officer or its representative without notice to the Contractor, and the affected systems may be inspected at any reasonable time during the performance of this cleaning. Verification of ACS cleanliness will be determined after Mechanical Cleaning and before the application of any treatment or introduction of any treatment-related substances to the ACS. Verification on Non-Porous Surface Cleaning shall be conducted before the ACS is restored to normal operation.

3.2.1 Verification of Non-Porous Surface Cleaning

All non-Porous ACS Surface must be Visibly Clean and capable of passing the NADCA Vacuum test. (NADCA 01)

3.2.2 Sanitizing

Sanitizing the air distribution network shall be performed as required. Using a chemical distribution system, coat the interior surfaces of the ductwork with a fine mist of an approved sanitizing fluid. Such sanitizer

must be a product registered with Environmental Protection Agency.

-- End of Section --

SECTION 15990

TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ASSOCIATED AIR BALANCE COUNCIL (AABC)

AABC MN-1 (1989) National Standards for Testing and

Balancing Heating, Ventilating, and Air

Conditioning Systems

NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB)

NEBB Procedural Studs (1991) Procedural Standards for Testing

Adjusting Balancing of Environmental

Systems

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

TAB Schematic Drawings and Report Forms; G WA

Three copies of the TAB Schematic Drawings and Report Forms, no later than 21 days prior to the start of TAB field measurements.

SD-03 Product Data

TAB Related HVAC Submittals

A list of the TAB Related HVAC Submittals, no later than 7 days after the approval of the TAB Specialist.

TAB Procedures; G WA

Proposed procedures for TAB, submitted with the TAB Schematic Drawings and Report Forms.

SD-06 Test Reports

TAB Report; G WA

Three copies of the completed TAB Reports, no later that 7 days after the execution of TAB. All items in the TAB Report shall be signed by the TAB Specialist and shall bear the seal of the Professional Society or National Association used as the TAB Standard.

TAB Verification Report; G WA

Three copies of the completed TAB Verification Report, no later that 7 days after the execution of TAB Verification. All items in the TAB Verification Report shall be signed by the TAB Specialist and shall bear the seal of the Professional Society or National Association used as the TAB Standard.

SD-07 Certificates

Ductwork Leak Testing

A written statement signed by the TAB Specialist certifying that the TAB Specialist witnessed the Ductwork Leak Testing, it was successfully completed, and that there are no known deficiencies related to the ductwork installation that will prevent TAB from producing satisfactory results.

TAB Firm; G WA

Certification of the proposed TAB Firm's qualifications by either AABC or NEBB to perform the duties specified herein and in other related Sections, no later than 21 days after the Notice to Proceed. The documentation shall include the date that the Certification was initially granted and the date that the current Certification expires. Any lapses in Certification of the proposed TAB Firm or disciplinary action taken by AABC or NEBB against the proposed TAB Firm shall be described in detail.

TAB Specialist; G WA

Certification of the proposed TAB Specialist's qualifications by either AABC or NEBB to perform the duties specified herein and in other related Sections, no later than 21 days after the Notice to Proceed. The documentation shall include the date that the Certification was initially granted and the date that the current Certification expires. Any lapses in Certification of the proposed TAB Specialist or disciplinary action taken by AABC or NEBB against the proposed TAB Specialist shall be described in detail.

1.3 SIMILAR TERMS

In some instances, terminology differs between the Contract and the TAB Standard primarily because the intent of this Section is to use the industry standards specified, along with additional requirements listed herein to produce optimal results. The following table of similar terms is

provided for clarification only. Contract requirements take precedent over the corresponding AABC or NEBB requirements where differences exist.

SIMILAR TERMS

Contract Term	AABC Term	NEBB Term
TAB Standard	National Standards for	Procedural Standards
Adjusting	Testing and Balancing	for Testing
	Heating, Ventilating, and Air Conditioning Systems	Balancing of Environmental Systems.
TAB Specialist	TAB Engineer	TAB Supervisor
Systems Readiness Check	Construction Phase Inspection	Field Readiness Check & Preliminary Field Procedures.

1.4 TAB STANDARD

TAB shall be performed in accordance with the requirements of the standard under which the TAB Firm's qualifications are approved, i.e., AABC MN-lor NEBB Procedural Stds, unless otherwise specified herein. All recommendations and suggested practices contained in the TAB Standard shall be considered mandatory. The provisions of the TAB Standard, including checklists, report forms, etc., shall, as nearly as practical, be used to satisfy the Contract requirements. The TAB Standard shall be used for all aspects of TAB, including qualifications for the TAB Firm and Specialist and calibration of TAB instruments. Where the instrument manufacturer calibration recommendations are more stringent than those listed in the TAB Standard, the manufacturer's recommendations shall be adhered to. All quality assurance provisions of the TAB Standard such as performance guarantees shall be part of this contract. For systems or system components not covered in the TAB Standard, TAB procedures shall be developed by the TAB Specialist. Where new procedures, requirements, etc., applicable to the Contract requirements have been published or adopted by the body responsible for the TAB Standard used (AABC or NEBB), the requirements and recommendations contained in these procedures and requirements shall be considered mandatory.

1.5 QUALIFICATIONS

1.5.1 TAB Firm

The TAB Firm shall be either a member of AABC or certified by the NEBB and certified in all categories and functions where measurements or performance are specified on the plans and specifications. The certification shall be maintained for the entire duration of duties specified herein. If, for any reason, the firm loses subject certification during this period, the Contractor shall immediately notify the Contracting Officer and submit another TAB Firm for approval. Any firm that has been the subject of disciplinary action by either the AABC or the NEBB within the five years

preceding Contract Award shall not be eligible to perform any duties related to the HVAC systems, including TAB. All work specified in this Section and in other related Sections to be performed by the TAB Firm shall be considered invalid if the TAB Firm loses its certification prior to Contract completion and must be performed by an approved successor. These TAB services are to assist the prime Contractor in performing the quality oversight for which it is responsible. The TAB Firm shall be a subcontractor of the prime Contractor, and shall report to and be paid by the prime Contractor.

1.5.2 TAB Specialist

The TAB Specialist shall be either a member of AABC or an experienced technician of the Firm certified by the NEBB. The certification shall be maintained for the entire duration of duties specified herein. If, for any reason, the Specialist loses subject certification during this period, the Contractor shall immediately notify the Contracting Officer and submit another TAB Specialist for approval. Any individual that has been the subject of disciplinary action by either the AABC or the NEBB within the five years preceding Contract Award shall not be eligible to perform any duties related to the HVAC systems, including TAB. All work specified in this Section and in other related Sections performed by the TAB Specialist shall be considered invalid if the TAB Specialist loses its certification prior to Contract completion and must be performed by the approved successor.

1.6 TAB SPECIALIST RESPONSIBILITIES

All TAB work specified herein and in related sections shall be performed under the direct guidance of the TAB Specialist. The TAB Specialist shall participate in the commissioning process specified in Section 15995 COMMISSIONING OF HVAC SYSTEMS.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 DESIGN REVIEW

The TAB Specialist shall review the Contract Plans and Specifications and advise the Contracting Officer of any deficiencies that would prevent the HVAC systems from effectively operating in accordance with the sequence of operation specified or prevent the effective and accurate TAB of the system. The TAB Specialist shall provide a Design Review Report individually listing each deficiency and the corresponding proposed corrective action necessary for proper system operation.

3.2 TAB RELATED HVAC SUBMITTALS

The TAB Specialist shall prepare a list of the submittals from the Contract Submittal Register that relate to the successful accomplishment of all HVAC TAB. The submittals identified on this list shall be accompanied by a letter of approval signed and dated by the TAB Specialist when submitted to the Government. The TAB Specialist shall also ensure that the location and

details of ports, terminals, connections, etc., necessary to perform TAB are identified on the submittals.

3.3 TAB SCHEMATIC DRAWINGS AND REPORT FORMS

A schematic drawing showing each system component, including balancing devices, shall be provided for each system. Each drawing shall be accompanied by a copy of all report forms required by the TAB Standard used for that system. Where applicable, the acceptable range of operation or appropriate setting for each component shall be included on the forms or as an attachment to the forms. The schematic drawings shall identify all testing points and cross reference these points to the report forms and procedures.

3.4 TESTING, ADJUSTING, AND BALANCING

3.4.1 TAB Procedures

Step by step procedures for each measurement required during TAB Execution shall be provided. The procedures shall be oriented such that there is a separate section for each system. The procedures shall include measures to ensure that each system performs as specified in all operating modes, interactions with other components and systems, and with all seasonal operating differences, diversity, simulated loads, and pressure relationships required.

3.4.2 Systems Readiness Check

The TAB Specialist shall inspect each system to ensure that it is complete, including installation and operation of controls, and that all aspects of the facility that have any bearing on the HVAC systems, including installation of ceilings, walls, windows, doors, and partitions, are complete to the extent that TAB results will not be affected by any detail or touch-up work remaining. The TAB Specialist shall also verify that all items such as ductwork and piping ports, terminals, connections, etc., necessary to perform TAB shall be complete during the Systems Readiness Check.

3.4.3 Preparation of TAB Report

The TAB Report shall be oriented so that there is a separate section for each system. The Report shall include a copy of the appropriate approved Schematic Drawings and TAB Related Submittals, such as pump curves, fan curves, etc., along with the completed report forms for each system. The operating points measured during successful TAB Execution and the theoretical operating points listed in the approved submittals shall be marked on the performance curves and tables. Where possible, adjustments shall be made using an "industry standard" technique which would result in the greatest energy savings, such as adjusting the speed of a fan instead of throttling the flow. Any deficiencies outside of the realm of normal adjustments and balancing during TAB Execution shall be noted along with a description of corrective action performed to bring the measurement into the specified range. If, for any reason, the TAB Specialist determines during TAB Execution that any Contract requirement cannot be met, the TAB

Specialist shall immediately provide a written description of the deficiency and the corresponding proposed corrective action necessary for proper system operation to the Contracting Officer.

3.4.4 TAB Verification

The TAB Specialist shall recheck ten percent of the measurements listed in the Tab Report and prepare a TAB Verification Report. The measurements selected for verification and the individuals that witness the verification will be selected by the Contracting Officer's Representative (COR). The measurements will be recorded in the same manner as required for the TAB All measurements that fall outside the acceptable operating range specified shall be accompanied by an explanation as to why the measurement does not correlate with that listed in the TAB Report and a description of corrective action performed to bring the measurement into the specified range. The TAB Specialist shall update the original TAB report to reflect any changes or differences noted in the TAB verification report and submit the updated TAB report. If over 20 percent of the measurements selected by the COR for verification fall outside of the acceptable operating range specified, the COR will select an additional ten percent for verification. If over 20 percent of the total tested (including both test groups) fall outside of the acceptable range, the TAB Report shall be considered invalid and all contract TAB work shall be repeated beginning with the Systems Readiness Check.

3.4.5 Marking of Setting

Following approval of TAB Verification Report, the setting of all HVAC adjustment devices including valves, splitters, and dampers shall be permanently marked by the TAB Specialist so that adjustment can be restored if disturbed at any time.

3.4.6 Identification of Test Ports

The TAB Specialist shall permanently and legibly identify the location points of duct test ports. If the ductwork has exterior insulation, the identification shall be made on the exterior side of the insulation. All penetrations through ductwork and ductwork insulation shall be sealed to prevent air leakage or to maintain integrity of vapor barrier.

-- End of Section --

SECTION 16415

ELECTRICAL WORK, INTERIOR

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI C37.16	(2000) Low-Voltage Power Circuit Breakers and AC Power Circuit Protectors - Preferred Ratings, Related Requirements, and Application Recommendations
INSTITUTE OF ELECTRICAL	AND ELECTRONICS ENGINEERS (IEEE)
IEEE C2	(1997) National Electrical Safety Code
IEEE C37.13	(1990; R 1995) Low-Voltage AC Power Circuit Breakers Used in Enclosures
NATIONAL ELECTRICAL MAN	UFACTURERS ASSOCIATION (NEMA)
NEMA AB 1	(1993) Molded Case Circuit Breakers and Molded Case Switches
NEMA FU 1	(1986) Low Voltage Cartridge Fuses
NEMA ICS 1	(1993) Industrial Control and Systems
NEMA ICS 2	(1993) Industrial Controls and Systems Controllers, Contactors, and Overload Relays Rated Not More Than 2,000 Volts AC or 750 Volts DC
NEMA ICS 3	(1993) Industrial Control and Systems Factory Built Assemblies
NEMA ICS 6	(1993) Industrial Control and Systems, Enclosures
NEMA MG 10	(1994) Energy Management Guide for Selection and Use of Polyphase Motors
NEMA OS 1	(1996) Sheet-Steel Outlet Boxes, Device Boxes, Covers, and Box Supports
NEMA OS 2	(1998) Nonmetallic Outlet Boxes, Device

Boxes, Covers and Box Supports

NEMA PB 1	(1995) Panelboards
NEMA TC 13	(1993) Electrical Nonmetallic Tubing (ENT)
NEMA TC 2	(1998) Electrical Polyvinyl Chloride (PVC) Tubing (EPT) and Conduit (EPC-40 and EPC-80)
NEMA WD 1	(1999) General Requirements for Wiring Devices
NEMA WD 6	(1997) Wiring Devices - Dimensional Requirements
NATIONAL FIRE PROTECT	TION ASSOCIATION (NFPA)
NFPA 101	(2000) Life Safety Code
NFPA 70	(1999) National Electrical Code
UNDERWRITERS LABORATO	DRIES (UL)
UL 1	(2000) Flexible Metal Conduit
UL 1004	(1994; Rev thru Nov 1999) Electric Motors
UL 1242	(1996; Rev Mar 1998) Intermediate Metal Conduit
UL 1660	(2000) Liquid-Tight Flexible Nonmetallic Conduit
UL 20	(1995; Rev thru Oct 1998) General-Use Snap Switches
UL 360	(1996; Rev thru Oct 1997) Liquid-Tight Flexible Steel Conduit
UL 486A	(1997; Rev thru Dec 1998) Wire Connectors and Soldering Lugs for Use with Copper Conductors
UL 489	(1996; Rev thru Dec 1998) Molded-Case Circuit Breakers, Molded-Case Switches, and Circuit-Breaker Enclosures
UL 498	(1996; Rev thru Jan 1999) Attachment Plugs and Receptacles
UL 50	(1995; Rev thru Nov 1999) Enclosures for Electrical Equipment
UL 508	(1999) Industrial Control Equipment

UL 510	(1994; Rev thru Apr 1998) Polyvinyl Chloride, Polyethylene, and Rubber Insulating Tape
UL 512	(1993; Rev thru Mar 1999) Fuseholders
UL 514A	(1996; Rev Dec 1999) Metallic Outlet Boxes
UL 514B	(1997; Rev Oct 1998) Fittings for Cable and Conduit
UL 514C	(1996; Rev thru Dec 1999) Nonmetallic Outlet Boxes, Flush-Device Boxes, and Covers
UL 6	(1997) Rigid Metal Conduit
UL 651	(1995; Rev thru Oct 1998) Schedule 40 and 80 Rigid PVC Conduit
UL 67	(1993; Rev thru Oct 1999) Panelboards
UL 719	(1996; Rev Jul 1999) Nonmetallic-Sheathed Cables
UL 797	(1993; Rev thru Mar 1997) Electrical Metallic Tubing

1.2 GENERAL

1.2.1 Rules

The installation shall conform to the requirements of NFPA 70 and NFPA 101, unless more stringent requirements are indicated or shown.

1.2.2 Coordination

The drawings indicate the extent and the general location and arrangement of equipment, conduit, and wiring. The Contractor shall become familiar with all details of the work and verify all dimensions in the field so that the outlets and equipment shall be properly located and readily accessible. The Contractor shall coordinate the electrical requirements of the mechanical work and provide all power related circuits, wiring, hardware and structural support, even if not shown on the drawings.

1.2.3 Special Environments

1.2.3.1 Weatherproof Locations

Wiring and equipment in designated locations shall conform to NFPA 70 requirements for installation in damp or wet locations.

1.2.3.2 Ducts, Plenums and Other Air-Handling Spaces

Wiring and equipment in ducts, plenums and other air-handling spaces shall be installed using materials and methods in conformance with NFPA 70unless more stringent requirements are indicated in this specification or on the contract drawings.

1.2.4 Standard Products

Material and equipment shall be a standard product of a manufacturer regularly engaged in the manufacture of the product and shall essentially duplicate items that have been in satisfactory use for at least 2 years prior to bid opening.

1.2.5 Nameplates

1.2.5.1 Identification Nameplates

Major items of electrical equipment and major components shall be permanently marked with an identification name to identify the equipment by type or function and specific unit number as indicated. Designation of motors shall coincide with their designation in the motor control center or panel. Unless otherwise specified, identification nameplates shall be made of laminated plastic in accordance with ASTM D 709 with black outer layers and a white core. Edges shall be chamfered. Plates shall be fastened with black-finished round-head drive screws, except motors, or approved nonadhesive metal fasteners. When the nameplate is to be installed on an irregular-shaped object, the Contractor shall devise an approved support suitable for the application and ensure the proper installation of the supports and nameplates. In all instances, the nameplate shall be installed in a conspicuous location. At the option of the Contractor, the equipment manufacturer's standard embossed nameplate material with black paint-filled letters may be furnished in lieu of laminated plastic. The front of each panelboard, motor control center, switchgear, and switchboard shall have a nameplate to indicate the phase letter, corresponding color and arrangement of the phase conductors. The following equipment, as a minimum, shall be provided with identification nameplates:

> Minimum 1/4 inch High Letters

Minimum 1/8 inch High Letters

Panelboards
Starters
Safety Switches
Motor Control Centers
Equipment Enclosures
Motors

Control Power Transformers Control Devices Instrument Transformers

Each panel, section, or unit in motor control centers, switchgear or similar assemblies shall be provided with a nameplate in addition to nameplates listed above, which shall be provided for individual compartments in the respective assembly, including nameplates which identify "future," "spare," and "dedicated" or "equipped spaces."

1.2.6 As-Built Drawings

Following the project completion or turnover, within 30 days the Contractor shall furnish 2 sets of as-built drawings to the Contracting Officer.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Interior Electrical Equipment; G WA.

Detail drawings consisting of equipment drawings, illustrations, schedules, instructions, diagrams, and other information necessary to define the installation. Detail drawings shall show the rating of items and systems and how the components of an item and system are assembled, function together, and how they will be installed on the project. Data and drawings for component parts of an item or system shall be coordinated and submitted as a unit. Data and drawings shall be coordinated and included in a single submission. Multiple submissions for the same equipment or system are not acceptable except where prior approval has been obtained from the Contracting Officer. In such cases, a list of data to be submitted later shall be included with the first submission. Detail drawings shall show physical arrangement, construction details, connections, finishes, materials used in fabrication, provisions for conduit or busway entrance, access requirements for installation and maintenance, physical size, electrical characteristics, foundation and support details, and equipment weight. Drawings shall be drawn to scale and/or dimensioned. Optional items shall be clearly identified as included or excluded. Detail drawings shall as a minimum include:

- a. Motors and rotating machinery.
- b. Single line electrical diagrams including primary, metering, sensing and relaying, control wiring, and control logic.

Structural drawings showing the structural or physical features of major equipment items, components, assemblies, and structures, including foundations or other types of supports for equipment and conductors. These drawings shall include accurately scaled or dimensioned outline and arrangement or layout drawings to show the physical size of equipment and components and the relative arrangement and physical connection of related components. Weights of equipment, components and assemblies shall be provided when required to verify the adequacy of design and proposed construction of foundations or other types of supports. Dynamic forces shall be stated for switching devices when such forces must be considered in the design of support structures. The

appropriate detail drawings shall show the provisions for leveling, anchoring, and connecting all items during installation, and shall include any recommendations made by the manufacturer.

Electrical drawings including single-line and three-line diagrams, and schematics or elementary diagrams of each electrical system; internal wiring and field connection diagrams of each electrical device when published by the manufacturer; wiring diagrams of cabinets, panels, units, or separate mountings; interconnection diagrams that show the wiring between separate components of assemblies; field connection diagrams that show the termination of wiring routed between separate items of equipment; internal wiring diagrams of equipment showing wiring as actually provided for this project. Field wiring connections shall be clearly identified.

If departures from the contract drawings are deemed necessary by the Contractor, complete details of such departures, including changes in related portions of the project and the reasons why, shall be submitted with the detail drawings. Approved departures shall be made at no additional cost to the Government.

SD-03 Product Data

Manufacturer's Catalog

Data composed of catalog cuts, brochures, circulars, specifications, product data, and printed information in sufficient detail and scope to verify compliance with the requirements of the contract documents.

Material, Equipment Lists; G WA.

A complete itemized listing of equipment and materials proposed for incorporation into the work. Each entry shall include an item number, the quantity of items proposed, and the name of the manufacturer of each item.

Installation Procedures

Installation procedures for rotating equipment, transformers, switchgear, battery systems, voltage regulators, and grounding resistors. Procedures shall include diagrams, instructions, and precautions required to install, adjust, calibrate, and test devices and equipment.

As-Built Drawings; G WA.

The as-built drawings shall be a record of the construction as installed. The drawings shall include all the information shown on the contract drawings, deviations, modifications, and changes from the contract drawings, however minor. The as-built drawings shall be kept at the job site and updated daily. The as-built drawings shall be a full-sized set of prints marked to reflect all deviations, changes, and modifications. The as-built drawings

shall be complete and show the location, size, dimensions, part identification, and other information. Additional sheets may be added. The as-built drawings shall be jointly inspected for accuracy and completeness by the Contractor's quality control representative and by the Contracting Officer prior to the submission of each monthly pay estimate. Upon completion of the work, the Contractor shall submit three full sized sets of the marked prints to the Contracting Officer for approval. If upon review, the as-built drawings are found to contain errors and/or omissions, they will be returned to the Contractor for correction. The Contractor shall correct and return the as-built drawings to the Contracting Officer for approval within ten calendar days from the time the drawings are returned to the Contractor.

Onsite Tests; G WA.

A detailed description of the Contractor's proposed procedures for on-site tests.

SD-06 Test Reports

Field Test Plan; G WA.

A detailed description of the Contractor's proposed procedures for onsite test submitted 20 days prior to testing the installed system. No field test will be performed until the test plan is approved. The test plan shall consist of complete field test procedures including tests to be performed, test equipment required, and tolerance limits.

Field Test Reports; G WA.

Six copies of the information described below in $8\ 1/2\ x\ 11$ inch binders having a minimum of 5 rings from which material may readily be removed and replaced, including a separate section for each test. Sections shall be separated by heavy plastic dividers with tabs.

- a. A list of equipment used, with calibration certifications.
- b. A copy of measurements taken.
- c. The dates of testing.
- d. The equipment and values to be verified.
- e. The conditions specified for the test.
- f. The test results, signed and dated.
- g. A description of adjustments made.
- h. Final position of controls and device settings.

SD-07 Certificates

Materials and Equipment

The label or listing of the Underwriters Laboratories, Inc., will be accepted as evidence that the materials or equipment conform to the applicable standards of that agency. In lieu of this label or listing, a statement from a nationally recognized, adequately equipped testing agency indicating that the items have been tested in accordance with required procedures and that the materials and equipment comply with all contract requirements will be accepted. However, materials and equipment installed in hazardous locations must bear the UL label unless the data submitted from other testing agency is specifically approved in writing by the Contracting Officer. Items which are required to be listed and labeled in accordance with Underwriters Laboratories must be affixed with a UL label that states that it is UL listed. No exceptions or waivers will be granted to this requirement. Materials and equipment will be approved based on the manufacturer's published data.

For other than equipment and materials specified to conform to UL publications, a manufacturer's statement indicating complete compliance with the applicable standard of the American Society for Testing and Materials, National Electrical Manufacturers Association, or other commercial standard, is acceptable.

1.4 WORKMANSHIP

Materials and equipment shall be installed in accordance with NFPA 70, recommendations of the manufacturer, and as shown.

PART 2 PRODUCTS

Products shall conform to the respective publications and other requirements specified below. Materials and equipment not listed below shall be as specified elsewhere in this section. Items of the same classification shall be identical including equipment, assemblies, parts, and components.

2.1 CABLES AND WIRES

Conductors No. 8 AWG and larger diameter shall be stranded. Conductors No. 10 AWG and smaller diameter shall be solid, except that conductors for remote control, alarm, and signal circuits, classes 1, 2, and 3, shall be stranded unless specifically indicated otherwise. Conductor sizes and ampacities shown are based on copper, unless indicated otherwise. All conductors shall be copper.

2.1.1 Equipment Manufacturer Requirements

When manufacturer's equipment requires copper conductors at the terminations or requires copper conductors to be provided between components of equipment, provide copper conductors or splices, splice

boxes, and other work required to meet manufacturer's requirements.

2.1.2 Insulation

Unless indicated otherwise, or required by NFPA 70, power and lighting wires shall be 600-volt, Type THWN, THHN, or THW conforming to UL 83 or RHW conforming to UL 44, except that grounding wire may be type TW conforming to UL 83; remote-control and signal circuits shall be Type TW, THW or TF, conforming to UL 83. Where lighting fixtures require 90-degree Centigrade (C) conductors, provide only conductors with 90-degree C insulation or better.

2.1.3 Bonding Conductors

ASTM B 1, solid bare copper wire for sizes No. 8 AWG and smaller diameter; ASTM B 8, Class B, stranded bare copper wire for sizes No. 6 AWG and larger diameter.

2.1.4 Non-metallic Sheathed Cable

UL 719, type NM or NMC.

2.2 CIRCUIT BREAKERS

2.2.1 MOLDED-CASE CIRCUIT BREAKERS

Molded-case circuit breakers shall conform to NEMA AB 1 and UL 489and UL 877 for circuit breakers and circuit breaker enclosures located in hazardous (classified) locations. Circuit breakers may be installed in panelboards, switchboards, enclosures, motor control centers, or combination motor controllers.

2.2.1.1 Construction

Circuit breakers shall be suitable for mounting and operating in any position. Lug shall be listed for copper conductors only and copper and aluminum conductors in accordance with UL 486E. Single-pole circuit breakers shall be full module size with not more than one pole per module. Multi-pole circuit breakers shall be of the common-trip type having a single operating handle such that an overload or short circuit on any one pole will result in all poles opening simultaneously. Sizes of 100 amperes or less may consist of single-pole breakers permanently factory assembled into a multi-pole unit having an internal, mechanical, nontamperable common-trip mechanism and external handle ties. All circuit breakers shall have a quick-make, quick-break overcenter toggle-type mechanism, and the handle mechanism shall be trip-free to prevent holding the contacts closed against a short-circuit or sustained overload. All circuit breaker handles shall assume a position between "ON" and "OFF" when tripped automatically. All ratings shall be clearly visible.

2.2.1.2 Ratings

Voltage ratings shall be not less than the applicable circuit voltage. The interrupting rating of the circuit breakers shall be at least equal to the

available short-circuit current at the line terminals of the circuit breaker and correspond to the UL listed integrated short-circuit current rating specified for the panelboards and switchboards. Molded-case circuit breakers shall have nominal voltage ratings, maximum continuous-current ratings, and maximum short-circuit interrupting ratings in accordance with NEMA AB 1. Ratings shall be coordinated with system X/R ratio.

2.2.1.3 Cascade System Ratings

Circuit breakers used in series combinations shall be in accordance with UL 489. Equipment, such as switchboards and panelboards, which house series-connected circuit breakers shall be clearly marked accordingly. Series combinations shall be listed in the UL Recognized Component Directory under "Circuit Breakers-Series Connected."

- 2.3 CONDUIT AND TUBING
- 2.3.1 Electrical, Zinc-Coated Steel Metallic Tubing (EMT)

UL 797

2.3.2 Electrical Nonmetallic Tubing (ENT)

NEMA TC 13.

2.3.3 Electrical Plastic Tubing and Conduit

NEMA TC 2.

2.3.4 Flexible Conduit, Steel and Plastic

General-purpose type, UL 1; liquid tight, UL 360, and UL 1660.

2.3.5 Intermediate Metal Conduit

UL 1242.

2.3.6 Rigid Metal Conduit

UL 6.

2.3.7 Rigid Plastic Conduit

NEMA TC 2, UL 651 and UL 651A.

- 2.3.8 Surface Metal Electrical Raceways and Fittings
 - UL 5.
- 2.4 CONDUIT AND DEVICE BOXES AND FITTINGS
- 2.4.1 Boxes, Metallic Outlet

NEMA OS 1 and UL 514A.

- 2.4.2 Boxes, Nonmetallic, Outlet and Flush-Device Boxes and Covers
 NEMA OS 2 and UL 514C.
- 2.4.3 Boxes, Switch (Enclosed), Surface-Mounted UL 98.
- 2.4.4 Fittings for Conduit and Outlet Boxes
 UL 514B.
- 2.4.5 Fittings, PVC, for Use with Rigid PVC Conduit and Tubing UL 514B.
- 2.5 CONNECTORS, WIRE PRESSURE
- 2.5.1 For Use With Copper Conductors
 UL 486A.
- 2.6 ENCLOSURES
- 2.6.1 Cabinets and Boxes

Cabinets and boxes with volume greater than 100 cubic inches shall be in accordance with UL 50, hot-dip, zinc-coated, if sheet steel.

2.6.2 Circuit Breaker Enclosures

UL 489.

- 2.7 LOW-VOLTAGE FUSES AND FUSEHOLDERS
- 2.7.1 Fuses, Low Voltage Cartridge Type

NEMA FU 1.

2.7.2 Fuseholders

UL 512.

2.8 INSTRUMENTS, ELECTRICAL INDICATING

ANSI C39.1.

2.9 MOTORS, AC, FRACTIONAL AND INTEGRAL

Motors, ac, fractional and integral horsepower, 500 hp and smaller shall conform to NEMA MG 1 and UL 1004for motors. In addition to the standards listed above, motors shall be provided with efficiencies as specified in the table "MINIMUM NOMINAL EFFICIENCIES" below.

2.9.1 Rating

The horsepower rating of motors should be limited to no more than 125 percent of the maximum load being served unless a NEMA standard size does not fall within this range. In this case, the next larger NEMA standard motor size should be used.

2.9.2 Motor Efficiencies

All permanently wired polyphase motors of 1 hp or more shall meet the minimum full-load efficiencies as indicated in the following table, and as specified in this specification. Motors of 1 hp or more with open, drip proof or totally enclosed fan cooled enclosures shall be high efficiency type, unless otherwise indicated. Motor efficiencies indicated in the tables apply to general-purpose, single-speed, polyphase induction motors. Applications which require definite purpose, special purpose, special frame, or special mounted polyphase induction motors are excluded from these efficiency requirements. Motors provided as an integral part of motor driven equipment are excluded from this requirement if a minimum seasonal or overall efficiency requirement is indicated for that equipment by the provisions of another section.

MINIMUM NOMINAL MOTOR EFFICIENCIES OPEN DRIP PROOF MOTORS

<u>kW</u>	1200 RPM	1800 RPM	3600 RPM
0 546	00.5	0.5.	
0.746	82.5	85.5	80.0
1.12	86.5	86.5	85.5
1.49	87.5	86.5	86.5
2.24	89.5	89.5	86.5
3.73	89.5	89.5	89.5
5.60	91.7	91.0	89.5
7.46	91.7	91.7	90.2
11.2	92.4	93.0	91.0
14.9	92.4	93.0	92.4
18.7	93.0	93.6	93.0
22.4	93.6	93.6	93.0
29.8	94.1	94.1	93.6
37.3	94.1	94.5	93.6
44.8	95.0	95.0	94.1
56.9	95.0	95.0	94.5
74.6	95.0	95.4	94.5
93.3	95.4	95.4	95.0
112.0	95.8	95.8	95.4
149.0	95.4	95.8	95.4
187.0	95.4	96.2	95.8
224.0	95.4	95.0	95.4
261.0	94.5	95.4	95.0
298.0	94.1	95.8	95.0
336.0	94.5	95.4	95.4
373.0	94.5	94.5	94.5

MINIMUM NOMINAL MOTOR EFFICIENCIES

TOTALLY ENCLOSED FAN-COOLED MOTORS

kW	1200 RPM	1800 RPM	3600 RPM
0.746	82.5	85.5	78.5
1.12	87.5	86.5	85.5
1.49	88.5	86.5	86.5
2.24	89.5	89.5	88.5
3.73	89.5	89.5	89.5
5.60	91.7	91.7	91.0
7.46	91.7	91.7	91.7
11.2	92.4	92.4	91.7
14.9	92.4	93.0	92.4
18.7	93.0	93.6	93.0
22.4	93.6	93.6	93.0
29.8	94.1	94.1	93.6
37.3	94.1	94.5	94.1
44.8	94.5	95.0	94.1
56.9	95.0	95.4	94.5
74.6	95.4	95.4	95.0
93.3	95.4	95.4	95.4
112.0	95.8	95.8	95.4
149.0	95.8	96.2	95.8
187.0	95.6	96.2	95.9
224.0	95.4	96.1	95.8
261.0	94.5	96.2	94.8
298.0	94.5	95.8	94.5
336.0	94.5	94.5	94.5
373.0	94.5	94.5	94.5

MINIMUM NOMINAL MOTOR EFFICIENCIES OPEN DRIP PROOF MOTORS

HP	1200 RPM	1800 RPM	3600 RPM
1	82.5	85.5	80.0
1.5	86.5	86.5	85.5
2	87.5	86.5	86.5
3	89.5	89.5	86.5
5	89.5	89.5	89.5
7.5	91.7	91.0	89.5
10	91.7	91.7	90.2
15	92.4	93.0	91.0
20	92.4	93.0	92.4
25	93.0	93.6	93.0
30	93.6	93.6	93.0
40	94.1	94.1	93.6
50	94.1	94.5	93.6
60	95.0	95.0	94.1
75	95.0	95.0	94.5
100	95.0	95.4	94.5
125	95.4	95.4	95.0
150	95.8	95.8	95.4

	TOTALLY ENC	LOSED FAN-COOLED MOTOR	S
200	95.4	95.8	95.4
250	95.4	96.2	95.8
300	95.4	95.0	95.4
350	94.5	95.4	95.0
400	94.1	95.8	95.0
450	94.5	95.4	95.4
500	94.5	94.5	94.5

TOTALLY ENCLOSED FAN-COOLED MOTORS

HP	1200 RPM	1800 RPM	3600 RPM
_			
1	82.5	85.5	78.5
1.5	87.5	86.5	85.5
2	88.5	86.5	86.5
3	89.5	89.5	88.5
5	89.5	89.5	89.5
7.5	91.7	91.7	91.0
10	91.7	91.7	91.7
15	92.4	92.4	91.7
20	92.4	93.0	92.4
25	93.0	93.6	93.0
30	93.6	93.6	93.0
40	94.1	94.1	93.6
50	94.1	94.5	94.1
60	94.5	95.0	94.1
75	95.0	95.4	94.5
100	95.4	95.4	95.0
125	95.4	95.4	95.4
150	95.8	95.8	95.4
200	95.8	96.2	95.8
250	95.6	96.2	95.9
300	95.4	96.1	95.8
350	94.5	96.2	94.8
400	94.5	95.8	94.5
450	94.5	94.5	94.5
500	94.5	94.5	94.5

2.10 MOTOR CONTROLS AND MOTOR CONTROL CENTERS

2.10.1 Automatic Control Devices

2.10.1.1 Direct Control

Automatic control devices (such as thermostats, float or pressure switches) which control the starting and stopping of motors directly shall be designed for that purpose and have an adequate horsepower rating.

2.11 PANELBOARDS

Dead-front construction, NEMA PB 1 and UL 67.

2.12 RECEPTACLES

2.12.1 NEMA Standard Receptacle Configurations

NEMA WD 6.

a. 20-Ampere, 250 Volt

Two-pole, 3-wire grounding, non-locking: NEMA type 6-20R, locking: NEMA type L6-20R. Three-pole, 4-wire grounding, non-locking: NEMA type 15-20R, locking: NEMA type L15-20R.

2.13 POWER-SWITCHGEAR ASSEMBLIES INCLUDING SWITCHBOARDS

2.13.1 Circuit Breakers

Circuit breakers shall be molded-case circuit breakers.

2.14 WIRING DEVICES

NEMA WD 1 for wiring devices, and NEMA WD 6 for dimensional requirements of wiring devices.

PART 3 EXECUTION

3.1 GROUNDING

Grounding shall be in conformance with NFPA 70, the contract drawings, and the following specifications.

3.1.1 Grounding Conductors

A green equipment grounding conductor, sized in accordance with NFPA 70 shall be provided, regardless of the type of conduit. Equipment grounding bars shall be provided in all panelboards. The equipment grounding conductor shall be carried back to the service entrance grounding connection or separately derived grounding connection. All equipment grounding conductors, including metallic raceway systems used as such, shall be bonded or joined together in each wiring box or equipment enclosure. Metallic raceways and grounding conductors shall be checked to assure that they are wired or bonded into a common junction. Metallic boxes and enclosures, if used, shall also be bonded to these grounding conductors by an approved means per NFPA 70. [When switches, or other utilization devices are installed, any designated grounding terminal on these devices shall also be bonded to the equipment grounding conductor junction with a short jumper.

3.2 WIRING METHODS

Wiring shall conform to NFPA 70, the contract drawings, and the following specifications. Unless otherwise indicated, wiring shall consist of insulated conductors installed in rigid plastic conduit, electrical metallic tubing, electrical nonmetallic tubing. Wire fill in conduits shall be based on NFPA 70 for the type of conduit and wire insulations specified.

3.2.1 Conduit and Tubing Systems

Conduit and tubing systems shall be installed as indicated. Conduit sizes shown are based on use of copper conductors with insulation types as described in paragraph WIRING METHODS. Minimum size of raceways shall be 1/2 inch. Only metal conduits will be permitted when conduits are required for shielding or other special purposes indicated, or when required by conformance to NFPA 70. Nonmetallic conduit and tubing may be used in damp, wet or corrosive locations when permitted by NFPA 70 and the conduit or tubing system is provided with appropriate boxes, covers, clamps, screws or other appropriate type of fittings. Electrical metallic tubing (EMT) may be installed only within buildings. EMT may be installed in concrete and grout in dry locations. EMT installed in concrete or grout shall be provided with concrete tight fittings. EMT shall not be installed in damp or wet locations, or the air space of exterior masonry cavity walls. Bushings, manufactured fittings or boxes providing equivalent means of protection shall be installed on the ends of all conduits and shall be of the insulating type, where required by NFPA 70. Only UL listed adapters shall be used to connect EMT to rigid metal conduit, cast boxes, and conduit bodies. Penetrations of above grade floor slabs, time-rated partitions and fire walls shall be firestopped in accordance with Section 07840FIRESTOPPING. Except as otherwise specified, IMC may be used as an option for rigid steel conduit in areas as permitted by NFPA 70. Raceways shall not be installed under the firepits of boilers and furnaces and shall be kept 6 inches away from parallel runs of flues, steam pipes and hot-water pipes. Raceways shall be concealed within finished walls, ceilings, and floors unless otherwise shown. Raceways crossing structural expansion joints or seismic joints shall be provided with suitable expansion fittings or other suitable means to compensate for the building expansion and contraction and to provide for continuity of grounding.

3.2.1.1 Pull Wires

A pull wire shall be inserted in each empty raceway in which wiring is to be installed if the raceway is more than 50 feet in length and contains more than the equivalent of two 90-degree bends, or where the raceway is more than 150 feet in length. The pull wire shall be of No. 14 AWG zinc-coated steel, or of plastic having not less than 200 pounds per square inch tensile strength. Not less than 10 inches of slack shall be left at each end of the pull wire.

3.2.1.2 Conduit Stub-Ups

Where conduits are to be stubbed up through concrete floors, a short elbow shall be installed below grade to transition from the horizontal run of conduit to a vertical run. A conduit coupling fitting, threaded on the inside shall be installed, to allow terminating the conduit flush with the finished floor. Wiring shall be extended in rigid threaded conduit to equipment, except that where required, flexible conduit may be used 6 inches above the floor. Empty or spare conduit stub-ups shall be plugged flush with the finished floor with a threaded, recessed plug.

3.2.1.3 Below Slab-on-Grade or in the Ground

Electrical wiring below slab-on-grade shall be protected by a conduit system. Conduit passing vertically through slabs-on-grade shall be rigid steel or IMC. Rigid steel or IMC conduits installed below slab-on-grade or in the earth shall be field wrapped with 0.010 inch thick pipe-wrapping plastic tape applied with a 50 percent overlay, or shall have a factory-applied polyvinyl chloride, plastic resin, or epoxy coating system.

3.2.1.4 Installing in Slabs Including Slabs on Grade

Conduit installed in slabs-on-grade shall be rigid steel or IMC. Conduits shall be installed as close to the middle of concrete slabs as practicable without disturbing the reinforcement. Outside diameter shall not exceed 1/3 of the slab thickness and conduits shall be spaced not closer than 3 diameters on centers except at cabinet locations where the slab thickness shall be increased as approved by the Contracting Officer. Where conduit is run parallel to reinforcing steel, the conduit shall be spaced a minimum of one conduit diameter away but not less than one inch from the reinforcing steel.

3.2.1.5 Changes in Direction of Runs

Changes in direction of runs shall be made with symmetrical bends or cast-metal fittings. Field-made bends and offsets shall be made with an approved hickey or conduit-bending machine. Crushed or deformed raceways shall not be installed. Trapped raceways in damp and wet locations shall be avoided where possible. Lodgment of plaster, dirt, or trash in raceways, boxes, fittings and equipment shall be prevented during the course of construction. Clogged raceways shall be cleared of obstructions or shall be replaced.

3.2.1.6 Supports

Metallic conduits and tubing, and the support system to which they are attached, shall be securely and rigidly fastened in place to prevent vertical and horizontal movement at intervals of not more than 10 feet and within 3 feet of boxes, cabinets, and fittings, with approved pipe straps, wall brackets, conduit clamps, conduit hangers, threaded C-clamps, beam clamps, or ceiling trapeze. Loads and supports shall be coordinated with supporting structure to prevent damage or deformation to the structure. Loads shall not be applied to joist bridging. Attachment shall be by wood screws or screw-type nails to wood; by toggle bolts on hollow masonry units; by expansion bolts on concrete or brick; by machine screws, welded threaded studs, heat-treated or spring-steel-tension clamps on steel work. Nail-type nylon anchors or threaded studs driven in by a powder charge and provided with lock washers and nuts may be used in lieu of expansion bolts or machine screws. Raceways or pipe straps shall not be welded to steel structures. Cutting the main reinforcing bars in reinforced concrete beams or joists shall be avoided when drilling holes for support anchors. Holes drilled for support anchors, but not used, shall be filled. In partitions of light steel construction, sheet-metal screws may be used. Raceways shall not be supported using wire or nylon ties. Raceways shall be independently supported from the structure. Upper raceways shall not be used as a means of support for lower raceways. Supporting means shall not

be shared between electrical raceways and mechanical piping or ducts. Cables and raceways shall not be supported by ceiling grids. Except where permitted by NFPA 70, wiring shall not be supported by ceiling support systems. Conduits shall be fastened to sheet-metal boxes and cabinets with two locknuts where required by NFPA 70, where insulating bushings are used, and where bushings cannot be brought into firm contact with the box; otherwise, a single locknut and bushing may be used. Threadless fittings for electrical metallic tubing shall be of a type approved for the conditions encountered. Additional support for horizontal runs is not required when EMT rests on steel stud cutouts.

3.2.1.7 Exposed Raceways

Exposed raceways shall be installed parallel or perpendicular to walls, structural members, or intersections of vertical planes and ceilings. Raceways under raised floors and above accessible ceilings shall be considered as exposed installations in accordance with NFPA 70 definitions.

3.2.1.8 Exposed Risers

Exposed risers in wire shafts of multistory buildings shall be supported by U-clamp hangers at each floor level, and at intervals not to exceed 10 feet.

3.2.2 Cables and Conductors

Installation shall conform to the requirements of NFPA 70. Covered, bare or insulated conductors of circuits rated over 600 volts shall not occupy the same equipment wiring enclosure, cable, or raceway with conductors of circuits rated 600 volts or less.

3.2.2.1 Sizing

Unless otherwise noted, all sizes are based on copper conductors and the insulation types indicated. Sizes shall be not less than indicated. Branch-circuit conductors shall be not smaller than No. 12 AWG. Conductors for branch circuits of 120 volts more than 100 feet long and of 277 volts more than 230 feet long, from panel to load center, shall be no smaller than No. 10 AWG. Class 1 remote control and signal circuit conductors shall be not less than No. 14 AWG. Class 2 remote control and signal circuit conductors shall be not less than No. 16 AWG. Class 3 low-energy, remote-control and signal circuits shall be not less than No. 22 AWG.

3.2.2.2 Conductor Identification and Tagging

Power, control, and signal circuit conductor identification shall be provided within each enclosure where a tap, splice, or termination is made. Where several feeders pass through a common pull box, the feeders shall be tagged to indicate clearly the electrical characteristics, circuit number, and panel designation. Phase conductors of low voltage power circuits shall be identified by color coding. Phase identification by a particular color shall be maintained continuously for the length of a circuit, including junctions.

a. Color coding shall be provided for service, feeder, branch, and ground conductors. Color shall be green for grounding conductors and white for neutrals; except where neutrals of more than one system are installed in the same raceway or box, other neutral shall be white with colored (not green) stripe. The color coding for 3-phase and single-phase low voltage systems shall be as follows:

120/208-volt, 3-phase: Black(A), red(B), and blue(C).
277/480-volt, 3-phase: Brown(A), orange(B), and yellow(C).
120/240-volt, 1-phase: Black and red.

- b. Conductor phase and voltage identification shall be made by color-coded insulation for all conductors smaller than No. 6 AWG. For conductors No. 6 AWG and larger, identification shall be made by color-coded insulation, or conductors with black insulation may be furnished and identified by the use of half-lapped bands of colored electrical tape wrapped around the insulation for a minimum of 3 inches of length near the end, or other method as submitted by the Contractor and approved by the Contracting Officer.
- c. Control and signal circuit conductor identification shall be made by color-coded insulated conductors, plastic-coated self-sticking printed markers, permanently attached stamped metal foil markers, or equivalent means as approved. Control circuit terminals of equipment shall be properly identified. Terminal and conductor identification shall match that shown on approved detail drawings. Hand lettering or marking is not acceptable.

3.3 BOXES AND SUPPORTS

Boxes shall be provided in the wiring or raceway systems where required by NFPA 70 for pulling of wires, making connections, and mounting of devices or fixtures. Pull boxes shall be furnished with screw-fastened covers. Indicated elevations are approximate, except where minimum mounting heights for hazardous areas are required by NFPA 70. Unless otherwise indicated, boxes for wall switches shall be mounted 48 inches above finished floors. Switch and outlet boxes located on opposite sides of fire rated walls shall be separated by a minimum horizontal distance of 24 inches. The total combined area of all box openings in fire rated walls shall not exceed 100 square inches per 100 square feet. Maximum box areas for individual boxes in fire rated walls vary with the manufacturer and shall not exceed the maximum specified for that box in UL Elec Const Dir. Only boxes listed in UL Elec Const Dir shall be used in fire rated walls.

3.3.1 Box Applications

Each box shall have not less than the volume required by NFPA 70 for number of conductors enclosed in box.

3.3.2 Brackets and Fasteners

Boxes and supports shall be fastened to wood with wood screws or screw-type

nails of equal holding strength, with bolts and metal expansion shields on concrete or brick, with toggle bolts on hollow masonry units, and with machine screw or welded studs on steel work. Threaded studs driven in by powder charge and provided with lockwashers and nuts, or nail-type nylon anchors may be used in lieu of expansion shields, or machine screws. Penetration of more than 1-1/2 inches into reinforced-concrete beams or more than 3/4 inch into reinforced-concrete joists shall avoid cutting any main reinforcing steel. The use of brackets which depend on gypsum wallboard or plasterboard for primary support will not be permitted. partitions of light steel construction, bar hangers with 1 inch long studs, mounted between metal wall studs or metal box mounting brackets shall be used to secure boxes to the building structure. When metal box mounting brackets are used, additional box support shall be provided on the side of the box opposite the brackets. This additional box support shall consist of a minimum 12 inch long section of wall stud, bracketed to the opposite side of the box and secured by two screws through the wallboard on each side of the stud. Metal screws may be used in lieu of the metal box mounting brackets.

3.3.3 Mounting in Walls, Ceilings, or Recessed Locations

In walls or ceilings of concrete, tile, or other non-combustible material, boxes shall be installed so that the edge of the box is not recessed more than 1/4 inch from the finished surface. Boxes mounted in combustible walls or ceiling material shall be mounted flush with the finished surface. The use of gypsum or plasterboard as a means of supporting boxes will not be permitted. Boxes installed for concealed wiring shall be provided with suitable extension rings or plaster covers, as required. The bottom of boxes installed in masonry-block walls for concealed wiring shall be mounted flush with the top of a block to minimize cutting of the blocks, and boxes shall be located horizontally to avoid cutting webs of block. Separate boxes shall be provided for flush or recessed fixtures when required by the fixture terminal operating temperature, and fixtures shall be readily removable for access to the boxes unless ceiling access panels are provided.

3.3.4 Installation in Overhead Spaces

In open overhead spaces, cast-metal boxes threaded to raceways need not be separately supported except where used for fixture support; cast-metal boxes having threadless connectors and sheet metal boxes shall be supported directly from the building structure or by bar hangers. Hangers shall not be fastened to or supported from joist bridging. Where bar hangers are used, the bar shall be attached to raceways on opposite sides of the box and the raceway shall be supported with an approved type fastener not more than 24 inches from the box.

3.4 RECEPTACLES

3.4.1 Single and Duplex, 15 or 20-ampere, 125 volt

Duplex receptacles shall be rated 20 amperes, 125 volts, two-pole, three-wire, grounding type with polarized parallel slots. Bodies shall be of ivory. Contact arrangement shall be such that contact is made on two

sides of an inserted blade. Receptacle shall be side- or back-wired with two screws per terminal. The third grounding pole shall be connected to the metal mounting yoke.

3.4.2 Receptacles, 20-Ampere, 250-Volt

Receptacles, single, 20-ampere, 250-volt, shall be ivorymolded plastic, two-pole, three-wire or three-pole, four-wire, grounding type complete with appropriate mating cord-grip plug.

3.5 PANELBOARDS AND LOADCENTERS

Circuit breakers and switches used as a motor disconnecting means shall be capable of being locked in the open position. Door locks shall be keyed alike. Nameplates shall be as approved. Directories shall be typed to indicate loads served by each circuit and mounted in a holder behind a clear protective covering. Busses shall be copper.

3.5.1 Loadcenters

Loadcenters shall be circuit breaker equipped.

3.5.2 Panelboards

Panelboards shall be circuit breaker or fusible switch equipped as indicated on the drawings.

3.6 FUSES

Equipment provided under this contract shall be provided with a complete set of properly rated fuses when the equipment manufacturer utilize fuses in the manufacture of the equipment, or if current-limiting fuses are required to be installed to limit the ampere-interrupting capacity of circuit breakers or equipment to less than the maximum available fault current at the location of the equipment to be installed. Fuses shall have a voltage rating of not less than the phase-to-phase circuit voltage, and shall have the time-current characteristics required for effective power system coordination.

3.7 MOTORS

Each motor shall conform to the hp and voltage ratings indicated, and shall have a service factor and other characteristics that are essential to the proper application and performance of the motors under conditions shown or specified. Three-phase motors for use on 3-phase 208-volt systems shall have a nameplate rating of 200 volts. Unless otherwise specified, all motors shall have open frames, and continuous-duty classification based on a 40 degree C ambient temperature reference. Polyphase motors shall be squirrel-cage type, having normal-starting-torque and low-starting-current characteristics, unless other characteristics are specified in other sections of these specifications or shown on contract drawings. The Contractor shall be responsible for selecting the actual horsepower ratings and other motor requirements necessary for the applications indicated. When electrically driven equipment furnished under other sections of these

specifications materially differs from the design, the Contractor shall make the necessary adjustments to the wiring, disconnect devices and branch-circuit protection to accommodate the equipment actually installed.

3.8 MOTOR CONTROL

Each motor or group of motors requiring a single control [and not controlled from a motor-control center] shall be provided under other sections of these specifications with a suitable controller and devices that will perform the functions as specified for the respective motors. Each motor of 1/8 hp or larger shall be provided with thermal-overload protection. Polyphase motors shall have overload protection in each ungrounded conductor. The overload-protection device shall be provided either integral with the motor or controller, or shall be mounted in a separate enclosure. Unless otherwise specified, the protective device shall be of the manually reset type. Single or double pole tumbler switches specifically designed for alternating-current operation only may be used as manual controllers for single-phase motors having a current rating not in excess of 80 percent of the switch rating. Automatic control devices such as thermostats, float or pressure switches may control the starting and stopping of motors directly, provided the devices used are designed for that purpose and have an adequate horsepower rating. When the automatic-control device does not have such a rating, a magnetic starter shall be used, with the automatic-control device actuating the pilot-control circuit. When combination manual and automatic control is specified and the automatic-control device operates the motor directly, a double-throw, three-position tumbler or rotary switch shall be provided for the manual control; when the automatic-control device actuates the pilot control circuit of a magnetic starter, the latter shall be provided with a three-position selector switch marked MANUAL-OFF-AUTOMATIC. Connections to the selector switch shall be such that only the normal automatic regulatory control devices will be bypassed when the switch is in the Manual position; all safety control devices, such as low- or high-pressure cutouts, high-temperature cutouts, and motor-overload protective devices, shall be connected in the motor-control circuit in both the Manual and the Automatic positions of the selector switch. Control circuit connections to any MANUAL-OFF-AUTOMATIC switch or to more than one automatic regulatory control device shall be made in accordance with wiring diagram approved by the Contracting Officer unless such diagram is included on the drawings. All controls shall be 120 volts or less unless otherwise indicated.

3.8.1 Contacts

Unless otherwise indicated, contacts in miscellaneous control devices such as float switches, pressure switches, and auxiliary relays shall have current and voltage ratings in accordance with NEMA ICS 2 for rating designation B300.

3.8.2 Safety Controls

Safety controls for boilers shall be connected to a 2-wire, 120 volt grounded circuit supplied from the associated boiler-equipment circuit. Where the boiler circuit is more than 120 volts to ground, safety controls shall be energized through a two-winding transformer having its 120 volt

secondary winding grounded. Overcurrent protection shall be provided in the ungrounded secondary conductor and shall be sized for the load encountered.

3.9 MOTOR-DISCONNECT MEANS

Each motor shall be provided with a disconnecting means when required by NFPA 70 even though not indicated. For single-phase motors, a single or double pole toggle switch, rated only for alternating current, will be acceptable for capacities less than 30 amperes, provided the ampere rating of the switch is at least 125 percent of the motor rating. Switches shall disconnect all ungrounded conductors.

3.10 EQUIPMENT CONNECTIONS

Wiring not furnished and installed under other sections of the specifications for the connection of electrical equipment as indicated on the drawings shall be furnished and installed under this section of the specifications. Connections shall comply with the applicable requirements of paragraph WIRING METHODS. Flexible conduits 6 feet or less in length shall be provided to all electrical equipment subject to periodic removal, vibration, or movement and for all motors. All motors shall be provided with separate grounding conductors. Liquid-tight conduits shall be used in damp or wet locations.

3.10.1 Motors and Motor Control

Motors, motor controls, and motor control centers shall be installed in accordance with NFPA 70, the manufacturer's recommendations, and as indicated. Wiring shall be extended to motors, motor controls, and motor control centers and terminated.

3.10.2 Installation of Boiler and A.C. Unit Equipment

Wiring shall be extended to the equipment and terminated.

3.11 PAINTING AND FINISHING

Field-applied paint on exposed surfaces shall be provided under Section 09900 PAINTING, GENERAL.

3.12 REPAIR OF EXISTING WORK

The work shall be carefully laid out in advance, and where cutting, channeling, chasing, or drilling of floors, walls, partitions, ceiling, or other surfaces is necessary for the proper installation, support, or anchorage of the conduit, raceways, or other electrical work, this work shall be carefully done, and any damage to building, piping, or equipment shall be repaired by skilled mechanics of the trades involved at no additional cost to the Government.

3.13 FIELD TESTING

Field testing shall be performed in the presence of the Contracting

Officer. The Contractor shall notify the Contracting Officer 14 days prior to conducting tests. The Contractor shall furnish all materials, labor, and equipment necessary to conduct field tests. The Contractor shall perform all tests and inspection recommended by the manufacturer unless specifically waived by the Contracting Officer. The Contractor shall maintain a written record of all tests which includes date, test performed, personnel involved, devices tested, serial number and name of test equipment, and test results. All field test reports will be signed and dated by the Contractor.

3.13.1 Safety

The Contractor shall provide and use safety devices such as rubber gloves, protective barriers, and danger signs to protect and warn personnel in the test vicinity. The Contractor shall replace any devices or equipment which are damaged due to improper test procedures or handling.

3.14 OPERATING TESTS

After the installation is completed, and at such time as the Contracting Officer may direct, the Contractor shall conduct operating tests for approval. The equipment shall be demonstrated to operate in accordance with the specified requirements. An operating test report shall be submitted in accordance with paragraph FIELD TEST REPORTS.

3.15 ACCEPTANCE

Final acceptance of the facility will not be given until the Contractor has successfully completed all tests and after all defects in installation, material or operation have been corrected.

-- End of Section --